

Proposed Acorn Valley Development – 83, Christie Drive, Dorchester, Ontario

Cyril J. Demeyere Limited (CJDL)
Preliminary report
Hydrogeology Study Report

April 5th, 2024
160-P-0019257-0-01-300-HD-R-0002-00



eNGLOBE

Cyri J. Demeyere Limited (CJDL)
160-P-0019257-0-01-300-HD-R-0002-00

Prepared by :



Francis Proteau-Bédard, M. Sc. A.

Project manager

Geoscience - Hydrogeology

Reviewed by :



Jean-Philippe Gobeil, P. Geo., M. Sc.

Hydrogeologist

Geoscience - Hydrogeology



Production Team

Cyril J. Demeyere Limited (CJDL)

Scientific Advisor	Mr. Deren Lyle, P. Eng.
--------------------	-------------------------

Englobe Corp.

Project manager	Francis Proteau-Bédard, M. Sc. A.
Reviewer	Jean-Philippe Gobeil, P., Geo., M. Sc.
Mapping/GIS	Rémi Careau
Publishing	Francine Néron

Registre des révisions et émissions

REVISION N°	DATE	MODIFICATION AND/OR PUBLICATION DETAILS
0A	May 29, 2020	Preliminary version published for comments
0B	October 3, 2023	Preliminary version published for comments
0C	February, 15 th , 2024	Preliminary version published for comments
00	April 5 th , 2024	Final

Distribution

1 original (PDF copy)	Mr. Deren Lyle, P. Eng. (dlyle@cjdleeng.com)
-----------------------	---

Property and Confidentiality

“This report can only be used for the purposes stated therein. Any use of the report must take into consideration the object and scope of the mandate by virtue of which the report was prepared, as well as the limitations and conditions specified therein and the state of scientific knowledge at the time the report was prepared. Englobe Corp. provides no warranty and makes no representations other than those expressly contained in the report.

This document is the work product of Englobe Corp. Any reproduction, distribution or adaptation, partial or total, is strictly forbidden without the prior written authorization of Englobe Corp. and its Client. For greater certainty, use of any and all extracts from the report is strictly forbidden without the written authorization of Englobe Corp. and its Client, given that the report must be read and considered in its entirety.

No information contained in this report can be used by any third party without the prior written authorization of Englobe Corp. and its Client. Englobe Corp. disclaims any responsibility or liability for any unauthorized reproduction, distribution, adaptation or use of the report.

If tests have been carried out, the results of these tests are valid only for the sample described in this report.

Englobe Corp.’s subcontractors who have carried out on-site or laboratory work are duly assessed according to the purchase procedure of our quality system. For further information, please contact your project manager.”

Table of Contents

1	Introduction	1
1.1	Objectives of the Study	1
1.2	Current and Proposed Land Use	2
1.3	Physical Setting of the Site	2
2	Hydrogeological Study Methodology	3
2.1	Review of Previous Studies and On-Line Databases	3
2.2	Hydraulic Conductivity Testing	4
2.2.1	Rising Head Tests	4
2.2.2	Grain Size Analysis	5
2.2.3	Guelph permeameter analysis	5
2.3	Groundwater and Surface Water Chemistry Sampling	5
3	Hydrogeological Investigation Results	6
3.1	Stratigraphy	6
3.2	Hydraulic Conductivity and Design Infiltration Rates	7
3.3	Groundwater Elevations, Flow Direction	8
3.4	Groundwater Chemistry	8
3.4.1	Groundwater quality	8
3.4.2	Nitrate.....	8
3.5	Pre-Development Water Balance	9
3.6	Post-Development Water Balance (No LID Measures)	10
3.7	Comments on LID measures	11
4	Dewatering assessment.....	12
4.1	Sanitary sewer construction	12
4.2	SWM pond	14
4.3	Permit to take water	14
5	Potential Impacts of Land Development.....	15
5.1	Water users	15
5.2	Sensitive Areas - Wetlands	16
5.3	Soil settlement	16
6	Conclusion	17
7	Statement of Limitations	18
8	References	19

TABLES

Table 1 :	Test pits location.....	5
Table 2 :	Boreholes, monitoring wells and mini piezometers locations.....	6
Table 3 :	Pre-Development Water Balance for the Site.....	10
Table 4 :	Post-Development Land use.....	10
Table 5 :	Post Development Water Balance for the Site	11

APPENDICES

Appendix A	Drawings
Appendix B	Borehole Logs
Appendix C	Figures
Appendix D	Tables
Appendix E	Hydraulic Conductivity Testing
Appendix F	Laboratory Certificate of Analysis
Appendix G	MECP Well Records and Well Survey Results (Summary)
Appendix H	Residential development and sewer plans
Appendix I	Water balance



1 Introduction

1.1 Objectives of the Study

Englobe Corp. (Englobe) was retained to carry out a hydrogeology study of the proposed residential Acorn Valley Development at 83 Christie Drive in Dorchester, Ontario (herein referred to as the Site or the property) as shown on the Location Plan, Drawing 1 in Appendix A. This work was authorized by Mr. Deren Lyle of Cyril J. Demeyere Ltd.

The scope of work for this hydrogeology study included a review of available topographic, geological and hydrogeological information for the Site and adjacent lands, and a subsurface investigation within the Site. The subsurface investigation was performed to identify the subsoil stratigraphy and hydrogeological properties, groundwater conditions and hydraulic gradients, and the relationship between groundwater and surface water features.

The objectives of this report are:

- To assess the geological and hydrogeological conditions beneath the Site;
- To calculate a pre- and post-development water balance;
- To describe the soil physical properties (including infiltration rates);
- To identify water users and sensitive areas within or near the Site;
- To provide an assessment of proposed Low Impact Development technique(s);
- Provide a preliminary dewatering assessment; and,
- To identify potential impacts of development.

Prior to this hydrogeology study, Englobe undertook a geotechnical investigation at the Site (Englobe project number 160-B-P0019257-0-01-100-GE-R-0001).

1.2 Current and Proposed Land Use

The Site is located in Dorchester, Municipality of Thames Centre, Middlesex County, Ontario (Drawings 1, and 2, Appendix A). The size of the Site is approximately 44 ha. The Site is currently used for agricultural purposes and is intended to be developed into a residential subdivision. The proposed development of the Site will be fully serviced with municipal sanitary sewers and water supply.

The Site is bounded by a variety of land uses including a Provincially Significant Wetland (Tamarack Swamp) to the immediate north, an existing subdivision to the east, woodland and rural residential to the west and agricultural and woodland to the south. Recent environmental studies also identified an additional wetland area is located on the southwestern border of the site.

In addition to the wetlands, surface water features are also present in/near the west-central portion of the Site (the Shaw Drain) and in the southeastern portion of the Site (Rath Harris Drain). The existing subdivision to the east of the Site is serviced with private wells and septic systems.

1.3 Physical Setting of the Site

The Site is situated within the Upper Thames River Watershed (major unit) and more specifically within the Dorchester Corridor. Surface drainage at the Site varies in direction due to the presence of an elevated area in the northeastern portion of the Site and three locally elevated areas in the vicinity of the southern Site boundary. The irregular topography results in drainage, at least locally, to all three surrounding surface water bodies.

The Site is located in a spillway between the Ingersoll Moraine to the south and the Dorchester Moraine to the north (i.e., northern limit of the Mount Elgin Physiographic Region; Chapman and Putnam, 1984). Geological mapping of the area shows surficial deposits in the area of the Site to be glaciolacustrine deposits of sand to sand and gravel. Geological mapping of the area indicates that bedrock beneath the Site is the limestone and dolostone of the Dundee Formation.

Water Well Records (WWRs) for the vicinity of the Site are summarized in Appendix G and indicate that sand, or at least sand with silt, is the predominant shallow soil type and is the local water supply aquifer.

The WWRs indicate that groundwater is used locally as a source of potable water. A municipal well is in the WWR survey and most rural resident seem to use private wells.

There is one Permits to Take Water (PTTWs) on file within 1 km of the Site. The PTTW is for the irrigation of a golf course located northwest of the Site. The Site is located within a Significant Groundwater Recharge Area and is the location of a Highly Vulnerable Aquifer. There are also two registrations on the Environmental Activity and Sector Registry (EASR) for construction dewatering at properties located east of the Site. Both registrations are expired.

Map 3-2 of T-S&RSPC, 2015 indicates that annual precipitation at the Site is approximately 1,028 mm/yr. Map 3-3 of T-S&RSPC, 2015 indicates that evapotranspiration at the Site is approximately 586 mm/yr. Map 3-4 of T-S&RSPC, 2015 indicates that groundwater recharge (i.e., infiltration) at the Site could range from 325 mm/yr in the northern and northeastern portions of the Site and approximately 125 mm/yr elsewhere.

The MNRF's Natural Heritage Areas website recognizes the Tamarack Swamp as a Provincially Significant Wetland and recognizes the woodlands along portions of the northern, western and southern boundaries of the Site. Schedule C, Natural Heritage Areas, of the Official Plan of Middlesex County designates the woodlands as Significant Woodlands. Appendix 1 (Part A), Natural Heritage Features, of the Official Plan of the Municipality of Thames Centre designates the larger woodlands in the vicinity of the Site as Significant Woodlands (> 4 hectares in area) and recognizes the Provincially Significant Wetland north of the Site.



2 Hydrogeological Study Methodology

The study methodology involved a number of tasks, which included :

- Reviewing topographic, geological, and hydrogeological mapping and reports for the area;
- Reviewing relevant on-line databases;
- Developing and then performing in situ permeability tests in the monitoring wells installed during the geotechnical investigation to determine hydraulic conductivity values;
- Analyzing grain size distribution data for selected soil samples to validate hydraulic conductivity magnitudes;
- Measuring groundwater levels in all monitoring wells to establish the flow direction and horizontal gradient;
- Collecting groundwater samples from monitoring wells and surface water samples for laboratory analysis for the parameters listed in the Municipality of Thames Centre's By-law No. 641-14 (sewer use by-law); and,
- Analyzing the data and preparing this report.

2.1 Review of Previous Studies and On-Line Databases

The only previous study consulted by Englobe for the Site consisted of a geotechnical investigation by Englobe (Englobe project number 160-B-0020770-1-GE-R-0001-0A dated May 27, 2019. The borehole/monitoring well logs, survey data and grain size distribution from that investigation have been incorporated, where applicable, into this report. Copies of the borehole logs are included in Appendix B.

Online databases used in the preparation of this report are cited in the References section. The findings of the database searches are summarized in Section 1.3, Physical Setting of the Site.

2.2 Hydraulic Conductivity Testing

Hydraulic conductivity estimates for the soils were determined using three methods. The first method consists of in situ permeability tests using a slug. This method is applicable to saturated soils at the well filter pack elevation.

The second method involved a calculated estimate of hydraulic conductivity based on soil sample particle size analysis using the multiple equations to a given sample as provided in Devlin, 2015. The results consist of a geometric mean of the values calculated using applicable equations. This method is valid for saturated and unsaturated soils.

The last method is an interpretation based on Guelph permeameter testing. This method is meant to evaluate percolation rates in unsaturated soils.

2.2.1 Rising Head Tests

Hydraulic conductivity estimates were determined for the saturated soils at depth using tests in three monitoring wells installed at the Site.

Each monitoring well was developed prior to the permeability tests. Well purging through the use of dedicated inertial lift (“Waterra”) pumps and polyethylene tubing was implemented to remove silt and sand introduced into the well during construction, and to remove fine particles from the coarse sand pack placed around the outside of the well screen during construction.

The slug test procedure entails measuring/timing water level recovery following the removal of a known volume from a monitoring well and the use of the theory of Hvorslev (1951). Hvorslev's method is expressed by the following equation:

$$K = \frac{r^2 \ln(L/R)}{2LT_0}$$

Where :

K	=	Hydraulic conductivity of the tested material (m/sec)
r	=	Inner radius of the well riser pipe (m)
R	=	Outer radius of the borehole (m)
L	=	Length of saturated screen and, if applicable, sand pack (m)
T ₀	=	Time lag (sec), where (H-h)/(H-H ₀) = 0.37
h	=	Water level at each time of measurement (m)
H ₀	=	Initial water level (m, start of test)
H	=	Static water level prior to test (m)

The time lag, T₀, is defined as the time required for the water level to recover to 63 % of the static level. This time lag is determined graphically as the time for which (H-h) divided by (H-H₀) is equal to 0.37.

Slug test data was analyzed using AquiferTest 10.0. The graphed results of the slug tests tests completed for the monitoring wells are included in Appendix E and in the summary of the hydraulic conductivity estimates in Table 102, Appendix D.

It should be noted that the analyses assume fully penetrating conditions because the thickness of the aquifer is not presently known. Testing with greater assumed thicknesses resulted in minor decreases in hydraulic conductivity. As the in situ tests permeability tests are to be used in the dewatering rates evaluation and not in percolation assessment, it is considered to be a conservative assessment.

2.2.2 Grain Size Analysis

Hydraulic conductivity values of nine soil samples were derived empirically using the particle size distribution data included in Appendix E and the applicable formulae provided in Devlin, 2015. These results are included in Table 102, Appendix D.

2.2.3 Guelph permeameter analysis

The Guelph Permeameter is a portable instrument using the same operating principle as a laboratory permeameter. A cylinder of known diameter, open at the bottom, is set into the soil interval to be tested and, as water leaks from the base, water is added to the cylinder from a graduated reservoir. Water is allowed to leak from the base of the cylinder until the flow rate stabilizes at which point the flow rate is recorded. The flow rate, cylinder/reservoir sizing and soil type is used to estimate hydraulic conductivity and subsequently the associated infiltration rate. Data were then treated on an excel spreadsheet published by Soilmoisture.

Table 1 presents the location of the test pits. The easting and northing values are referenced to Universal Trans Mercator North American Datum of 1983 (UTM NAD83, zone 17N) coordinates.

Table 1 : Test pits location

Test pit name	Easting (m)	Northing (m)
TP01-20	493972	4758450
TP02-20	494247	4758497
TP03-20	494473	4758350
TP04-20	494143	4758263
TP05-20	494078	4758664
TP06-20	493824	4758659

2.3 Groundwater and Surface Water Chemistry Sampling

Groundwater samples were obtained from three selected on-site monitoring wells on January 31, 2020 using the low flow sampling technique. Samples to be analyzed for metals were not field filtered. The samples were placed in coolers on ice packs and transported to ALS Laboratories in London, Ontario (ALS), under continuous Chain of Custody documentation, for analysis of the parameters listed in the Municipality of Thames Centre's By-law No. 641-14 (sewer use by-law). ALS Laboratories is accredited by the Canadian Association for Laboratory Accreditation.

Analytical results for the groundwater samples are summarized in the appended Table 103 with comparison to the applicable sanitary and storm sewer use criteria. A copy of the laboratory Certificate of Analysis is included in Appendix F.



3 Hydrogeological Investigation Results

3.1 Stratigraphy

Fourteen (14) boreholes have been completed during Englobe geotechnical study. Six of these boreholes have then been converted into monitoring wells. Five (5) additional mini piezometers were also added during the hydrogeological study to sample additional areas next to wetlands. Table 2 presents the location of the boreholes and the mini piezometers. The easting and northing values are referenced to Universal Transverse Mercator North American Datum of 1983 (UTM NAD83, zone 17N) coordinates.

Table 2 : Boreholes, monitoring wells and mini piezometers locations

Borehole, wells or mini piezometer ID	Easting (m)	Northing (m)
BH01-19	493813	4758802
BH02-19	493967	4758691
MW03-19	494189	4758756
MW04-19	493813	4758609
MW05-19	494078	4758532
BH06-19	494319	4758587
BH07-19	493859	4758411
MW08-19	493908	4758277

Table 2 : Boreholes, monitoring wells and mini piezometers locations (suite)

Borehole, wells or mini piezometer ID	Easting (m)	Northing (m)
BH09-19	494038	4758390
MW10-19	494386	4758447
BH11-19	494587	4758396
BH12-19	494551	4758258
BH13-19	494392	4758195
MW14-19	493813	4758802
MP01-20	493871	4758800
MP02-20	494064	4758742
MP03-20	493815	4758475
MP04-20	494596	4758258
MP05-20	493671	4758283

The stratigraphy encountered within the depth of investigation consisted of 0.2 to 0.5 m of topsoil over sand with a variable silt content unit. An exception is noted at BH12-19, southeast of the proposed development area, where the top layer is a 2 m of peat. No other geological unit has been observed beneath this aquifer in the boreholes made by Englobe for this project.

Local Water Well records (WWRs) indicate that the sand aquifer is underlain by clay at depths ranging from 20 to 55 mBGS and that the clay extends to bedrock at depths ranging from 34 to 74 m.

3.2 Hydraulic Conductivity and Design Infiltration Rates

Discussion and test results provided herein are focused on the portion of the Site that is to be developed. Grain size analyses, in-situ permeability testing and Guelph permeameter testing have been performed on the site. Hydraulic conductivity estimates determined by all testing methods are summarized in Table 102 in Appendix D, with graphical analyses of rising head tests. Grain size distribution data included in Appendix C.

As indicated in Table 102 in Appendix D, the hydraulic conductivity of the on-Site shallow, unsaturated soil ranged from 1.7×10^{-10} m/s to 1.7×10^{-4} m/s for the grain size analysis, with a geometric mean of 3.3×10^{-6} m/s. Guelph permeameter hydraulic conductivities ranged from 1.9×10^{-7} m/s to 2.4×10^{-4} m/s for the grain size analysis, with a geometric mean of 4.3×10^{-5} m/s. Both methods were used to calculate infiltration rates ranging from 1.3 to 57.3 mm/hr (geometric mean 27.8 mm/hr) based on a safety correction factor of 3.5 (inhomogeneous soil) for soil types encountered over the depth interval of interest, as referenced from the Credit Valley Conservation's "Low Impact Development Stormwater Management Planning and Design Guide" (CVC, 2010). Englobe also note that Guelph permeameter values are more reliable for the evaluation of the infiltration rates, ranging from 8.4 to 57.3 mm/hr and a geometric mean of 36.1 mm/hr. If these results are used for design purpose, location of the test pit and depth of analysis should be considered.

Hydraulic conductivity values for the on-Site saturated soil ranged from 1.2×10^{-5} m/s to 1.3×10^{-4} m/s with a geometric mean of 3.9×10^{-5} m/s.

3.3 Groundwater Elevations, Flow Direction

Table 101, Appendix D, summarizes groundwater and surface water measurements across the Site on multiple surveys. The shallow water table occurs in sand unit. On April 29, 2020, groundwater elevations in the proposed development area of the Site ranged from 251.84 mASL in MW03-19 in the northeastern portion of the Site to 259.98 mASL in MW-14-19 in the south portion (Drawing 2 of appendix A). The horizontal hydraulic gradient of the overall Site is approximately 0.02 northeast.

3.4 Groundwater Chemistry

3.4.1 Groundwater quality

Samples of groundwater were obtained from wells MW-03-19, MW-08-19, MW-10-19, MP-01-19, MP-04-19 and MP-05-19 on January 31, 2020. The results for the tested parameters were compared to the applicable storm and sanitary sewer use criteria provided in the Municipality of Thames Centre's By-law No. 07-18 (sewer use by-law) due to the possible need for construction dewatering during development. In addition, due to the presence of Shaw drain on-Site, the results are also compared to the Provincial Water Quality Objectives (PWQOs), which are applicable to surface water. All samples, except MW-03-19 have an absolute error on ionic balance under 10 %. The MW-03-19 has an error of +11 % on its ionic balance. The results are still discussed in the analysis, but a possible bias must be considered.

There were no exceedances of the criteria for discharge to the sanitary sewer systems. The PWQO limits were exceeded for three parameters. The concentration of zinc in samples collected from MW-03-19, MW-05-19, and MW-08-19 of 0.195, 0.07 and 0.616 mg/L, respectively, exceeded its PWQO of 0.030 mg/L. The concentration of phosphorus in the sample collected from MW-05-19, 0.034 mg/L, exceeded its PWQO of 0.030 mg/L. The concentration of iron in the sample collected from MW-04-19, 0.838 mg/L, exceeded its PWQO of 0.3 mg/L.

Based on the analytical results obtained during groundwater sampling, it is recommended that suspended solids removal is implemented using a combination of silt removing bags and settling ponds prior to discharging to the environment if the discharge of groundwater to surface water outlets is considered. Additional groundwater sampling should be performed in the settling ponds prior to discharging the water to the environment. At a minimum, monitoring of turbidity and suspended solids in surface water should also be conducted in surface water bodies upstream, at, and downstream of the discharge points.

Chemistry representation on a Piper diagram indicate that samples are Ca-HCO₃ water types. This water type is generally associated with recharge water or groundwater with a short residence time. Results are also compared to the PGMN 487-2 well (Drawing 3 of appendix A). Both wells are in the same fluvioglacial sediments and have a similar water type. Results from the PGMN well indicate higher sodium and chloride contents and lower calcium contents. An anthropic contamination is evaluated as the cause of this difference. The well is located next to a street, the aquifer sampled is shallow and located next to the surface and the sampling surveys occurred at the beginning of winter.

3.4.2 Nitrate

Nitrate was identified as a potential concern in scoping session with Upper Thames River Conservation Authority. High nitrate loads caused by the existing residential development were anticipated on the eastern end of the site. High nitrate content in groundwater is identified as a contamination risk for the wetland areas.

High nitrate contents were observed across the site for MW-03-19, MW-08-19 and MW-10-19. Low contents were observed in MP-01-19 and MP-04-19, located on the border of the site. This indicates that activities on the site could be the cause for high nitrate concentrations in groundwater. The use of fertilizer for agricultural purposes is considered the most plausible source. However, the actual nitrate contamination is not expected to be a persistent concern for future groundwater quality if the source is neutralized.

Also, Englobe notes that the neighbouring residential development is located downgradient of the site. Therefore, nitrate contamination from the neighbouring development is unlikely, as the contamination is anticipated to migrate away from the site area based on the groundwater flow direction.

The residential development project would change the purpose of the site, from agricultural to residential. This change of land use is anticipated to lower the nitrate contamination in groundwater.

3.5 Pre-Development Water Balance

The water balance discussed herein addresses only that portion of the Site proposed for development and where LID measures will be required. The focus of this water balance assessment is (i) to determine the infiltration deficit (reduction in current contribution to baseflow) resulting from the proposed development and (ii) to indicate recommendations for the LID methods and the parameters for the design.

The water balance accounts for all water in- and out-flows in the hydrologic cycle. Precipitation (P) falls as rain and snow. Then it can run off towards wetlands, ponds, lakes, and streams (R), infiltrate to the groundwater table (I), or evaporate from surface water and vegetation (ET). When long-term average values of P, R, I and ET are used then minimal or no net change to groundwater storage (ΔS) is assumed.

The annual water balance can be stated as :

$$P = ET + R + I + \Delta S$$

Where :

P	=	Precipitation (mm/year)
ET	=	Evapotranspiration (mm/year)
R	=	Runoff (mm/year)
I	=	Infiltration (mm/year)
ΔS	=	Change in groundwater storage (taken as zero) (mm/year)

The average annual precipitation for the site is taken as 1011.5 mm/year, corresponding to the climate normal of the London International Airport weather station (Government of Canada, 2019). This rate is used as the input for the water balance calculation.

The Thornthwaite and Mather (1957) method has been used to evaluate the potential evapotranspiration (PET). Climatic data used for the PET calculation were taken from the London weather station (Government of Canada, 2019). The resulting PET is 598 mm/yr. As a result, the combined infiltration and runoff components of the water budget are 413.5 mm/yr.

Localized infiltration rates vary based on factors such as the saturated hydraulic conductivity of surface soils, land slope, rainfall intensity, relative soil moisture at the start of a rainfall event, and type of cover of the ground surface. MOE (1995) summarizes all these elements into infiltration rates factor to evaluate the proportion of the infiltration and the runoff. This factor is separated into three parts: slope, surficial soil and land use.

The slope across the Site is over the range of a Rolling Land definition, but under the hilly definition (Table 2, Chapter 4 of MOE, 1995). As a result, the infiltration factor of 0.20 is used.

Surficial soil at the site is typically sand. Therefore, the infiltration factor used for this type of soil is the one of the sandy loam, lowered to acknowledge the smaller particle size of the sand (0.30) from Table 2, Chapter 4 of MOE 1995.

The land is largely open field. An infiltration factor of 0.1 has been used, based on Table 2, Chapter 4 of MOE, 1995.

The combined infiltration factor is 0.6. With an available water surplus of 413.5 mm/year, this results in an average infiltration rate of 248.0 mm/yr. This is within the range given in Table 3, Chapter 4 of MOE, 1995 for medium to coarse sand. This associated type of soil seems to be slightly coarser, Therefore, the recharge could be overestimated, but this value will be used as a conservative approach. The values of the water balance calculation are presented in Table 3, below.

Table 3 : Pre-Development Water Balance for the Site

Hydrologic Component	Site (mm/year)	%
Total Precipitation	1 011.5	100.0
Evapotranspiration	598.2	59.1
Infiltration	248.0	22.5
Runoff	165.3	18.4

3.6 Post-Development Water Balance (No LID Measures)

Post-development water balance is calculated for the developed part of the site. Future development areas are not considered and would need to be updated when the development plans are known.

Cyril J. Demeyere has evaluated the following impervious coverage of the site :

Table 4 : Post-Development Land use

Land use	Total area (m ²)	Impervious surface cover (%)	Impervious surface cover (m ²)
Medium density residential	11 400	75	8 550
High density residential	39 200	85	33 320
Freehold lots	103 600	65	67 340
SWM pond	15 300	100	15 300
Streets and walkway	37 800	100	37 800
Open channel, archaeological site, parks and open space	49 300	0	0
Total	256 600	---	162 310

For conservative purposes, it will be considered that the impervious surfaces will create 100 % runoff on their surface. On other surfaces, PET, runoff and infiltration will keep the same proportions as the predeveloped land.

The development of impervious structures also increases the amount of stormwater runoff across the Site. The pre-development runoff is estimated to be 42 416 m³/year out of the total precipitation of 259 551 m³/year. Post-development runoff without the development of LID measures could increase runoff to 179 763,904 m³/year, or 69.3 % of precipitation. Appendix I and Table 5, below, summarize the post-development water balance for the Site without LID measures being implemented.

Table 5 : Post Development Water Balance for the Site

Hydrologic Component	Pre-Development		Post Development (No LID Measures)	
	Site (m ³ /year)	%	Site (m ³ /year)	%
Total Precipitation	259 551	100.0	259 551	100
Evapotranspiration	153 498	59.1	56 404	21.7
Infiltration	63 637	24.5	23 384	9,0
Runoff	42 416	16.3	179 763	69,3

3.7 Comments on LID measures

Based on post development water balance calculations presented in the previous section, a loss of 40,253 m³ is anticipated annually if no LID measures are implemented. The structure currently planned to mitigate the infiltration loss is an open channel located on the northern side of Christie Drive. This channel could be used as an infiltration trench. In order to promote infiltration, the open channel design should consider including features promoting some retention to slow down runoff and allow time for infiltration. The high infiltration rates from Guelph permeameter testing indicate that this method could be considered for the site conditions given that shallow soils at the site have a good infiltration potential. In effect, the calculated infiltration rates discussed in section 3.2 suggest the open channel has the potential to infiltrate a sufficient volume to compensate for the anticipated loss in infiltration related to the development if water is allowed to pool and infiltrate. The feasibility and design for infiltration should nevertheless be designed and confirmed by a qualified professional.

It should also be noted that besides the quantity of infiltration to be augmented by the LID measures, the quality of the runoff water to be infiltrated should be kept as the highest priority. In effect, infiltrating poor quality water, for example water with a high salt content originating from road salt, could potentially prove more detrimental to nearby wetlands and well users than a localized marginal loss of infiltration. Water directed to the LID structures should therefore not originate from areas where significant risks of contamination are anticipated.

According to the overall groundwater flow direction, most of the infiltration from the channel would reach Tamarack Swamp. Modifications to the groundwater flow to the wetland area could affect some species that are vulnerable to groundwater level changes or the difference of groundwater discharge in the land slope to the swamp. Good groundwater quality would also need to be maintained, as contaminated water could impact the wetlands. Therefore, in addition to the LID, it is recommended to implement a post development groundwater level monitoring plan.



4 Dewatering assessment

4.1 Sanitary sewer construction

It is Engobe's understanding that residential structures will not be built under or near the water table, taking into consideration spring high water level conditions. The calculated hydraulic conductivities indicate that construction under the water table, if considered, would require significant drainage that is not adapted for conventional houses.

Sanitary sewer construction is planned to be the deepest construction under the water table level. In addition, some sections of the sewer will also be located in areas where the greatest hydraulic conductivity was calculated, therefore the construction of the sanitary sewer has the potential of generating the greatest construction dewatering rates for the proposed development. A dewatering study is therefore needed on this part of the construction planning. The Thiem Equation for unconfined flow into a long excavation (Powers et al., 2007) was used to estimate lateral flow into the excavation. Please note that desktop calculations do not consider vertical flow from the bottom of the excavation (upwelling of groundwater). Further, the values calculated are for steady state dewatering rates and transient, initial dewatering rates could be up to 4 times higher than the steady state dewatering in order to remove groundwater from storage within the surrounding soils. The following assumptions were made for the dewatering calculations:

- Construction dewatering is assumed to be completed in segments. A typical 30 m segment has been used for calculation.
- Steady state unconfined flow conditions are occurring;
- The drawdown required for the sewers construction varies on the site. For conservative assumption, required drawdown was evaluated at every location presented on drawing 3 of Appendix A. The sector with the largest drawdown was used for the dewatering assessment, as it is the most restrictive for construction planning and for PPTW application. The largest distance between the water table and the bottom of excavation was evaluated at location 1 at a distance of approximately 8,66 m.

- Water levels from the April 2020 survey are retained for the dewatering assessment. These water levels are considered to represent a high-water table condition. An additional 0,30 m has been added to the water level to represent a higher water table occurrence;
- The maximum dewatering target depths were assumed to be 0,5 m below the projected trunk sewer to ensure a dry excavation base for the pipe placement;
- The K-value used for the dewatering calculation for the sand is the in-situ result from MW-04-19, as it is the closest to the evaluated dewatering location;
- Clay aquitard elevation has not been observed in boreholes. As mentioned in section 1.3, the range for the aquitard is between 20 and 55m mBGS. However, these values don't correspond to the thickness of the aquifer. Thiem equation suppose an aquifer completely screened and mostly horizontal flow. Therefore, the thickness of the aquifer is considered to be equal to the bottom of the excavation and an additional 2 m for a conservative assessment. This thickness in the calculation is noted as active dewatering thickness.

Dewatering assessment consider that the trenches would have a width of 10 m. This assumption is only for dewatering assumption. Please refer to the geotechnical study for the excavation design recommendations.

Unconfined flow into a long excavation is calculated with the following equation

$$Q = \frac{\pi K(H^2 - h^2)}{\ln R_0/r_s} + 2 \left[\frac{xK(H^2 - h^2)}{2L} \right]$$

where:

- Q = Construction dewatering rate (m³/sec)
- K = Hydraulic conductivity (m/sec)
- H = Hydraulic charge of water in aquifer (static head) prior to dewatering
- h = Hydraulic charge of the water during dewatering
- R₀ = Area of influence of construction dewatering/pumping = 3000*(H-h)*K^{0.5}
- r_s = Equivalent well radius of well = (area of excavation)^{0.5} / π
- x = Length of the trench = 100 m
- L = R₀/2 (m)
- π = Pi = 3.14159

Drawing 3 of Appendix A presents the location of the sewers on the Site. The undeveloped portions have not been considered in the dewatering evaluation.

Based on the assumptions noted above, the proposed steady-state water taking would be approximately 1 102 700 L/day for a 30 m x 10 m trench. Dewatering design should be made for larger flow than the flow presented in this report. Transient flow state during the drawdown, variations in soil and groundwater conditions beyond those encountered during the geotechnical and hydrogeological investigations, and any other unforeseen events that may contribute to increased dewatering requirements.

4.2 SWM pond

January 2024 stormwater management report indicate the SWM pond would have permanent pool at elevation 254,5 m ASL and its bottom would be at elevation 253,0 m. The water table would be higher than both elevations. This situation could cause hydrostatic pressure under the pond since no drainage layers are identified in the drawings. This would also suggest that an impervious liner would be required to prevent the pond from acting like a drain if significant seepage occurred. The thickness and properties of the liner should be defined by the design engineer. Englobe would require a confirmation from the SWM pond designer to ensure that the concept is still maintained.

SWM pond construction would require dewatering for its construction, as it reaches lower than the groundwater level. Dewatering assumptions are similar to those of section 4.1, with the following differences:

- The whole pond is expected cover an area of 260 x 80 m
- The base of the excavation is expected to reach an elevation of 253,00 m.
- The drawdown required for the pond construction is based on March 2020 water level from MW-10-19. With the addition of 0.30 m for seasonal variations, the water level is 253.53 m.
- The maximum dewatering target depths were assumed to be 0,5 m below the projected trunk sewer to ensure a dry excavation base for the pipe placement;
- The K-value used for the dewatering calculation (1.2×10^{-5} m/s) for the sand is the in-situ result from MW-10-19, as it is the closest monitoring well to the evaluated dewatering location;

Based on the assumptions noted above, the proposed steady-state water taking would be approximately 240 300 L/day for the whole pond. Dewatering design should be made for larger flow than the flow presented in this report. Transient flow state during the drawdown, variations in soil and groundwater conditions beyond those encountered during the geotechnical and hydrogeological investigations, and any other unforeseen events that may contribute to increased dewatering requirements.

4.3 Permit to take water

Based on our calculations, the estimated dewatering rate will be over 400 000L/day. Based on these assumptions, it is recommended that a Category 3 Permit to Take Water (PTTW) application is submitted for this project.



5 Potential Impacts of Land Development

5.1 Water users

Well Records from the Ministry of the Environment and Climate Change (MOECC) Water Well Record (WWR) Database were reviewed to determine the number of private supply wells present within a 500 m radius of the limits of the property. A total of 104 wells were reported by the MOECC; 25 of these wells have been either abandoned or are wells identified as monitoring wells, test holes, not in use.

According to the MOECC WWR database, the remaining 79 wells are unlisted (considered for domestic use), listed for domestic use, listed as commercial use or listed as municipal supply. These considered wells are plotted on the appended Drawing 3 in Appendix A. These wells are identified in Table 6 and are referenced to Universal Trans Mercator North American Datum of 1983 (UTM NAD83, zone 17N) coordinates. However, Englobe notes that some wells are located in the woodland and in the wetland areas, probably due to a lack of precision in the well location coordinates provided in the WWRs, suggesting that the actual well locations remain unknown. Validation should be made with the land owners.

Prior to dewatering, residents that are serviced by private wells within the area of influence of the selected scenario should be contacted in writing to notify them of the upcoming water takings and, on a voluntary basis, fill a survey regarding the location, construction details and current condition of their well with respect to water quantity and quality. The contractor must be prepared to address complaints promptly and provide water totes should any of the households be negatively impacted by the water takings.

It is noted that the wells plotted on Drawing 3 in Appendix A, may not be plotted in their precise location; however, the MOECC WWR coordinate data has been used in the absence of more reliable information. A summary of the Water Well Records is included in Appendix G.

5.2 Sensitive Areas - Wetlands

As mentioned in section 1.2, the Site is bounded by the Tamarack Swamp. According to the groundwater flow direction, a part of the recharge from the Site goes through these wetlands. Therefore, a decrease in recharge could affect the wetland water balance.

Due to the steep difference in topography between the residential development site and the wetlands area, a part of the water input to the wetland could be from the groundwater discharge in the slope in the north of the development. A difference in the overall water balance of the site could then affect the groundwater flow to the wetlands. It is therefore recommended to maintain the pre-development water balance.

This increases the importance of a proper LID method planning. By developing the Site with LID stormwater structures, it is anticipated that infiltration into the shallow groundwater system could be maintained. The LID method should also include considerations for groundwater quality. Implementation of LID structures, including surface bioretention cells, could allow for additional filtration of the typical contaminants (sediment) carried with stormwater. Additional recommendations could also be provided to the population to ensure the awareness for environmental considerations. In effect, some recommendations could be made regarding the use of chemicals such as fertilizers, herbicides, pesticides and salts or with respect to the location of the discharge of swimming pool water, for example.

For the wetland on the southwestern corner of the site, the long-term hydrogeological impact from the site is not expected to be significant. This wetland area is on the upgradient of the site and seems to be recharged from outside the residential development area.

5.3 Soil settlement

Groundwater drawdown can cause soil settlement. Soil settlement could cause stress on existing structures. Its impact should be evaluated by a geotechnical engineer prior to dewatering activities and settlement monitoring should be conducted during construction if warranted.



6 Conclusion

The hydrogeological study conducted by Englobe has provided information about the subsurface stratigraphy across the Site. The subsurface stratigraphy across the Site is mainly sand with variable content of silt overlying clayey silt/silty clay. The shallow water table is present in the sand unit.

Maximum groundwater elevations to date (April 29th, 2020) in the proposed development area of the Site range from 251.84 mASL in MW03-19 in the northeastern portions of the Site to 259.98 mASL in MW-14-19 in the south portion of the Site. Groundwater flow across the Site is to the north towards the wetlands.

There was no exceedance of the sanitary sewer use criteria. However, three parameters exceeded the PWQO criteria. Zinc (0.07 mg/L as opposed to a PWQO of 0.03 mg/L) and phosphorus (0.034 mg/L as opposed to a PWQO of 0.03 mg/L) are exceeded at MW-05-19. Iron (0.838 mg/L as opposed to a PWQO of 0.3 mg/L) is exceeded at MW-04-19.

Water balance calculations indicate that the proposed development, without LID measures, will increase the amount of runoff and decrease the amount of infiltration. The potential infiltration deficit is estimated at 40 253 m³/yr for the developed portion of the site. Englobe's calculations indicate that additional LID methods should be implemented on the upgradient of the wetland area to maintain the pre-development groundwater flow to the wetland area on the northern end.

It is expected that the construction of the sewers and other structures will require authorization for dewatering. The high hydraulic conductivity and the shallow water table in some area of the site indicate that significant groundwater discharge is to be expected. Land developer should expect the need for a category 3 PTTW.

Multiple wells have been identified in the area of influence of the dewatering. The developer should plan monitoring and communicating with potentially impacted well owners. Impacts on the wetlands could be significant due to the change in water balance of the site. The implementation of LID methods during the construction planning is highly recommended to reduce the impacts. The LID methods should maintain a quantity and quality of water that is similar to the pre-development state. Potential soil settlement concerns should also need to be addressed.



7 Statement of Limitations

The hydrogeology recommendations provided in this report are applicable only to the project described in the text and are intended for the use of the project designer. Any use which a contractor makes of this report, or decisions made based on it, are the responsibility of the contractor. The contractor must also accept the responsibility for means and methods of construction, seek additional information if required, and draw their own conclusions as to how the subsurface conditions may affect their work. Englobe accepts no responsibility and denies any liability whatsoever for any damages arising from improper or unauthorized use of the report or parts thereof.

It is important to note that this investigation involves a limited sampling of the Site gathered at specific test hole locations, and the conclusions in this report are based on this information gathered. The subsurface conditions between and beyond the boreholes may differ from those encountered at the boreholes. Should subsurface conditions be encountered which differ materially from those indicated in the borehole logs, we request that we be notified in order to assess the additional information and determine whether or not changes should be made as a result of the conditions.

Additionally, much of the information and conclusions presented in this report have been based on, and taken from, data and reports collected and prepared by other consultants. Englobe is not responsible for any errors or omissions in these third-party reports.

The professional services provided for this project include only the hydrogeological aspects of the subsurface conditions at the Site, unless otherwise stated specifically in the report. The recommendations and opinions given in this report are based on our professional judgment and are for the guidance of the Client and Consultant in the design of the specific project. No other warranties or guarantees, expressed or implied, are made.

We trust that this report is suitable for your present requirements and we thank Cyril J Demeyere Ltd. Properties Inc. for this opportunity to have provided hydrogeological services. If you have any questions or require further hydrogeological or geotechnical consultation, please do not hesitate to contact our office.



8 References

- Bouwer, H., 1989. *The Bouwer and Rice Slug Test - an Update*. Groundwater vol. 27, no. 3, pp. 304-309.
- Chapman, L.J., Putnam, D.F. 1984. The Physiography of Southern Ontario. 3rd ed. Ontario Geological Survey Special Volume 2, Ontario Ministry of Natural Resources, Ontario, Canada.
- Credit Valley Conservation. 2010. Low Impact Development Stormwater Management Planning and Design Guide. Version 1.0.
- Devlin, J.F. 2015. HydrogeoSieveXL: an Excel-based tool to estimate hydraulic conductivity from grain-size analysis. Hydrogeology Journal (spreadsheet version 2.2., Sept. 2016 used).
- Drinking Water Source Protection. 2017. Thames-Sydenham & Region. Accessed August 13, 2019. <http://maps.thamesriver.on.ca/gvh/?viewer=tsrassessmentreport>
- Ministry of the Environment and Energy. 1995. MOEE Hydrogeological Technical Information Requirements for Land Development Applications. April 1995.
- Ministry of the Environment, Conservation and Parks. <https://www.ontario.ca/environment-and-energy/map-well-records>, accessed August 05, 2019.
- Ministry of the Environment, Conservation and Parks. <https://www.ontario.ca/environment-and-energy/map-permits-take-water>, accessed August 05, 2019.
- Ministry of the Environment, Conservation and Parks. <https://www.gisapplication.lrc.gov.on.ca/SourceWaterProtection/Index.html?viewer=SourceWaterProtection.SWPViewer&locale=en-US>, accessed August 05, 2019.
- Ministry of Natural Resources and Forestry. http://www.gisapplication.lrc.gov.on.ca/mamnh/Index.html?site=MNR_NHLUPS_NaturalHeritage&viewer=NaturalHeritage&locale=en-US, accessed August 05, 2019.

- Ministry of Natural Resources and Forestry.
<https://www.gisapplication.lrc.gov.on.ca/OFAT/Index.html?site=OFAT&viewer=OFAT&locale=en-US>; accessed August 05, 2019.
- Ministry of Northern Development and Mines. 1991. Map 2556, Quaternary Geology of Southern Ontario.
- Municipality of Thames Centre. Consolidation Version December 2016, Municipality of Thames Centre Official Plan.
- Thames-Sydenham and Region Source Protection Committee. September 17, 2015. Thames-Sydenham and Region Source Protection Plan.
- Upper Thames River Conservation Authority in cooperation with Middlesex County Conservation Authorities, October 28, 2014. Middlesex Natural Heritage Systems Study.
- Varni, Marcelo; Comas, Rocio; Weinzettel, Pablo and Dietrich, Sebastian, 2013. *Application of the water table fluctuation method to characterize groundwater recharge in the Pampa plain, Argentina*. Hydrological Sciences Journal, 58:7, p. 1445 - 1455.

Appendix A

Drawings

Drawing 1 : Location Plan

Drawing 2 : Groundwater Contours, 31 January 2020

Drawing 3 : PGMN Well W107-1 Location water well record and area of influence



eNGLOBE

\\EGN\TDRIVE\ENGLOBE\SHARED\CALON\DATA\PROJECTS\16011_PROJECTS\2019\P-0019257 SUBDIVISION, CHRISTIE STREET, DORCHESTER\ZA_CADD\DWG\05_P-0019257_000_0100_GS_P-0101_00.DWG

10 cm

5

4

3

2

1

0



LEGEND:

- Boreholes
- Monitoring Wells
- Mini Piezometers
- Site Limits

This document must be used in a joint way with the recommendations formulated in the report study

Scale

0 20 40 60 80 100 150 200 m

1:4 000

This document is the work of Englobe Corp. Any reproduction, distribution or adaptation, in whole or in part, is strictly prohibited without the prior written authorization of Englobe and its Client. No information contained in this document may be used by any third party without the written permission of Englobe and its Client. Englobe Corp. disclaims all liability for any unauthorized reproduction, distribution, adaptation, or use of the document.

Client

Cyril J. Demeyere Ltd.

englobe

Englobe Corp.

4222 Bourque Blvd
Sherbrooke, QC J1L 1W6
T 819 563-3372
F 819 563-3326

Project

Hydrogeology
Study Report

284 Christie Drive, Dorchester

Title

Drawing 1 :
Site Location

Discipline:	Geosciences	Prepared by:	F. Proteau-Bédard, M.Sc.A.	Checked by:	F. Proteau-Bédard, M.Sc.A.
Scale:	1:4 000	Drawn by:	R. Careau	Approved by:	J.-P. Gobeil, P.Geo. Geo., M.Sc.
Date:	30/01/2024	Figure N°:	01		
Page setup:	0001	Paper format:	ANSI full bleed B (17,00 x 11,00 pouces)		
Register N°:					

Resp.	Project	Phase	Disc.	Type	Drawing N°	Rev.
05	P-0019257.000	0100	GS	D	0101	00

10 cm
5
4
3
2
1
0



LEGEND:

- Boreholes (Water Level)
- Monitoring Wells (Water Level)
- Site Limits
- Piezometry

This document must be used in a joint way with the recommendations formulated in the report study

Scale

0 20 40 60 80 100 150 200 m

1:4 000

This document is the work of Englobe Corp. Any reproduction, distribution or adaptation, in whole or in part, is strictly prohibited without the prior written authorization of Englobe and its Client. No information contained in this document may be used by any third party without the written permission of Englobe and its Client. Englobe Corp. disclaims all liability for any unauthorized reproduction, distribution, adaptation, or use of the document.

Client

Cyril J. Demeyere Ltd.

ENGLOBE

Englobe Corp.

4222 Bourque Blvd
Sherbrooke, QC J1L 1W6
T 819 563-3372
F 819 563-3326

Project

Hydrogeology
Study Report

284 Christie Drive, Dorchester

Title

Drawing 2 :
Piezometric Map

Discipline:	Geosciences	Prepared by:	F. Proteau-Bédard, M.Sc.A.	Checked by:	F. Proteau-Bédard, M.Sc.A.
Scale:	1:4 000	Drawn by:	R. Careau	Approved by:	J.-P. Gobeil, P.Geo. Geo., M.Sc.
Date:	30/01/2024	Figure N°:	02		
Page setup:	0002	Paper format:	ANSI full bleed B (17,00 x 11,00 pouces)		
Register N°:					

Resp.	Project	Phase	Disc.	Type	Drawing N°	Rev.
05	P-0019257.000	0100	GS	D	0102	00

10 cm
5
4
3
2
1
0
\\EGN\TDRIVE\ENGLOBE\SHARED\CALON\DATA\PROJECTS\16011_PROJECTS\2019\P-0019257 SUBDIVISION, CHRISTIE STREET, DORCHESTER\Z\ CAD\DWG\05.P-0019257.000.0100.GS.D-0103.00.DWG



LEGEND:

- Water Wells
- Site Limits
- Area of influence
- Sanitary sewer location

Dewatering sources

- Sewers
- SWM pond

This document must be used in a joint way with the recommendations formulated in the report study

Scale

1:5 000

This document is the work of Englobe Corp. Any reproduction, distribution or adaptation, in whole or in part, is strictly prohibited without the prior written authorization of Englobe and its Client. No information contained in this document may be used by any third party without the written permission of Englobe and its Client. Englobe Corp. disclaims all liability for any unauthorized reproduction, distribution, adaptation, or use of the document.

Client

Cyril J. Demeyere Ltd.

Englobe Corp.
4222 Bourque Blvd
Sherbrooke, QC J1L 1W6
T 819 563-3372
F 819 563-3326

Project

Hydrogeology
Study Report

284 Christie Drive, Dorchester

Title

Drawing 3 :
Water Wells Records (WWR)

Discipline:	Geosciences	Prepared by:	F. Proteau-Bédard, M.Sc.A.	Checked by:	F. Proteau-Bédard, M.Sc.A.
Scale:	1:5 000	Drawn by:	R. Careau	Approved by:	J.-P. Gobeil, P.Geo. Geo., M.Sc.
Date:	05/04/2024	Figure N°:	03		
Page setup:	0003	Paper format:	ANSI full bleed B (17,00 x 11,00 pouces)		
Register N°:					

Resp.	Project	Phase	Disc.	Type	Drawing N°	Rev.
05	P-0019257.000	0100	GS	D	0103	01

Appendix B

Borehole Logs

Boreholes BH01-19 to BH-14-19




eNGLOBE

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

01-19

Encl. No. 01 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 16, 2019



REF. NO.: P-0019257-100

LOG OF BOREHOLE NO.

Encl. No. 02 (Sheet 1 of 1)

CLIENT: Cyril J. Demeyere Ltd.

DRILLING DATA: London Soil Test

PROJECT: Proposed Residential Subdivision

METHOD: Hollow Stem Auger


LOCATION: 83 Christie Drive, Dorchester, Ontario

02-19

DIAMETER: 200mm

DATUM ELEVATION: Geodetic

DATE: Jul 16, 2019



REF. NO.: P-0019257-100 LOG OF BOREHOLE NO. 03-19
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

Encl. No. 03 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 16, 2019

SUBSURFACE PROFILE							LEL %	NATURAL WATER %	GAS %	WELL CONSTRUCTION
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft			
262.27	0	300 mm topsoil.								0.88m stickup
262		SAND: Very loose, brown sand, some silt, moist.								Concrete
261	1				1	ss	4	6		
260	2				2	ss	2	4		
259	3				3	ss	2	3		
258	4	compact, trace gravel.			4	ss	3	3		
257	5				5	ss	10	3		
256	6				6	ss	11	3		
255	7				7	ss	17	3		Bentonite
254	8				8	ss	21	4		
253	9				9	ss	21	5		
252	10									
251	11	saturated.			10	ss	16	21		
250	12	dense.			11	ss	36	19		
249	13									Sand Filter 50 mm diameter screen with filter pack
	14	Borehole terminated. Water level at 10.52 m below ground surface upon completion of drilling.			12	ss	40			

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

04-19

Encl. No. 04 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 18, 2019

SUBSURFACE PROFILE							LEL %	NATURAL WATER %	GAS %	WELL CONSTRUCTION
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft			
259.14	0	250 mm topsoil.								0.85m stickup
259		SAND: Very loose to compact, brown sand, some silt, moist.								concrete
	1				1	ss	3			
258										
	2	very moist.			2	ss	10			
257										Bentonite
	3	TILL: Stiff to very stiff, clayey silt, seams of sandy silt, saturated.			3	ss	11	17		
256										
	4	SAND: Compact, brown sand trace silt and gravel, saturated.			4	ss	17	17		
255										
	5	grey, loose silty sand.			5	ss	10			
254										Sand Filter 50 mm diameter screen with filter pack
	6	compact.			6	ss	9	15		
253										
		some gravel. Borehole terminated. Monitoring Well Installed.			7	ss	27	17		

REF. NO.: P-0019257-100
CLIENT: Cyril J. Demeyere Ltd.
PROJECT: Proposed Residential Subdivision
LOCATION: 83 Christie Drive, Dorchester, Ontario
DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

05-19

Encl. No. 05 (Sheet 1 of 1)
DRILLING DATA: London Soil Test
METHOD: Hollow Stem Auger
DIAMETER: 200mm
DATE: Jul 18, 2019


SUBSURFACE PROFILE							LEL %	NATURAL WATER %	GAS %	WELL CONSTRUCTION
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft			
260.10	0	230 mm topsoil.								0.80m stickup
260		SAND: Loose, brown sand, some silt, moist.								Concrete
259	1	saturated.			1	ss	6	16		
258	2	SILT: Stiff, brown clayey silt, trace sand, very moist.			2	ss	9	14		Bentonite
		seams of sandy silt.			3	ss	14	17		
257	3	very stiff, grey.			4	ss	19			
256	4	SAND: Compact, brown sand, some silt, trace gravel, saturated.			5	ss	16	10		
255	5				6	ss	11			50 mm diameter screen with filter pack Sand Filter
254	6				7	ss	22	16		
253	7	grey sand.			8	ss	11	15		Bentonite
	8	Borehole terminated. Monitoring Well installed.								

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

06-19

Encl. No. 06 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 16, 2019




REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

07-19

Encl. No. 07 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 16, 2019



REF. NO.: P-0019257-100 LOG OF BOREHOLE NO.
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

08-19

Encl. No. 08 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Jul 18, 2019


SUBSURFACE PROFILE							LEL %	NATURAL WATER %	GAS %	WELL CONSTRUCTION
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft			
266.37	0	230 mm topsoil.								0.90m stickup
266		SAND: Loose to very loose, brown sand, some silt, moist.								Concrete
	1				1	ss	5			
265										
	2				2	ss	3			
264		Compact, very moist.						9		
	3				3	ss	13			
263								1		
	4				4	ss	20			
262										
	5				5	ss	24	1		Bentonite
261										
	6				6	ss	29	1		
260										
	7									
259										
	8				7	ss	19	17		
258										
	9	saturated.			8	ss	20	14		
257										
	10									50 mm diameter screen with filter pack Sand Filter
256										
	11	Borehole terminated. Monitoring Well Installed.			9	ss	23	17		

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

09-19

Encl. No. 09 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Aug 1, 2019



Englobe

CONSULTING SOILS AND MATERIALS ENGINEERS

417 Exeter Road, London, Ontario, N6E 2Z3

Phone: 519-685-6400 Fax: 519-685-0943

REF. NO.: P-0019257-100

LOG OF BOREHOLE NO.

Encl. No.

10 (Sheet 1 of 1)

CLIENT: Cyril J. Demeyere Ltd.

DRILLING DATA:

London Soil Test

PROJECT: Proposed Residential Subdivision

METHOD:

Hollow Stem Auger

LOCATION: 83 Christie Drive, Dorchester, Ontario

10-19

DIAMETER:

200mm

DATUM ELEVATION: Geodetic

DATE:

Aug 1, 2019

SUBSURFACE PROFILE							LEL %	NATURAL WATER %	GAS %	WELL CONSTRUCTION
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft			
257.33	0	500 mm topsoil.								
257	1	SAND: Very loose, brown sand, trace silt and gravel, trace rootlets, moist.			1	ss	2	7		
256	2				2	ss	7	19		
255	3	Dense.			3	ss	39	18		
254	4	compact, brown sand and gravel, trace silt, saturated.			4	ss	12	11		
253	5	gravelly sand.			5	ss	18	5		
252	6				6	ss	34	9		
251	7	dense			7	ss	42	14		
250	8	SILT: Compact, brown silt and sand, trace gravel, moist.			8	ss	25	15		
249	9	clayey silt.			9	ss	24	9		
248		Borehole terminated. Water level at 4.88 m below ground surface upon completion of drilling. Monitoring Well Installed.								

0.9m stickup.
Concrete

Bentonite

50 mm
diameter
screen with
filter pack

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.

11-19

Encl. No. 11 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Aug 1, 2019

SUBSURFACE PROFILE								● Penetration Resistance Blows/ft				PLASTIC LIMIT %	NATURAL WATER %	LIQUID LIMIT %
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft	20	40	60	80			
								Undrained Shear Strength kPa						
								▲ Field Vane Test ★ Compression Test						
								20	40	60	80			
257.58	0	500 mm topsoil.												
	257	SAND: Loose, brown sand, some silt, moist.												
	1				1	ss	7							2
	256													
	2				2	ss	9							3
	255	compact.												
	3				3	ss	14							3
	254													
	4				4	ss	17							2
	253	Dense, saturated.												
	5				5	ss	15							
														
					6	ss	36							16
		Borehole terminated. Open and dry.												

Englobe

CONSULTING SOILS AND MATERIALS ENGINEERS

417 Exeter Road, London, Ontario, N6E 2Z3

Phone: 519-685-6400 Fax: 519-685-0943

REF. NO.: P-0019257-100

LOG OF BOREHOLE NO.

Encl. No. 12 (Sheet 1 of 1)

CLIENT: Cyril J. Demeyere Ltd.

DRILLING DATA: London Soil Test

PROJECT: Proposed Residential Subdivision

METHOD: Hollow Stem Auger

LOCATION: 83 Christie Drive, Dorchester, Ontario

12-19

DIAMETER: 200mm

DATUM ELEVATION: Geodetic

DATE: Aug 1, 2019


SUBSURFACE PROFILE								● Penetration Resistance Blows/ft				PLASTIC LIMIT %	NATURAL WATER %	LIQUID LIMIT %
Elev. metres	Depth metres	DESCRIPTION	SYMBOL	GROUND WATER	NUMBER	TYPE	"N" Blows/ft	20	40	60	80			
								Undrained Shear Strength kPa						
								20	40	60	80			
255.19	0	Peat: Very loose, dark brown/black, silt, some sand and clay, very moist.												
255														
	1				1	ss	2	●						88
254														
	2				2	ss	2	●						31
253		CLAY: Soft to firm, brown silty clay, some sand seams, very moist to wet.												
	2			▽	3	ss	7	●						
	3													
252					4	ss	7	●						
	4				5	ss	5	●						
251		Borehole terminated. Water level at 2.29 m below ground surface upon completion of drilling.												

REF. NO.: P-0019257-100
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

LOG OF BOREHOLE NO.


13-19

Encl. No. 13 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Aug 2, 2019



REF. NO.: P-0019257-100 LOG OF BOREHOLE NO. 14-19
 CLIENT: Cyril J. Demeyere Ltd.
 PROJECT: Proposed Residential Subdivision
 LOCATION: 83 Christie Drive, Dorchester, Ontario
 DATUM ELEVATION: Geodetic

Encl. No. 14 (Sheet 1 of 1)
 DRILLING DATA: London Soil Test
 METHOD: Hollow Stem Auger
 DIAMETER: 200mm
 DATE: Aug 13, 2019



Appendix C

Figures

Figure 1 : Grain Size Distribution Graph (Boreholes BH03-19, BH-05-19 and BH-06-19)

Figure 2 : Grain Size Distribution Graphs (Boreholes BH08-19 and BH-09-19)

Figure 3 : Grain Size Distribution Graphs (Boreholes BH12-19 and BH-13-19)

Figure 4 : Piper diagram of the site



eNGLOBE

Project: **Proposed Residential Subdivision**


Figure No : **1**

Location: **83 Christie Street, Dorchester, Ontario**

File No : **P-0019257-0-01-100**

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN MILLIMETRES			U.S. STANDARD SIEVE No.			HYDROMETER



Symbol	Borehole n°	Sample n°	Depth (m)	Description
—○—	BH-03-19	SA-3	2.29 - 2.74	SAND, trace Silt
—□—	BH-05-19	SA-4	3.05 - 3.51	SILT and CLAY
—▽—	BH-06-19	SA-3	2.29 - 2.74	SAND, trace Silt

Project: **Proposed Residential Subdivision**


Figure No : **2**

Location: **83 Christie Street, Dorchester, Ontario**

File No : **P-0019257-0-01-100**

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN MILLIMETRES			U.S. STANDARD SIEVE No.			HYDROMETER



Symbol	Borehole n°	Sample n°	Depth (m)	Description
—○—	BH-08-19	SA-3	2.29 - 2.74	Silty SAND, some Gravel, trace Clay
—□—	BH-09-19	SA-2	1.52 - 1.98	SAND, trace Silt and Clay
—▽—	BH-09-19	SA-5	3.81 - 4.27	SAND, trace Silt and Clay

Project: **Proposed Residential Subdivision**


Figure No : **3**

Location: **83 Christie Street, Dorchester, Ontario**

File No : **P-0019257-0-01-100**

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN MILLIMETRES			U.S. STANDARD SIEVE No.			HYDROMETER




Symbol	Borehole n°	Sample n°	Depth (m)	Description
—○—	BH-12-19	SA-2	1.52 - 1.98	SAND and SILT, trace Clay
—□—	BH-12-19	SA-3	2.29 - 2.74	SILT and CLAY, trace Sand
—▽—	BH-13-19	SA-2	1.52 - 1.98	SAND, some SILT, trace Clay

Figure 4: Piper Diagram

▲ Englobe 2020 chemical survey

■ PGMN W487-2 chemical surveys



Appendix D

Tables

Table 101 : Groundwater and Surface Water Elevations

Table 102 : Hydraulic Conductivity Estimates and Infiltration Rates

Table 103 : Groundwater Chemistry Results

Table 104 : Water Levels Fluctuation for Infiltration Assessment



eNGLOBE

TABLE 101
WELLS LOCATIONS AND GROUNDWATER ELEVATION
83, CHRISTIE DR, DORCHESTER

Well ID	Northing (m) (UTM NAD83 - Zone 17N)	Easting (m) (UTM NAD83 - Zone 17N)	Ground surface elevation (m ASL)	Date	Water level (m BGS)	Water levels (m ASL)
MW03-19	4758756	494189	262,27	30/08/2019	10,52	251,75
				13/09/2019	10,54	251,73
				09/12/2019	10,61	251,66
				27/01/2020	10,53	251,745
				26/02/2020	10,49	251,78
				30/03/2020	10,44	251,83
				29/04/2020	10,43	251,84
				09/06/2020	10,50	251,77
				07/01/2021	10,60	251,67
				16/09/2022	10,58	251,69
				08/08/2019	2,51	256,635
				30/08/2019	2,63	256,515
MW04-19	4758609	493813	259,14	13/09/2019	2,67	256,47
				09/12/2019	2,36	256,785
				27/01/2020	1,85	257,295
				26/02/2020	2,19	256,955
				30/03/2020	1,96	257,185
				29/04/2020	2,17	256,975
				09/06/2020	2,24	256,905
				07/01/2021	2,19	256,955
				16/09/2022	2,72	256,425
				08/08/2019	3,49	256,61
				30/08/2019	3,64	256,46
				13/09/2019	3,71	256,39
MW05-19	4758532	494078	260,1	09/12/2019	3,78	256,32
				27/01/2020	3,39	256,715
				26/02/2020	3,37	256,73
				30/03/2020	3,28	256,82
				29/04/2020	3,30	256,8
				09/06/2020	3,34	256,76
				07/01/2021	3,68	256,42
				16/09/2022	3,87	256,23
				08/08/2019	7,92	258,42
				30/08/2019	8,02	258,32
				13/09/2019	8,06	258,28
				09/12/2019	8,11	258,23
MW08-19	4758277	493908	266,37	27/01/2020	7,92	258,42
				26/02/2020	7,83	258,51
				30/03/2020	7,77	258,57
				29/04/2020	7,76	258,58
				09/06/2020	7,84	258,5
				07/01/2021	8,10	258,24
				16/09/2022	8,95	257,39
				08/08/2019	2,23	255,1
				30/08/2019	2,33	255
				13/09/2019	2,33	255
				09/12/2019	2,38	254,95
				27/01/2020	2,17	255,16
MW10-19	4758447	494386	257,33	26/02/2020	2,20	255,135
				30/03/2020	2,10	255,23
				29/04/2020	2,16	255,17
				09/06/2020	2,18	255,15
				07/01/2021	2,32	255,01
				16/09/2022	2,43	254,9
				30/08/2019	5,82	259,81
				13/09/2019	5,90	259,73
				09/12/2019	6,08	259,55
				27/01/2020	5,88	259,75
				26/02/2020	5,77	259,86
				30/03/2020	5,71	259,92
MW14-19	4758073	494200	265,63	29/04/2020	5,65	259,98
				09/06/2020	5,17	260,46
				07/01/2021	6,14	259,49
				16/09/2022	6,11	259,52
				13/09/2019	0,06	252,815
				09/12/2019	0,04	252,835
				27/01/2020	0,01	252,865
				26/02/2020	0,02	252,855
				30/03/2020	0,04	252,835
				29/04/2020	0,04	252,835
				09/06/2020	0,04	252,835
				07/01/2021	0,05	252,825
MP01-20	4758800	493871	252,87	16/09/2022	0,11	252,765
				13/09/2019	0,01	251,87
				09/12/2019	0,01	251,87
				27/01/2020	0,01	251,87
				26/02/2020	0,00	251,88
				30/03/2020	0,01	251,87
				29/04/2020	0,01	251,87
				09/06/2020	0,01	251,87
				07/01/2021	-0,01	251,89
				16/09/2022	0,01	251,87
				13/09/2019	0,60	256,845
				09/12/2019	0,45	256,99
				27/01/2020	0,02	257,42
MP03-20	4758475	493815	257,44	26/02/2020	0,20	257,245
				30/03/2020	0,05	257,39
				29/04/2020	0,16	257,28
				09/06/2020	0,23	257,21
				07/01/2021	0,35	257,09
				16/09/2022	0,57	256,87
				13/09/2019	0,96	252,86
				09/12/2019	0,52	253,3
				27/01/2020	0,47	253,35
				26/02/2020	0,79	253,03
				30/03/2020	0,55	253,27
				29/04/2020	0,55	253,27
MP04-20	4758258	494596	253,82	09/06/2020	0,57	253,25
				07/01/2021	0,36	253,46
				16/09/2022	0,71	253,11
				29/04/2020	0,32	-
				09/06/2020	0,15	-
				07/01/2021	0,01	-
				16/09/2022	0,43	-
MP05-20	4758283	493671	-			

TABLE 102							
HYDRAULIC CONDUCTIVITY ESTIMATES AND INFILTRATION RATES							
83, CHRISTIE DR, DORCHESTER							
Test ID	Test Used	Depth (mBGS)	K (cm/s)	LN(I)	Infiltration Rate (mm/hour)	Safety factor of 2.5	Safety factor of 3.5
BH3SA3	Grain size	1.60 - 2.00	1,4E-02	5,16	173,64	69,45	49,61
BH5SA4	Grain size	3.00 - 3.50	5,9E-08	1,84	6,32	2,53	1,81
BH6SA3	Grain size	2.25 - 2.75	1,6E-02	5,19	179,95	71,98	51,42
BH8SA3	Grain size	2.25 - 2.75	1,8E-03	4,61	100,28	40,11	28,65
BH9SA2	Grain size	1.50 - 2.00	9,7E-03	5,06	157,40	62,96	44,97
BH9SA5	Grain size	3.80 - 4.25	1,7E-02	5,21	182,90	73,16	52,26
BH12SA2	Grain size	1.50 - 2.00	3,1E-04	4,14	62,63	25,05	17,89
BH12SA3	Grain size	2.30 - 2.80	1,7E-08	1,51	4,53	1,81	1,30
BH13SA2	Grain size	1.50 - 2.00	2,5E-03	4,70	109,49	43,80	31,28
TP01-20	Guelph	1,20	1,1E-03	4,47	87,68	35,07	25,05
TP01-20	Guelph	1,80	3,4E-03	4,77	118,42	47,37	33,83
TP02-20 -test1	Guelph	1,20	5,8E-03	4,92	137,41	54,96	39,26
TP02-20-test2	Guelph	1,20	4,9E-03	4,88	131,25	52,50	37,50
TP02-20-test1	Guelph	1,80	1,2E-02	5,12	167,36	66,94	47,82
TP02-20 -test2	Guelph	1,80	8,2E-03	5,01	150,23	60,09	42,92
TP03-20	Guelph	1,20	1,9E-05	3,38	29,45	11,78	8,41
TP04-20	Guelph	1,20	2,3E-03	4,67	106,45	42,58	30,41
TP04-20	Guelph	1,70	8,6E-04	4,41	82,39	32,96	23,54
TP04-20 -test1	Guelph	2,35	1,7E-02	5,21	182,32	72,93	52,09
TP04-20 -test2	Guelph	2,35	2,4E-02	5,30	200,58	80,23	57,31
TP05-20	Guelph	1,20	3,1E-03	4,75	115,48	46,19	32,99
TP05-20-test1	Guelph	1,75	1,9E-02	5,24	188,95	75,58	53,99
TP05-20-test2	Guelph	1,75	1,8E-02	5,22	185,16	74,07	52,90
TP05-20	Guelph	2,35	1,9E-02	5,24	188,16	75,26	53,76
Geometric Mean, Shallow Soil			1,6E-03	4,58	97,89	39,16	27,97
MW04-19	Hvorslev/Rising head	4.20-5.70	1,3E-02	-	-	-	-
MW05-19	Hvorslev/Rising head	4.10-5.60	3,9E-03	-	-	-	-
MW10-19	Hvorslev/Rising head	4.30-5.80	1,2E-03	-	-	-	-
Geometric Mean, Water Table Soils			-	-	-	-	-

mBGS = metres below ground surface.

$y=6E-11(X^{3.7363})$
 $LN(K)=LN6-11LN10+3.7363LN(I)$
K = cm/s
I = mm/hour
 $LN(I)=(LN(K)+11LN(10)-LN(6))/3.7363$

Use safety factor of 2.5 if soils in the infiltration interval are homogeneous. Use 3.5 otherwise.

TABLE 103

GROUNDWATER CHEMICAL RESULTS

83, CHRISTE DR, DORCHESTER

Parameter	Thames center limits for sanitary sewer discharge	Provinvial Water Quality Objective	Detection Limit	Units	MW-03-19	MW-08-19	MW-10-19	MP-01-19	MP-04-19	MW-05-19
Colour, Apparent			2	CU	7,50	20,90	51,50	40,00	96,10	
Conductivity			3	umhos/cm	599,00	666,00	600,00	478,00	652,00	
Hardness (as CaCO3)			0,5	mg/L	366,00	355,00	325,00	283,00	265,00	
pH		6.5 - 8.5	0,1	pH units	7,78	8,16	7,71	8,14	8,26	7,94
Total Suspended Solids	350		2	mg/L						41,40
Total Dissolved Solids			20	mg/L	376,00	386,00	451,00	272,00	359,00	
Turbidity			0,1	NTU	5,68	29,40	211,00	9,47	24,20	
Alkalinity, Total (as CaCO3)	Not decreased by more than 25% from natural		10	mg/L	254,00	315,00	284,00	255,00	251,00	
Ammonia, Total (as N)			0,01	mg/L	0,02	<0.010	0,02	0,02	0,37	
Chloride (Cl)			0,5	mg/L	12,30	9,22	9,71	2,63	53,80	
Fluoride (F)	10		0,02	mg/L	0,07	0,05	0,12	0,05	0,15	0,06
Nitrate (as N)			0,02	mg/L	8,04	7,21	9,42	0,03	0,83	
Nitrite (as N)			0,01	mg/L	0,03	<0.010	0,03	<0.010	<0.010	
Total Kjeldahl Nitrogen	100		0,15	mg/L						
Orthophosphate-Dissolved (as P)			0,003	mg/L	<0.0030	0,0054	<0.0030	0,0088	0,01	
Phosphorus, Total	10	0,03	0,003	mg/L						0,034
Sulfate (SO4)	1500		0,3	mg/L	24	17,7	27,5	7,85	14,70	25,90
Sulphide (as S)	1	1,7	0,018	mg/L						<0.018
Sulphide (as H2S)			0,019	mg/L						<0.019
Cyanide, Total	1	0,005	0,002	mg/L						<0.0020
Antimony (Sb)-Total	5	0,1	0,0001	mg/L						<0.00010
Arsenic (As)-Total	1	0,005	0,0001	mg/L						0,00
Cadmium (Cd)-Total		0,0002	0,000005	mg/L						0,00
Chromium (Cr)-Total		0,008	0,0005	mg/L						0,00
Cobalt (Co)-Total		0,0009	0,0001	mg/L						0,00
Copper (Cu)-Total		0,005	0,001	mg/L						0,00
Lead (Pb)-Total	1	0,025	0,00	mg/L						0,00
Mercury (Hg)-Total	0,01	0,0002	0,00	mg/L						
Molybdenum (Mo)-Total		0,04	0,00	mg/L						0,00
Nickel (Ni)-Total		0,025	0,00	mg/L						0,00
Selenium (Se)-Total	1	0,1	0,00	mg/L						0,00
Silver (Ag)-Total	5	0,0001	0,00	mg/L						<0.000050
Tin (Sn)-Total	5		0,00	mg/L						0,00
Zinc (Zn)-Total		0,03	0,00	mg/L						0,07
Aluminum (Al)-Dissolved		0,075	0,005	mg/L	<0.0050	7,5E-03	<0.0050	<0.0050	<0.0050	
Antimony (Sb)-Dissolved		0,02	0,0001	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Arsenic (As)-Dissolved		0,1	0,0001	mg/L	0,00023	2,9E-04	0,0004	0,00023	0,00	
Barium (Ba)-Dissolved			0,0001	mg/L	0,023	1,9E-02	0,0427	0,0169	0,02	
Beryllium (Be)-Dissolved		1,1	0,0001	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Bismuth (Bi)-Dissolved			0,00005	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	
Boron (B)-Dissolved		0,2	0,01	mg/L	0,013	1,6E-02	0,013	<0.010	0,02	
Cadmium (Cd)-Dissolved	0,7		0,000005	mg/L	0,0000098	1,3E-05	0,0000137	<0.0000050		
Calcium (Ca)-Dissolved			0,05	mg/L	106	1,0E+02	93,4	86,9	77,40	
Chromium (Cr)-Dissolved	3		0,0005	mg/L	0,00051	<0.00050	0,00073	<0.00050	<0.00050	
Cobalt (Co)-Dissolved	5		0,00	mg/L	<0.00010	<0.00010	<0.00010	0,00	0,00	
Copper (Cu)-Dissolved	3		0,00	mg/L	1,98E-03	4,7E-03	0,00	0,00	0,00	
Iron (Fe)-Dissolved		0,3	0,01	mg/L	<0.010	<0.010	<0.010	0,21	0,84	
Lead (Pb)-Dissolved		0,025	0,00	mg/L	<0.000050	3,1E-04	0,00	<0.000050	0,00	
Magnesium (Mg)-Dissolved			0,01	mg/L	24,7	2,4E+01	22,20	16,10	17,30	
Manganese (Mn)-Dissolved			0,00	mg/L	0,00272	4,1E-03	0,01	0,17	0,93	
Molybdenum (Mo)-Dissolved	5		0,00	mg/L	0,000415	9,0E-04	0,00	0,00	0,00	
Nickel (Ni)-Dissolved	2	0,025	0,00	mg/L	0,00142	<0.00050	0,00	0,00	0,00	
Phosphorus (P)-Dissolved			0,05	mg/L	<0.050	<0.050	<0.050	<0.050	<0.050	
Potassium (K)-Dissolved			0,05	mg/L	0,785	8,7E-01	1,56	0,271	2,03	
Selenium (Se)-Dissolved			0,00005	mg/L	0,00111	3,0E-03	0,000142	0,000247	0,00	
Silicon (Si)-Dissolved			0,05	mg/L	6,41	6,3E+00	5,6	4,82		
Silver (Ag)-Dissolved			0,00005	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	
Sodium (Na)-Dissolved			0,05	mg/L	4,24	3,3E+00	8,37	2,84	29,70	
Strontium (Sr)-Dissolved			0,001	mg/L	0,185	1,5E-01	0,199	0,155	0,25	
Thallium (Tl)-Dissolved			0,00001	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010	
Tin (Sn)-Dissolved			0,0001	mg/L	0,00062	3,1E-04	0,00037	0,00036	0,00	
Titanium (Ti)-Dissolved			0,0003	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030	
Tungsten (W)-Dissolved			0,00	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Uranium (U)-Dissolved		0,005	0,00	mg/L	5,99E-04	1,0E-03	0,00	0,00	0,00	
Vanadium (V)-Dissolved		0,006	0,00	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Zinc (Zn)-Dissolved	3		0,00	mg/L	1,95E-01	6,2E-01	0,03	0,02	0,01	
Zirconium (Zr)-Dissolved			0,00	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030	
BOD	300		2,00	mg/L						<2.0
Oil and Grease, Total			5,00	mg/L						<5.0
Animal/Veg Oil & Grease			5,00	mg/L						
Mineral Oil and Grease			2,5	mg/L						<2.5
Phenols (4AAP)	1	0,001	0,001	mg/L						0,00
Benzene		0,1	0,5	ug/L						<0.50
Chloroform	40		1	ug/L						<1.0
1,2-Dichlorobenzene	50	2,5	0,5	ug/L						<0.50
1,4-Dichlorobenzene	80	4	0,5	ug/L						<0.50
Dichloromethane			2	ug/L						<2.0
Ethylbenzene	160	8	0,5	ug/L						<0.50
1,1,2,2-Tetrachloroethane	40	70	0,5	ug/L						<0.50
Tetrachloroethylene	50	50	0,5	ug/L						<0.50
Toluene	200	0,8	0,50	ug/L						<0.50
Trichloroethylene	50	20	0,50	ug/L						<0.50
Xylenes (Total)			0,50	ug/L						<0.50
4-Bromofluorobenzene				%						
1,4-Difluorobenzene				%						99,70
Total THMs			2,00	ug/L						<2.0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-01-01	1,2	0,01	0,86	2004-01-01	0	0	0	2005-01-01	0	0,15	12,9	2006-01-01	2,6	0	0	2008-01-01	7,2	0	0
2003-01-02	0	0,01	0,86	2004-01-02	6,6	0	0	2005-01-02	5,2	0	0	2006-01-02	3,2	0,01	0,86	2008-01-02	1,2	0	0
2003-01-03	5,8	0	0	2004-01-03	4,7	0,04	3,44	2005-01-03	14,2	0,11	9,46	2006-01-03	6,3	0,04	3,44	2008-01-03	3,4	0	0
2003-01-04	2,2	0	0	2004-01-04	3	0	0	2005-01-04	3,5	0	0	2006-01-04	0,6	0,02	1,72	2008-01-04	0,6	0,01	0,86
2003-01-05	0,4	0	0	2004-01-05	5,4	0	0	2005-01-05	2,2	0	0	2006-01-05	9,3	0,02	1,72	2008-01-05	0	0	0
2003-01-06	3,6	0	0	2004-01-06	2,8	0	0	2005-01-06	4	0	0	2006-01-06	1	0	0	2008-01-06	3,2	0,03	2,58
2003-01-07	1,8	0	0	2004-01-07	3,6	0	0	2005-01-07	5	0	0	2006-01-07	3,4	0	0	2008-01-07	1	0,08	6,88
2003-01-08	1,2	0	0	2004-01-08	1,6	0	0	2005-01-08	2	0	0	2006-01-08	5	0	0	2008-01-08	3,2	0,03	2,58
2003-01-09	0	0	0	2004-01-09	0,4	0	0	2005-01-09	4,2	0	0	2006-01-09	0	0	0	2008-01-09	49,6	0,24	20,64
2003-01-10	6,8	0	0	2004-01-10	0	0	0	2005-01-10	0	0	0	2006-01-10	0	0	0	2008-01-10	0,4	0	0
2003-01-11	6,4	0,02	1,72	2004-01-11	1,6	0	0	2005-01-11	1	0	0	2006-01-11	3,5	0,04	3,44	2008-01-11	2,5	0	0
2003-01-12	1	0	0	2004-01-12	15,8	0	0	2005-01-12	0,2	0	0	2006-01-12	0,6	0,01	0,86	2008-01-12	1,2	0	0
2003-01-13	3,8	0,01	0,86	2004-01-13	2,4	0,01	0,86	2005-01-13	6,8	0,1	8,6	2006-01-13	0	0	0	2008-01-13	0	0	0
2003-01-14	0,8	0	0	2004-01-14	0,8	0	0	2005-01-14	15,7	0,1	8,6	2006-01-14	6,4	0,01	0,86	2008-01-14	4,8	0	0
2003-01-15	1,8	0	0	2004-01-15	10,8	0	0	2005-01-15	0	0	0	2006-01-15	0	0	0	2008-01-15	0,6	0	0
2003-01-16	1,6	0	0	2004-01-16	0	0	0	2005-01-16	0	0	0	2006-01-16	0	0	0	2008-01-16	0,8	0	0
2003-01-17	0	0	0	2004-01-17	0	0	0	2005-01-17	1,2	0	0	2006-01-17	0	0	0	2008-01-17	0	0	0
2003-01-18	0	0	0	2004-01-18	7,6	0	0	2005-01-18	5,4	0	0	2006-01-18	19,2	0,08	6,88	2008-01-18	2,4	0	0
2003-01-19	1,8	0	0	2004-01-19	8,8	0	0	2005-01-19	11,4	0	0	2006-01-19	5,2	0	0	2008-01-19	1,8	0	0
2003-01-20	3	0,01	0,86	2004-01-20	18	0	0	2005-01-20	6,8	0	0	2006-01-20	0	0	0	2008-01-20	1	0	0
2003-01-21	0	0	0	2004-01-21	0,8	0	0	2005-01-21	0	0	0	2006-01-21	7,1	0,03	2,58	2008-01-21	0,8	0	0
2003-01-22	7	0	0	2004-01-22	9	0,01	0,86	2005-01-22	0	0	0	2006-01-22	0,8	0,01	0,86	2008-01-22	5,2	0	0
2003-01-23	3	0	0	2004-01-23	0,8	0	0	2005-01-23	14,6	0	0	2006-01-23	0	0	0	2008-01-23	3,6	0	0
2003-01-24	1,8	0	0	2004-01-24	0,2	0	0	2005-01-24	0	0,01	0,86	2006-01-24	0	0	0	2008-01-24	1,8	0	0
2003-01-25	0,6	0,02	1,72	2004-01-25	0	0	0	2005-01-25	4,4	0	0	2006-01-25	5,2	0	0	2008-01-25	0	0	0
2003-01-26	5,4	0	0	2004-01-26	0	0	0	2005-01-26	4,8	0	0	2006-01-26	3	0	0	2008-01-26	0	0	0
2003-01-27	2,2	0	0	2004-01-27	3,2	0	0	2005-01-27	0	0	0	2006-01-27	0	0	0	2008-01-27	8	0	0
2003-01-28	0,6	0,01	0,86	2004-01-28	11,4	0	0	2005-01-28	0	0	0	2006-01-28	0	0	0	2008-01-28	1	0	0
2003-01-29	2,6	0	0	2004-01-29	3,6	0	0	2005-01-29	0	0	0	2006-01-29	4,6	0,02	1,72	2008-01-29	2,9	0,02	1,72
2003-01-30	0	0	0	2004-01-30	0	0	0	2005-01-30	0	0	0	2006-01-30	14,7	0,11	9,46	2008-01-30	8	0,05	4,3
2003-01-31	0	0,01	0,86	2004-01-31	2	0	0	2005-01-31	0	0	0	2006-01-31	0	0	0	2008-01-31	1,2	0	0
2003-02-01	0,2	0	0	2004-02-01	0,4	0	0	2005-02-01	0	0	0	2006-02-01	0,2	0	0	2008-02-01	5,8	0	0
2003-02-02	0,2	0	0	2004-02-02	0	0	0	2005-02-02	0	0	0	2006-02-02	0	0	0	2008-02-02	9,8	0	0
2003-02-03	0	0,01	0,86	2004-02-03	6,3	0,01	0,86	2005-02-03	0	0	0	2006-02-03	11,2	0,04	3,44	2008-02-03	0	0	0
2003-02-04	13,4	0,01	0,86	2004-02-04	4,2	0,04	3,44	2005-02-04	0	0	0	2006-02-04	1,5	0,01	0,86	2008-02-04	0	0	0
2003-02-05	4	0,06	5,16	2004-02-05	0,4	0	0	2005-02-05	0	0	0	2006-02-05	29,2	0,1	8,6	2008-02-05	13,8	0,17	14,62
2003-02-06	0,6	0,01	0,86	2004-02-06	4	0,01	0,86	2005-02-06	0	0	0	2006-02-06	6	0	0	2008-02-06	22,2	0,11	9,46
2003-02-07	1,4	0,01	0,86	2004-02-07	2,5	0	0	2005-02-07	0	0	0	2006-02-07	3,6	0	0	2008-02-07	14,8	0	0
2003-02-08	2,6	0	0	2004-02-08	0	0	0	2005-02-08	10,9	0,08	6,88	2006-02-08	1,2	0	0	2008-02-08	1,2	0	0
2003-02-09	3,6	0	0	2004-02-09	0	0	0	2005-02-09	0,6	0,04	3,44	2006-02-09	0	0	0	2008-02-09	6,2	0	0
2003-02-10	0,4	0,01	0,86	2004-02-10	0	0	0	2005-02-10	7	0	0	2006-02-10	1,4	0	0	2008-02-10	3,8	0	0
2003-02-11	4,8	0	0	2004-02-11	2	0	0	2005-02-11	0,4	0	0	2006-02-11	1,4	0	0	2008-02-11	1,2	0	0
2003-02-12	14,4	0,03	2,58	2004-02-12	0	0	0	2005-02-12	2,6	0	0	2006-02-12	0	0	0	2008-02-12	0	0	0
2003-02-13	0,4	0	0	2004-02-13	0	0	0	2005-02-13	0	0	0	2006-02-13	0	0	0	2008-02-13	15,2	0	0
2003-02-14	0,4	0	0	2004-02-14	0	0	0	2005-02-14	6	0	0	2006-02-14	2,4	0	0	2008-02-14	0	0	0
2003-02-15	0	0	0	2004-02-15	0	0	0	2005-02-15	17	0,22	18,92	2006-02-15	0	0	0	2008-02-15	1,2	0	0
2003-02-16	0	0	0	2004-02-16	0	0	0	2005-02-16	24	0,11	9,46	2006-02-16	8,4	0,05	4,3	2008-02-16	0,4	0	0
2003-02-17	0	0	0	2004-02-17	0	0	0	2005-02-17	3,8	0	0	2006-02-17	22,7	0,15	12,9	2008-02-17	1,4	0,1	8,6
2003-02-18	5,2	0	0	2004-02-18	0	0	0	2005-02-18	8,8	0	0	2006-02-18	0,6	0	0	2008-02-18	23,2	0,11	9,46
2003-02-19	1	0	0	2004-02-19	0	0	0	2005-02-19	3	0	0	2006-02-19	3,2	0	0	2008-02-19	1,4	0	0
2003-02-20	0	0	0	2004-02-20	0,8	0	0	2005-02-20	1,8	0	0	2006-02-20	0	0	0	2008-02-20	2,6	0	0
2003-02-21	0	0,01	0,86	2004-02-21	17,5	0,09	7,74	2005-02-21	15,8	0	0	2006-02-21	0,6	0	0	2008-02-21	0	0	0
2003-02-22	0	0,01	0,86	2004-02-22	2,2	0,03	2,58	2005-02-22	0	0	0	2006-02-22	0,2	0	0	2008-02-22	2,6	0	0
2003-02-23	21,3	0,01	0,86	2004-02-23	0	0	0	2005-02-23	3,2	0	0	2006-02-23	0	0	0	2008-02-23	0,2	0	0
2003-02-24	2,2	0	0	2004-02-24	0	0	0	2005-02-24	0	0	0	2006-02-24	2,8	0	0	2008-02-24	0	0	0
2003-02-25	3,4	0	0	2004-02-25	0	0	0	2005-02-25	0	0	0	2006-02-25	0	0,02	1,72	2008-02-25	0	0	0
2003-02-26	0	0,01	0,86	2004-02-26	0	0	0	2005-02-26	2,6	0	0	2006-02-26	2,2	0	0	2008-02-26	2	0	0
2003-02-27	0	0	0	2004-02-27	0	0	0	2005-02-27	0,4	0	0	2006-02-27	0,2	0	0	2008-02-27	6,2	0	0
2003-02-28	0	0	0	2004-02-28	0	0,01	0,86	2005-02-28	0	0	0	2006-02-28	0,4	0	0	2008-02-28	0,4	0	0
2003-02-28	0	0	0	2004-02-29	0	0,01	0,86	2005-02-28	0	0	0	2006-02-28	0	0	0	2008-02-29	0	0	0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-03-01	0	0	0	2004-03-01	0	0.02	1.72	2005-03-01	8.8	0	0	2006-03-01	1.2	0	0	2008-03-01	10.2	0	0
2003-03-02	4.2	0.01	0.86	2004-03-02	3.1	0.04	3.44	2005-03-02	8.6	0	0	2006-03-02	4.2	0	0	2008-03-02	0.4	0	0
2003-03-03	0.6	0	0	2004-03-03	0	0.08	6.88	2005-03-03	5.8	0	0	2006-03-03	16.4	0	0	2008-03-03	1.8	0.04	3.44
2003-03-04	2.6	0.01	0.86	2004-03-04	0.6	0.04	3.44	2005-03-04	1.8	0	0	2006-03-04	0	0	0	2008-03-04	9.5	0.14	12.04
2003-03-05	8.6	0	0	2004-03-05	6.4	0.04	3.44	2005-03-05	0	0	0	2006-03-05	0	0.01	0.86	2008-03-05	19.8	0	0
2003-03-06	1.2	0	0	2004-03-06	12	0.21	18.06	2005-03-06	0	0	0	2006-03-06	0	0	0	2008-03-06	3.8	0	0
2003-03-07	0.2	0	0	2004-03-07	0.4	0	0	2005-03-07	0	0.01	0.86	2006-03-07	0	0	0	2008-03-07	0	0	0
2003-03-08	0.4	0	0	2004-03-08	10.2	0	0	2005-03-08	5.4	0.02	1.72	2006-03-08	0	0.01	0.86	2008-03-08	4.8	0	0
2003-03-09	15.7	0.04	3.44	2004-03-09	0.4	0	0	2005-03-09	1.8	0	0	2006-03-09	31.8	0.17	14.62	2008-03-09	27.8	0	0
2003-03-10	0	0.05	4.3	2004-03-10	0	0	0	2005-03-10	0.8	0	0	2006-03-10	10.3	0.2	17.2	2008-03-10	0	0	0
2003-03-11	0	0	0	2004-03-11	0	0	0	2005-03-11	2.4	0	0	2006-03-11	1.4	0	0	2008-03-11	0	0	0
2003-03-12	1	0	0	2004-03-12	8.6	0.02	1.72	2005-03-12	2.6	0	0	2006-03-12	5.2	0	0	2008-03-12	5.6	0	0
2003-03-13	6.2	0	0	2004-03-13	4.6	0	0	2005-03-13	1.8	0	0	2006-03-13	12.8	0.08	6.88	2008-03-13	0.4	0	0
2003-03-14	3	0	0	2004-03-14	0	0	0	2005-03-14	0	0	0	2006-03-14	8.9	0	0	2008-03-14	0.2	0.01	0.86
2003-03-15	0	0.01	0.86	2004-03-15	3.8	0.06	5.16	2005-03-15	0	0	0	2006-03-15	1.6	0	0	2008-03-15	0	0.02	1.72
2003-03-16	0	0.01	0.86	2004-03-16	0	0	0	2005-03-16	0	0	0	2006-03-16	0	0	0	2008-03-16	0	0.01	0.86
2003-03-17	0	0.02	1.72	2004-03-17	8	0	0	2005-03-17	0	0	0	2006-03-17	0	0.01	0.86	2008-03-17	0	0	0
2003-03-18	0	0.04	3.44	2004-03-18	1.2	0	0	2005-03-18	0	0	0	2006-03-18	0	0	0	2008-03-18	2.4	0.02	1.72
2003-03-19	0	0.17	14.62	2004-03-19	0	0	0	2005-03-19	0	0	0	2006-03-19	0.2	0	0	2008-03-19	12.2	0.16	13.76
2003-03-20	1.2	0.1	8.6	2004-03-20	5.3	0.02	1.72	2005-03-20	4.8	0	0	2006-03-20	0.4	0	0	2008-03-20	1.4	0	0
2003-03-21	0.4	0.08	6.88	2004-03-21	6.4	0.06	5.16	2005-03-21	3.8	0	0	2006-03-21	0	0	0	2008-03-21	0.4	0	0
2003-03-22	3.5	0.04	3.44	2004-03-22	1.2	0	0	2005-03-22	0	0.03	2.58	2006-03-22	0.8	0	0	2008-03-22	0	0	0
2003-03-23	2	0	0	2004-03-23	0	0	0	2005-03-23	0	0.02	1.72	2006-03-23	0.4	0	0	2008-03-23	0	0	0
2003-03-24	0	0	0	2004-03-24	1.4	0	0	2005-03-24	4.8	0	0	2006-03-24	0	0	0	2008-03-24	1.4	0	0
2003-03-25	0.8	0.02	1.72	2004-03-25	7.9	0.07	6.02	2005-03-25	0	0.02	1.72	2006-03-25	7.4	0	0	2008-03-25	0	0.02	1.72
2003-03-26	2.1	0.01	0.86	2004-03-26	6.5	0.01	0.86	2005-03-26	0	0.02	1.72	2006-03-26	2.7	0.02	1.72	2008-03-26	5.2	0.01	0.86
2003-03-27	0	0	0	2004-03-27	4.9	0.02	1.72	2005-03-27	0	0.03	2.58	2006-03-27	0	0	0	2008-03-27	0	0.02	1.72
2003-03-28	0	0.01	0.86	2004-03-28	0	0	0	2005-03-28	0	0.02	1.72	2006-03-28	0	0	0	2008-03-28	5.8	0.01	0.86
2003-03-29	12.8	0	0	2004-03-29	0	0	0	2005-03-29	0	0.16	13.76	2006-03-29	0	0	0	2008-03-29	0.2	0	0
2003-03-30	1.8	0.06	5.16	2004-03-30	12.8	0.01	0.86	2005-03-30	0	0.03	2.58	2006-03-30	0	0	0	2008-03-30	0	0	0
2003-03-31	0.4	0	0	2004-03-31	10.3	0.06	5.16	2005-03-31	0	0.03	2.58	2006-03-31	0	0.01	0.86	2008-03-31	4.4	0.09	7.74
2003-04-01	4.2	0	0	2004-04-01	2	0	0	2005-04-01	0.3	0	0	2006-04-01	4.9	0	0	2008-04-01	14.2	0.05	4.3
2003-04-02	4.3	0.01	0.86	2004-04-02	3.1	0	0	2005-04-02	4.8	0	0	2006-04-02	0.4	0	0	2008-04-02	0.8	0	0
2003-04-03	0	0	0	2004-04-03	0.3	0	0	2005-04-03	14.7	0.02	1.72	2006-04-03	1.6	0.01	0.86	2008-04-03	0	0	0
2003-04-04	32.6	0	0	2004-04-04	1.8	0	0	2005-04-04	3.2	0	0	2006-04-04	1.2	0	0	2008-04-04	7.3	0	0
2003-04-05	18	0.05	4.3	2004-04-05	0	0	0	2005-04-05	0	0	0	2006-04-05	4.2	0	0	2008-04-05	2.8	0	0
2003-04-06	2	0	0	2004-04-06	0	0	0	2005-04-06	0	0	0	2006-04-06	1.4	0	0	2008-04-06	0	0	0
2003-04-07	0	0.01	0.86	2004-04-07	0.8	0	0	2005-04-07	0.4	0	0	2006-04-07	1.7	0	0	2008-04-07	0	0	0
2003-04-08	4.8	0	0	2004-04-08	0	0	0	2005-04-08	2	0	0	2006-04-08	13	0.03	2.58	2008-04-08	0	0	0
2003-04-09	0	0.01	0.86	2004-04-09	0.6	0	0	2005-04-09	0	0	0	2006-04-09	0	0	0	2008-04-09	4.9	0	0
2003-04-10	0	0.01	0.86	2004-04-10	0	0	0	2005-04-10	0	0	0	2006-04-10	0	0	0	2008-04-10	0	0	0
2003-04-11	0	0.05	4.3	2004-04-11	0	0	0	2005-04-11	0	0	0	2006-04-11	0	0	0	2008-04-11	8.2	0.01	0.86
2003-04-12	0	0.05	4.3	2004-04-12	0	0	0	2005-04-12	0	0	0	2006-04-12	1	0.01	0.86	2008-04-12	14.8	0	0
2003-04-13	0	0	0	2004-04-13	6.8	0.03	2.58	2005-04-13	0	0	0	2006-04-13	13.8	0.07	6.02	2008-04-13	8.4	0	0
2003-04-14	0	0	0	2004-04-14	0.4	0	0	2005-04-14	0	0	0	2006-04-14	2.4	0	0	2008-04-14	0.6	0	0
2003-04-15	0	0	0	2004-04-15	0	0	0	2005-04-15	0	0	0	2006-04-15	0	0	0	2008-04-15	0	0	0
2003-04-16	0	0	0	2004-04-16	0	0	0	2005-04-16	0	0	0	2006-04-16	0	0	0	2008-04-16	0	0	0
2003-04-17	0.4	0	0	2004-04-17	0	0	0	2005-04-17	0	0	0	2006-04-17	0	0	0	2008-04-17	0	0	0
2003-04-18	1	0	0	2004-04-18	0	0	0	2005-04-18	0	0	0	2006-04-18	0	0	0	2008-04-18	0	0	0
2003-04-19	0	0	0	2004-04-19	3.8	0.02	1.72	2005-04-19	0	0	0	2006-04-19	0	0.01	0.86	2008-04-19	0	0.02	1.72
2003-04-20	0	0	0	2004-04-20	0.8	0	0	2005-04-20	0	0	0	2006-04-20	0	0	0	2008-04-20	0	0	0
2003-04-21	3.5	0	0	2004-04-21	7.4	0	0	2005-04-21	9.9	0.03	2.58	2006-04-21	0	0	0	2008-04-21	0	0	0
2003-04-22	2.4	0	0	2004-04-22	16.7	0.15	12.9	2005-04-22	0	0	0	2006-04-22	4.2	0.01	0.86	2008-04-22	0	0	0
2003-04-23	0.9	0	0	2004-04-23	0	0	0	2005-04-23	6.6	0.02	1.72	2006-04-23	13.2	0.03	2.58	2008-04-23	0	0	0
2003-04-24	0	0	0	2004-04-24	0	0	0	2005-04-24	32	0.15	12.9	2006-04-24	35.3	0.2	17.2	2008-04-24	0	0	0
2003-04-25	0	0	0	2004-04-25	0.6	0	0	2005-04-25	4.8	0	0	2006-04-25	0	0	0	2008-04-25	0	0	0
2003-04-26	0	0	0	2004-04-26	9.9	0.04	3.44	2005-04-26	1	0	0	2006-04-26	0	0	0	2008-04-26	1	0	0
2003-04-27	0	0	0	2004-04-27	0.4	0	0	2005-04-27	13	0.06	5.16	2006-04-27	0	0	0	2008-04-27	0.6	0	0
2003-04-28	0	0	0	2004-04-28	0	0	0	2005-04-28	3.4	0	0	2006-04-28	0	0	0	2008-04-28	5.3	0	0
2003-04-29	0.6	0	0	2004-04-29	6	0.01	0.86	2005-04-29	0.7	0	0	2006-04-29	0	0	0	2008-04-29	0.5	0	0
2003-04-30	0	0	0	2004-04-30	0	0	0	2005-04-30	0.7	0	0	2006-04-30	0	0	0	2008-04-30	0	0	0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-05-01	36.3	0.03	2.58	2004-05-01	5.9	0.01	0.86	2005-05-01	0	0	0	2006-05-01	0	0	0	2008-05-01	0	0	0
2003-05-02	14.7	0.14	12.04	2004-05-02	14.6	0	0	2005-05-02	1.1	0	0	2006-05-02	0	0	0	2008-05-02	1.2	0	0
2003-05-03	0	0.05	4.3	2004-05-03	8.2	0.1	8.6	2005-05-03	4.5	0	0	2006-05-03	0	0	0	2008-05-03	7.5	0.03	2.58
2003-05-04	0	0	0	2004-05-04	0	0	0	2005-05-04	1.4	0	0	2006-05-04	0	0	0	2008-05-04	11.4	0.03	2.58
2003-05-05	0	0	0	2004-05-05	5.9	0	0	2005-05-05	0	0	0	2006-05-05	0.2	0	0	2008-05-05	0	0	0
2003-05-06	14	0.05	4.3	2004-05-06	0	0	0	2005-05-06	0	0	0	2006-05-06	0.4	0	0	2008-05-06	0	0	0
2003-05-07	0	0	0	2004-05-07	4.2	0	0	2005-05-07	2.7	0	0	2006-05-07	0	0	0	2008-05-07	0	0	0
2003-05-08	0.2	0	0	2004-05-08	0	0	0	2005-05-08	0.2	0	0	2006-05-08	0	0	0	2008-05-08	10.4	0.05	4.3
2003-05-09	0	0	0	2004-05-09	21.2	0.03	2.58	2005-05-09	0	0	0	2006-05-09	0	0	0	2008-05-09	0	0	0
2003-05-10	2	0	0	2004-05-10	10.9	0.09	7.74	2005-05-10	0	0	0	2006-05-10	0	0	0	2008-05-10	0	0	0
2003-05-11	15	0.01	0.86	2004-05-11	35.5	0.2	17.2	2005-05-11	1	0	0	2006-05-11	15.6	0.07	6.02	2008-05-11	0	0	0
2003-05-12	8.1	0.02	1.72	2004-05-12	0	0	0	2005-05-12	0	0	0	2006-05-12	8.3	0.11	9.46	2008-05-12	10.3	0	0
2003-05-13	2.5	0	0	2004-05-13	0	0	0	2005-05-13	0	0	0	2006-05-13	6	0	0	2008-05-13	1.4	0	0
2003-05-14	0.4	0	0	2004-05-14	2.2	0	0	2005-05-14	14.6	0.05	4.3	2006-05-14	1.4	0	0	2008-05-14	0	0	0
2003-05-15	0	0	0	2004-05-15	3	0.03	2.58	2005-05-15	3	0	0	2006-05-15	0.2	0.01	0.86	2008-05-15	5.8	0.02	1.72
2003-05-16	1.9	0	0	2004-05-16	0	0	0	2005-05-16	0.3	0	0	2006-05-16	12.4	0.03	2.58	2008-05-16	0	0	0
2003-05-17	10.3	0.04	3.44	2004-05-17	0	0	0	2005-05-17	0	0	0	2006-05-17	0.4	0	0	2008-05-17	1.8	0	0
2003-05-18	0	0	0	2004-05-18	3.3	0	0	2005-05-18	0	0	0	2006-05-18	10.4	0	0	2008-05-18	2.9	0	0
2003-05-19	0	0	0	2004-05-19	0.4	0	0	2005-05-19	0	0	0	2006-05-19	3.6	0.01	0.86	2008-05-19	11.1	0.05	4.3
2003-05-20	0	0	0	2004-05-20	0	0	0	2005-05-20	0	0	0	2006-05-20	0.9	0	0	2008-05-20	0.2	0	0
2003-05-21	6.2	0.01	0.86	2004-05-21	21.6	0.08	6.88	2005-05-21	0	0	0	2006-05-21	3.8	0	0	2008-05-21	0	0	0
2003-05-22	0	0	0	2004-05-22	7.5	0	0	2005-05-22	0.5	0	0	2006-05-22	0.8	0	0	2008-05-22	6.2	0.01	0.86
2003-05-23	0	0	0	2004-05-23	42.4	0.13	11.18	2005-05-23	1.3	0	0	2006-05-23	0	0	0	2008-05-23	0	0	0
2003-05-24	20	0.07	6.02	2004-05-24	17	0.05	4.3	2005-05-24	0.4	0	0	2006-05-24	0	0	0	2008-05-24	0	0	0
2003-05-25	0.6	0.01	0.86	2004-05-25	0	0	0	2005-05-25	1	0	0	2006-05-25	0	0	0	2008-05-25	0	0	0
2003-05-26	0	0	0	2004-05-26	3	0	0	2005-05-26	0	0	0	2006-05-26	0.7	0	0	2008-05-26	0	0	0
2003-05-27	0	0	0	2004-05-27	0.4	0	0	2005-05-27	0.6	0	0	2006-05-27	0.4	0	0	2008-05-27	0.6	0	0
2003-05-28	2.7	0	0	2004-05-28	0.3	0	0	2005-05-28	13.1	0.03	2.58	2006-05-28	0	0	0	2008-05-28	0	0	0
2003-05-29	0	0	0	2004-05-29	0	0	0	2005-05-29	30.8	0.04	3.44	2006-05-29	0	0	0	2008-05-29	0	0	0
2003-05-30	0	0	0	2004-05-30	0	0	0	2005-05-30	0	0	0	2006-05-30	0	0	0	2008-05-30	0	0	0
2003-05-31	2	0	0	2004-05-31	0	0	0	2005-05-31	0	0	0	2006-05-31	0	0	0	2008-05-31	19.9	0.05	4.3
2003-06-01	4.3	0	0	2004-06-01	1.8	0	0	2005-06-01	0	0	0	2006-06-01	18.2	0.07	6.02	2008-06-01	10.4	0.08	6.88
2003-06-02	0	0	0	2004-06-02	2.8	0	0	2005-06-02	0	0	0	2006-06-02	0	0	0	2008-06-02	0	0	0
2003-06-03	0	0	0	2004-06-03	8.2	0.01	0.86	2005-06-03	0	0	0	2006-06-03	2.6	0.05	4.3	2008-06-03	7.1	0	0
2003-06-04	0	0	0	2004-06-04	0	0	0	2005-06-04	0.2	0	0	2006-06-04	30	0.03	2.58	2008-06-04	6.1	0.01	0.86
2003-06-05	7.2	0	0	2004-06-05	0	0	0	2005-06-05	0	0	0	2006-06-05	0	0	0	2008-06-05	0.4	0	0
2003-06-06	1	0	0	2004-06-06	0	0	0	2005-06-06	4.8	0	0	2006-06-06	0	0	0	2008-06-06	0	0	0
2003-06-07	0	0	0	2004-06-07	0	0	0	2005-06-07	0	0	0	2006-06-07	0	0	0	2008-06-07	0	0	0
2003-06-08	0	0	0	2004-06-08	0	0	0	2005-06-08	0	0	0	2006-06-08	0.3	0	0	2008-06-08	1.6	0	0
2003-06-09	8.6	0.03	2.58	2004-06-09	0	0	0	2005-06-09	0	0	0	2006-06-09	0	0	0	2008-06-09	2.6	0.02	1.72
2003-06-10	0	0	0	2004-06-10	7.5	0.03	2.58	2005-06-10	0	0	0	2006-06-10	0	0	0	2008-06-10	18.4	0.06	5.16
2003-06-11	0.6	0	0	2004-06-11	7	0.02	1.72	2005-06-11	0	0	0	2006-06-11	0	0	0	2008-06-11	1	0.01	0.86
2003-06-12	0.9	0	0	2004-06-12	0	0	0	2005-06-12	0	0	0	2006-06-12	0	0	0	2008-06-12	0	0	0
2003-06-13	20.1	0.08	6.88	2004-06-13	0	0	0	2005-06-13	1.1	0	0	2006-06-13	0	0	0	2008-06-13	0	0	0
2003-06-14	0	0	0	2004-06-14	7.8	0.06	5.16	2005-06-14	11.8	0.02	1.72	2006-06-14	0	0	0	2008-06-14	0.8	0	0
2003-06-15	0	0	0	2004-06-15	16.1	0	0	2005-06-15	2.6	0	0	2006-06-15	0	0	0	2008-06-15	0.2	0	0
2003-06-16	0	0	0	2004-06-16	0	0	0	2005-06-16	10.6	0.02	1.72	2006-06-16	0	0	0	2008-06-16	4.7	0.01	0.86
2003-06-17	0	0	0	2004-06-17	9.9	0	0	2005-06-17	1.3	0	0	2006-06-17	0	0	0	2008-06-17	0	0	0
2003-06-18	0	0	0	2004-06-18	4.8	0.02	1.72	2005-06-18	0	0	0	2006-06-18	0	0	0	2008-06-18	5.2	0.01	0.86
2003-06-19	8	0	0	2004-06-19	6.2	0	0	2005-06-19	0.2	0	0	2006-06-19	5.2	0	0	2008-06-19	0	0	0
2003-06-20	0	0.01	0.86	2004-06-20	0	0	0	2005-06-20	0	0	0	2006-06-20	1.7	0	0	2008-06-20	2.2	0	0
2003-06-21	0	0	0	2004-06-21	0	0	0	2005-06-21	0	0	0	2006-06-21	0.2	0	0	2008-06-21	0	0	0
2003-06-22	0	0	0	2004-06-22	2.6	0	0	2005-06-22	1.2	0	0	2006-06-22	9.4	0.01	0.86	2008-06-22	2.2	0	0
2003-06-23	0	0	0	2004-06-23	0	0	0	2005-06-23	0	0	0	2006-06-23	0.4	0	0	2008-06-23	0	0	0
2003-06-24	0	0	0	2004-06-24	0.3	0	0	2005-06-24	0	0	0	2006-06-24	0	0	0	2008-06-24	9	0.06	5.16
2003-06-25	0	0	0	2004-06-25	3.4	0	0	2005-06-25	0	0	0	2006-06-25	0	0	0	2008-06-25	0	0	0
2003-06-26	0	0	0	2004-06-26	0	0	0	2005-06-26	0	0	0	2006-06-26	0	0	0	2008-06-26	1.1	0	0
2003-06-27	7.4	0	0	2004-06-27	0	0	0	2005-06-27	0	0	0	2006-06-27	0.7	0	0	2008-06-27	7.6	0.03	2.58
2003-06-28	0	0	0	2004-06-28	2.2	0	0	2005-06-28	0	0	0	2006-06-28	0	0	0	2008-06-28	19.3	0	0
2003-06-29	0.4	0	0	2004-06-29	0	0	0	2005-06-29	0.3	0	0	2006-06-29	0	0	0	2008-06-29	1	0.06	5.16
2003-06-30	1.8	0.02	1.72	2004-06-30	0	0	0	2005-06-30	0	0	0	2006-06-30	0	0	0	2008-06-30	6.5	0	0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-07-01	0	0	0	2004-07-01	0	0	0	2005-07-01	0,2	0	0	2006-07-01	0,2	0	0	2008-07-01	1,4	0	0
2003-07-02	0	0	0	2004-07-02	0	0	0	2005-07-02	0	0	0	2006-07-02	0	0	0	2008-07-02	0	0,05	4,3
2003-07-03	0	0	0	2004-07-03	0	0	0	2005-07-03	0	0	0	2006-07-03	3,8	0	0	2008-07-03	5,2	0	0
2003-07-04	0,6	0	0	2004-07-04	0	0	0	2005-07-04	0	0	0	2006-07-04	2,4	0	0	2008-07-04	0,4	0	0
2003-07-05	21	0,03	2,58	2004-07-05	1,3	0	0	2005-07-05	0	0	0	2006-07-05	1	0	0	2008-07-05	0	0	0
2003-07-06	0	0	0	2004-07-06	0,5	0	0	2005-07-06	1,5	0	0	2006-07-06	0	0	0	2008-07-06	0	0	0
2003-07-07	1	0	0	2004-07-07	0,8	0	0	2005-07-07	2,4	0	0	2006-07-07	0	0	0	2008-07-07	0	0	0
2003-07-08	1,8	0	0	2004-07-08	4,2	0	0	2005-07-08	8,6	0	0	2006-07-08	0	0	0	2008-07-08	0	0	0
2003-07-09	4,1	0	0	2004-07-09	0,9	0	0	2005-07-09	2	0	0	2006-07-09	0	0	0	2008-07-09	4,2	0	0
2003-07-10	0	0	0	2004-07-10	0	0	0	2005-07-10	0	0	0	2006-07-10	18	0	0	2008-07-10	0	0	0
2003-07-11	6,5	0,02	1,72	2004-07-11	0	0	0	2005-07-11	0	0	0	2006-07-11	0	0,02	1,72	2008-07-11	0	0	0
2003-07-12	1,6	0	0	2004-07-12	3	0	0	2005-07-12	0	0	0	2006-07-12	29,4	0,03	2,58	2008-07-12	0	0	0
2003-07-13	0,4	0	0	2004-07-13	0,4	0	0	2005-07-13	0	0	0	2006-07-13	3	0,05	4,3	2008-07-13	2,8	0	0
2003-07-14	0	0	0	2004-07-14	2,9	0	0	2005-07-14	0	0	0	2006-07-14	0	0	0	2008-07-14	0	0	0
2003-07-15	0	0	0	2004-07-15	6,1	0,01	0,86	2005-07-15	0,2	0	0	2006-07-15	4,4	0	0	2008-07-15	0	0	0
2003-07-16	3	0	0	2004-07-16	1,8	0	0	2005-07-16	0,4	0	0	2006-07-16	0	0	0	2008-07-16	0	0	0
2003-07-17	0	0	0	2004-07-17	0	0	0	2005-07-17	2,3	0	0	2006-07-17	0	0	0	2008-07-17	0,7	0	0
2003-07-18	0	0	0	2004-07-18	1,6	0	0	2005-07-18	14,3	0,07	6,02	2006-07-18	1	0	0	2008-07-18	0	0	0
2003-07-19	0	0	0	2004-07-19	0	0	0	2005-07-19	7,2	0,03	2,58	2006-07-19	0	0	0	2008-07-19	0	0	0
2003-07-20	0,2	0	0	2004-07-20	0	0	0	2005-07-20	0	0	0	2006-07-20	0	0	0	2008-07-20	31,7	0,1	8,6
2003-07-21	0,3	0,05	4,3	2004-07-21	11,6	0	0	2005-07-21	0	0	0	2006-07-21	6,8	0	0	2008-07-21	5,2	0,02	1,72
2003-07-22	18,5	0,03	2,58	2004-07-22	9,9	0	0	2005-07-22	0,2	0	0	2006-07-22	0	0	0	2008-07-22	2,4	0	0
2003-07-23	0	0	0	2004-07-23	6,6	0	0	2005-07-23	0,4	0	0	2006-07-23	2,8	0,01	0,86	2008-07-23	3	0	0
2003-07-24	0	0	0	2004-07-24	0	0	0	2005-07-24	0	0	0	2006-07-24	5,7	0	0	2008-07-24	0,8	0	0
2003-07-25	0	0	0	2004-07-25	0	0	0	2005-07-25	8	0,01	0,86	2006-07-25	0	0	0	2008-07-25	0	0	0
2003-07-26	0	0	0	2004-07-26	0	0	0	2005-07-26	0	0	0	2006-07-26	16,8	0,04	3,44	2008-07-26	0	0	0
2003-07-27	0,4	0	0	2004-07-27	6	0	0	2005-07-27	15,1	0	0	2006-07-27	9,2	0,02	1,72	2008-07-27	1,2	0	0
2003-07-28	8,4	0	0	2004-07-28	7,3	0,03	2,58	2005-07-28	1,2	0,02	1,72	2006-07-28	19	0,04	3,44	2008-07-28	1,4	0	0
2003-07-29	0	0	0	2004-07-29	0,4	0	0	2005-07-29	0	0	0	2006-07-29	0	0,01	0,86	2008-07-29	0	0	0
2003-07-30	0	0	0	2004-07-30	0	0	0	2005-07-30	0	0	0	2006-07-30	0,2	0	0	2008-07-30	0	0	0
2003-07-31	0,8	0	0	2004-07-31	22	0,02	1,72	2005-07-31	0	0	0	2006-07-31	9,3	0	0	2008-07-31	12,2	0,03	2,58
2003-08-01	0	0	0	2004-08-01	1	0,04	3,44	2005-08-01	0	0	0	2006-08-01	0	0	0	2008-08-01	0	0	0
2003-08-02	1,8	0	0	2004-08-02	0	0	0	2005-08-02	0	0	0	2006-08-02	0	0	0	2008-08-02	17,7	0	0
2003-08-03	1,3	0	0	2004-08-03	4,2	0	0	2005-08-03	0	0	0	2006-08-03	33,2	0,12	10,32	2008-08-03	21,1	0,04	3,44
2003-08-04	2,2	0	0	2004-08-04	1,2	0	0	2005-08-04	0	0	0	2006-08-04	20,6	0,15	12,9	2008-08-04	0	0	0
2003-08-05	0,2	0	0	2004-08-05	10,6	0,04	3,44	2005-08-05	18,5	0	0	2006-08-05	0	0	0	2008-08-05	1,4	0	0
2003-08-06	1,5	0	0	2004-08-06	0	0	0	2005-08-06	0	0	0	2006-08-06	0	0	0	2008-08-06	0,4	0	0
2003-08-07	0	0	0	2004-08-07	0	0	0	2005-08-07	0	0	0	2006-08-07	0	0	0	2008-08-07	0,6	0	0
2003-08-08	0	0	0	2004-08-08	0	0	0	2005-08-08	0	0	0	2006-08-08	0	0	0	2008-08-08	1,9	0	0
2003-08-09	0	0	0	2004-08-09	0	0	0	2005-08-09	0	0	0	2006-08-09	0	0	0	2008-08-09	0	0	0
2003-08-10	2	0	0	2004-08-10	0	0,01	0,86	2005-08-10	0	0	0	2006-08-10	0	0	0	2008-08-10	41,8	0,08	6,88
2003-08-11	0	0	0	2004-08-11	0,4	0	0	2005-08-11	31,8	0,07	6,02	2006-08-11	0	0	0	2008-08-11	13,8	0,07	6,02
2003-08-12	2	0	0	2004-08-12	0,7	0	0	2005-08-12	1,2	0	0	2006-08-12	0	0	0	2008-08-12	0	0,01	0,86
2003-08-13	0,4	0	0	2004-08-13	1	0	0	2005-08-13	15,2	0,04	3,44	2006-08-13	0	0	0	2008-08-13	0	0	0
2003-08-14	0	0	0	2004-08-14	5,6	0,01	0,86	2005-08-14	5,2	0	0	2006-08-14	0	0	0	2008-08-14	0,4	0	0
2003-08-15	0	0	0	2004-08-15	0	0	0	2005-08-15	1,2	0,02	1,72	2006-08-15	2,1	0	0	2008-08-15	0	0	0
2003-08-16	0,9	0,01	0,86	2004-08-16	0	0	0	2005-08-16	0	0	0	2006-08-16	0	0	0	2008-08-16	0	0	0
2003-08-17	10	0	0	2004-08-17	0	0	0	2005-08-17	0	0,01	0,86	2006-08-17	0	0	0	2008-08-17	0	0	0
2003-08-18	0	0	0	2004-08-18	1	0	0	2005-08-18	0	0	0	2006-08-18	0	0	0	2008-08-18	0	0	0
2003-08-19	0	0	0	2004-08-19	2,2	0	0	2005-08-19	8	0	0	2006-08-19	0	0	0	2008-08-19	10,1	0	0
2003-08-20	0	0	0	2004-08-20	0	0	0	2005-08-20	0,4	0	0	2006-08-20	9,3	0,03	2,58	2008-08-20	0	0	0
2003-08-21	0	0	0	2004-08-21	1,2	0	0	2005-08-21	1,8	0	0	2006-08-21	0,2	0	0	2008-08-21	0	0	0
2003-08-22	1,8	0	0	2004-08-22	0	0	0	2005-08-22	0	0	0	2006-08-22	0	0	0	2008-08-22	0	0	0
2003-08-23	0	0	0	2004-08-23	0	0	0	2005-08-23	2,1	0	0	2006-08-23	0	0	0	2008-08-23	0	0	0
2003-08-24	0	0	0	2004-08-24	0	0	0	2005-08-24	0	0	0	2006-08-24	2,5	0	0	2008-08-24	0	0	0
2003-08-25	0	0	0	2004-08-25	0,6	0	0	2005-08-25	0	0	0	2006-08-25	6,8	0	0	2008-08-25	5,4	0	0
2003-08-26	0	0	0	2004-08-26	6,8	0	0	2005-08-26	0	0	0	2006-08-26	0	0,01	0,86	2008-08-26	0	0	0
2003-08-27	2,2	0	0	2004-08-27	2,9	0	0	2005-08-27	0	0	0	2006-08-27	5,6	0	0	2008-08-27	0	0	0
2003-08-28	0	0	0	2004-08-28	2,1	0,01	0,86	2005-08-28	1,8	0	0	2006-08-28	1	0,01	0,86	2008-08-28	0,8	0	0
2003-08-29	0	0	0	2004-08-29	2,3	0,02	1,72	2005-08-29	0	0	0	2006-08-29	9,9	0,01	0,86	2008-08-29	3,8	0	0
2003-08-30	3,5	0	0	2004-08-30	8,6	0,03	2,58	2005-08-30	0	0	0	2006-08-30	0,4	0	0	2008-08-30	0	0	0
2003-08-31	0	0	0	2004-08-31	0	0	0	2005-08-31	10,2	0	0	2006-08-31	0	0	0	2008-08-31	0	0	0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-09-01	3,2	0,01	0,86	2004-09-01	0	0	0	2005-09-01	0	0	0	2006-09-01	0	0	0	2008-09-01	0	0	0
2003-09-02	1,2	0	0	2004-09-02	0	0	0	2005-09-02	0	0	0	2006-09-02	0	0	0	2008-09-02	0	0	0
2003-09-03	0	0	0	2004-09-03	0	0	0	2005-09-03	0	0	0	2006-09-03	16,1	0,04	3,44	2008-09-03	0	0	0
2003-09-04	0	0	0	2004-09-04	0	0	0	2005-09-04	0	0	0	2006-09-04	0	0,01	0,86	2008-09-04	0	0	0
2003-09-05	0	0	0	2004-09-05	0	0	0	2005-09-05	0	0	0	2006-09-05	0	0	0	2008-09-05	1,4	0	0
2003-09-06	0	0	0	2004-09-06	0	0	0	2005-09-06	0	0	0	2006-09-06	0	0	0	2008-09-06	1,3	0,01	0,86
2003-09-07	0	0	0	2004-09-07	0,8	0	0	2005-09-07	0	0	0	2006-09-07	2	0	0	2008-09-07	0	0	0
2003-09-08	0	0	0	2004-09-08	5,6	0	0	2005-09-08	0,8	0	0	2006-09-08	0	0	0	2008-09-08	23,4	0,04	3,44
2003-09-09	0	0	0	2004-09-09	18,6	0	0	2005-09-09	2,4	0	0	2006-09-09	1,4	0	0	2008-09-09	15,8	0,01	0,86
2003-09-10	0	0	0	2004-09-10	0	0,04	3,44	2005-09-10	0	0	0	2006-09-10	1,4	0	0	2008-09-10	0	0,01	0,86
2003-09-11	0	0	0	2004-09-11	0	0	0	2005-09-11	0	0	0	2006-09-11	0	0	0	2008-09-11	0	0	0
2003-09-12	0	0	0	2004-09-12	0	0	0	2005-09-12	0	0	0	2006-09-12	1	0	0	2008-09-12	2,4	0	0
2003-09-13	0	0	0	2004-09-13	0	0	0	2005-09-13	0	0	0	2006-09-13	30,6	0,08	6,88	2008-09-13	3,5	0,01	0,86
2003-09-14	0	0	0	2004-09-14	0	0	0	2005-09-14	0	0	0	2006-09-14	55,4	0,17	14,62	2008-09-14	26,7	0,07	6,02
2003-09-15	11,6	0	0	2004-09-15	0	0	0	2005-09-15	24	0,02	1,72	2006-09-15	0	0,01	0,86	2008-09-15	18,6	0,06	5,16
2003-09-16	11,7	0,01	0,86	2004-09-16	0	0	0	2005-09-16	7,8	0	0	2006-09-16	0	0	0	2008-09-16	0,2	0,03	2,58
2003-09-17	0	0,01	0,86	2004-09-17	0	0	0	2005-09-17	8,3	0,02	1,72	2006-09-17	0	0	0	2008-09-17	0	0	0
2003-09-18	0	0	0	2004-09-18	0	0	0	2005-09-18	0	0,01	0,86	2006-09-18	0	0	0	2008-09-18	0	0	0
2003-09-19	9,8	0,01	0,86	2004-09-19	0	0,01	0,86	2005-09-19	0	0	0	2006-09-19	30,3	0,11	9,46	2008-09-19	0	0	0
2003-09-20	19,3	0,02	1,72	2004-09-20	0	0	0	2005-09-20	0	0	0	2006-09-20	0	0	0	2008-09-20	0	0	0
2003-09-21	0	0,01	0,86	2004-09-21	0	0	0	2005-09-21	0	0	0	2006-09-21	2,4	0	0	2008-09-21	0	0	0
2003-09-22	0,2	0,03	2,58	2004-09-22	0	0	0	2005-09-22	0	0	0	2006-09-22	0	0	0	2008-09-22	0	0	0
2003-09-23	31,2	0,03	2,58	2004-09-23	0	0	0	2005-09-23	27,2	0,06	5,16	2006-09-23	8	0,02	1,72	2008-09-23	0	0	0
2003-09-24	0	0,03	2,58	2004-09-24	0	0	0	2005-09-24	0	0	0	2006-09-24	2,7	0	0	2008-09-24	0	0	0
2003-09-25	7,8	0	0	2004-09-25	0	0	0	2005-09-25	6	0,01	0,86	2006-09-25	2,2	0	0	2008-09-25	0	0	0
2003-09-26	0	0,01	0,86	2004-09-26	0	0	0	2005-09-26	11,3	0	0	2006-09-26	4	0	0	2008-09-26	0	0	0
2003-09-27	22,8	0,03	2,58	2004-09-27	0	0	0	2005-09-27	2,4	0,02	1,72	2006-09-27	0	0	0	2008-09-27	0	0	0
2003-09-28	2,1	0,02	1,72	2004-09-28	0	0	0	2005-09-28	0	0,01	0,86	2006-09-28	12,4	0,03	2,58	2008-09-28	0	0	0
2003-09-29	0	0,01	0,86	2004-09-29	0	0	0	2005-09-29	17	0	0	2006-09-29	0	0	0	2008-09-29	0	0	0
2003-09-30	0	0,01	0,86	2004-09-30	0	0	0	2005-09-30	1,8	0,03	2,58	2006-09-30	2,2	0	0	2008-09-30	3,2	0,06	5,16
2003-10-01	1,5	0,02	1,72	2004-10-01	0	0	0	2005-10-01	0	0,01	0,86	2006-10-01	12,3	0,07	6,02	2008-10-01	2,9	0	0
2003-10-02	2,9	0	0	2004-10-02	0,4	0	0	2005-10-02	0	0	0	2006-10-02	0	0	0	2008-10-02	14,1	0,02	1,72
2003-10-03	1	0	0	2004-10-03	3,8	0,01	0,86	2005-10-03	0	0,01	0,86	2006-10-03	1	0	0	2008-10-03	9,5	0,04	3,44
2003-10-04	8,6	0,01	0,86	2004-10-04	0	0	0	2005-10-04	0	0	0	2006-10-04	25,7	0,04	3,44	2008-10-04	1,6	0	0
2003-10-05	1	0,01	0,86	2004-10-05	0	0,01	0,86	2005-10-05	0	0,01	0,86	2006-10-05	26,8	0,18	15,48	2008-10-05	0	0	0
2003-10-06	0	0,01	0,86	2004-10-06	0	0	0	2005-10-06	0	0	0	2006-10-06	0	0	0	2008-10-06	0	0	0
2003-10-07	0	0	0	2004-10-07	0	0	0	2005-10-07	0	0	0	2006-10-07	0	0	0	2008-10-07	0	0	0
2003-10-08	0	0,01	0,86	2004-10-08	0	0	0	2005-10-08	1,7	0,01	0,86	2006-10-08	0	0	0	2008-10-08	0	0	0
2003-10-09	0	0	0	2004-10-09	0,6	0	0	2005-10-09	0	0	0	2006-10-09	0	0	0	2008-10-09	10,4	0,04	3,44
2003-10-10	0	0,01	0,86	2004-10-10	0	0	0	2005-10-10	0	0,01	0,86	2006-10-10	0	0	0	2008-10-10	0	0	0
2003-10-11	0	0	0	2004-10-11	0	0	0	2005-10-11	0	0	0	2006-10-11	18,2	0,03	2,58	2008-10-11	0	0	0
2003-10-12	0	0	0	2004-10-12	0	0	0	2005-10-12	0	0	0	2006-10-12	7,4	0,09	7,74	2008-10-12	0	0	0
2003-10-13	0,3	0	0	2004-10-13	0	0	0	2005-10-13	1,3	0	0	2006-10-13	4,2	0	0	2008-10-13	0	0	0
2003-10-14	0	0	0	2004-10-14	0,2	0	0	2005-10-14	0	0	0	2006-10-14	1,2	0	0	2008-10-14	0	0	0
2003-10-15	33,6	0,01	0,86	2004-10-15	0,6	0	0	2005-10-15	0	0,01	0,86	2006-10-15	0,2	0	0	2008-10-15	0,3	0	0
2003-10-16	0	0,04	3,44	2004-10-16	17,1	0,02	1,72	2005-10-16	3,1	0	0	2006-10-16	0	0	0	2008-10-16	9,1	0,03	2,58
2003-10-17	0	0,01	0,86	2004-10-17	5,2	0,02	1,72	2005-10-17	0	0	0	2006-10-17	10,2	0,03	2,58	2008-10-17	0	0,01	0,86
2003-10-18	0	0,02	1,72	2004-10-18	0,6	0	0	2005-10-18	2,6	0	0	2006-10-18	12,2	0,08	6,88	2008-10-18	0	0	0
2003-10-19	0,4	0	0	2004-10-19	0	0	0	2005-10-19	0	0	0	2006-10-19	1,5	0	0	2008-10-19	0	0	0
2003-10-20	0	0,01	0,86	2004-10-20	0,2	0,01	0,86	2005-10-20	1,2	0	0	2006-10-20	0,3	0	0	2008-10-20	0	0	0
2003-10-21	0	0	0	2004-10-21	0	0	0	2005-10-21	0	0	0	2006-10-21	1	0	0	2008-10-21	3,6	0,01	0,86
2003-10-22	0	0	0	2004-10-22	0	0	0	2005-10-22	0	0,01	0,86	2006-10-22	3,6	0,01	0,86	2008-10-22	0	0	0
2003-10-23	0	0	0	2004-10-23	0	0	0	2005-10-23	6,3	0	0	2006-10-23	13,7	0,05	4,3	2008-10-23	0	0	0
2003-10-24	1,1	0	0	2004-10-24	15	0	0	2005-10-24	0	0	0	2006-10-24	6,1	0	0	2008-10-24	0	0	0
2003-10-25	1	0	0	2004-10-25	0,6	0,02	1,72	2005-10-25	7,1	0	0	2006-10-25	1,4	0	0	2008-10-25	6,9	0,02	1,72
2003-10-26	11,4	0	0	2004-10-26	0	0,01	0,86	2005-10-26	0	0,01	0,86	2006-10-26	0	0	0	2008-10-26	0	0,01	0,86
2003-10-27	3,1	0,02	1,72	2004-10-27	0,2	0,01	0,86	2005-10-27	0	0,01	0,86	2006-10-27	0	0	0	2008-10-27	1,9	0,01	0,86
2003-10-28	4,4	0,02	1,72	2004-10-28	0	0	0	2005-10-28	0,4	0	0	2006-10-28	18,8	0,08	6,88	2008-10-28	3,8	0	0
2003-10-29	7,7	0,02	1,72	2004-10-29	2,8	0	0	2005-10-29	0	0	0	2006-10-29	7	0	0	2008-10-29	12	0,01	0,86
2003-10-30	0	0,02	1,72	2004-10-30	13,4	0,01	0,86	2005-10-30	0	0	0	2006-10-30	0	0	0	2008-10-30	0,6	0,01	0,86
2003-10-31	0	0	0	2004-10-31	1,9	0,02	1,72	2005-10-31	0,9	0	0	2006-10-31	0,7	0	0	2008-10-31	0	0	0

TABLE 104

WATER LEVELS FLUCTUATION FOR INFILTRATION ASSESSMENT

83, CHRISTE DR, DORCHESTER

Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086	Date	Precip (mm)	WL rise (m)	Recharge (mm) assumed Sy 0.086
2003-11-01	0	0.01	0.86	2004-11-01	0	0.01	0.86	2005-11-01	4.2	0	0	2006-11-01	0.4	0	0	2008-11-01	0	0.02	1.72
2003-11-02	13.7	0	0	2004-11-02	8.3	0.01	0.86	2005-11-02	3	0.01	0.86	2006-11-02	0	0	0	2008-11-02	0	0	0
2003-11-03	28.8	0.2	17.2	2004-11-03	2.6	0.02	1.72	2005-11-03	0	0	0	2006-11-03	0	0	0	2008-11-03	9.6	0	0
2003-11-04	4.7	0.04	3.44	2004-11-04	0	0	0	2005-11-04	0	0	0	2006-11-04	0	0	0	2008-11-04	0.8	0.02	1.72
2003-11-05	0	0.05	4.3	2004-11-05	20.2	0.02	1.72	2005-11-05	0	0.01	0.86	2006-11-05	0	0	0	2008-11-05	0	0.01	0.86
2003-11-06	0.4	0.05	4.3	2004-11-06	0	0.02	1.72	2005-11-06	3.4	0	0	2006-11-06	0	0	0	2008-11-06	0	0.01	0.86
2003-11-07	0	0.01	0.86	2004-11-07	0	0.01	0.86	2005-11-07	1.6	0	0	2006-11-07	0.4	0	0	2008-11-07	0	0	0
2003-11-08	0	0	0	2004-11-08	2	0.01	0.86	2005-11-08	0	0	0	2006-11-08	9.8	0.03	2.58	2008-11-08	21.8	0.03	2.58
2003-11-09	0	0	0	2004-11-09	3	0.02	1.72	2005-11-09	22.2	0.01	0.86	2006-11-09	0	0	0	2008-11-09	0.7	0.09	7.74
2003-11-10	0	0	0	2004-11-10	0	0	0	2005-11-10	2.9	0.03	2.58	2006-11-10	0	0	0	2008-11-10	0.4	0.06	5.16
2003-11-11	5.8	0	0	2004-11-11	0	0	0	2005-11-11	0	0.01	0.86	2006-11-11	5	0.03	2.58	2008-11-11	0	0.02	1.72
2003-11-12	1	0.02	1.72	2004-11-12	0	0	0	2005-11-12	0	0	0	2006-11-12	0.7	0	0	2008-11-12	0	0	0
2003-11-13	3	0	0	2004-11-13	0	0.01	0.86	2005-11-13	2	0.02	1.72	2006-11-13	0	0	0	2008-11-13	5	0	0
2003-11-14	10.2	0	0	2004-11-14	0	0.01	0.86	2005-11-14	0	0	0	2006-11-14	0.5	0	0	2008-11-14	2.9	0.02	1.72
2003-11-15	0	0.02	1.72	2004-11-15	0	0	0	2005-11-15	4.4	0.01	0.86	2006-11-15	0	0	0	2008-11-15	19.5	0.02	1.72
2003-11-16	2.4	0	0	2004-11-16	0	0	0	2005-11-16	36.8	0.07	6.02	2006-11-16	20.8	0.13	11.18	2008-11-16	35.6	0.22	18.92
2003-11-17	4.8	0.04	3.44	2004-11-17	0	0.01	0.86	2005-11-17	0	0.03	2.58	2006-11-17	8.2	0	0	2008-11-17	2.2	0.01	0.86
2003-11-18	0	0.05	4.3	2004-11-18	4.1	0	0	2005-11-18	0.2	0.02	1.72	2006-11-18	0.4	0	0	2008-11-18	1.6	0	0
2003-11-19	18	0.02	1.72	2004-11-19	0	0.01	0.86	2005-11-19	4.2	0.01	0.86	2006-11-19	0	0	0	2008-11-19	0.2	0	0
2003-11-20	1.9	0.06	5.16	2004-11-20	5.7	0	0	2005-11-20	0	0	0	2006-11-20	0	0	0	2008-11-20	8.8	0	0
2003-11-21	0	0	0	2004-11-21	2.2	0.01	0.86	2005-11-21	0	0.01	0.86	2006-11-21	0	0	0	2008-11-21	2.2	0	0
2003-11-22	0	0	0	2004-11-22	0	0	0	2005-11-22	0	0.01	0.86	2006-11-22	0	0	0	2008-11-22	35.6	0	0
2003-11-23	0	0	0	2004-11-23	0	0.01	0.86	2005-11-23	0	0	0	2006-11-23	0	0	0	2008-11-23	2	0.01	0.86
2003-11-24	0	0	0	2004-11-24	1.8	0	0	2005-11-24	14.4	0	0	2006-11-24	0	0	0	2008-11-24	0	0	0
2003-11-25	9.6	0.01	0.86	2004-11-25	28.8	0.04	3.44	2005-11-25	3.2	0.01	0.86	2006-11-25	0	0	0	2008-11-25	4.9	0.02	1.72
2003-11-26	0	0	0	2004-11-26	1.2	0.03	2.58	2005-11-26	4.6	0	0	2006-11-26	0	0	0	2008-11-26	2.4	0	0
2003-11-27	0	0	0	2004-11-27	2	0.02	1.72	2005-11-27	0.2	0.01	0.86	2006-11-27	0	0	0	2008-11-27	1.2	0.01	0.86
2003-11-28	19	0.05	4.3	2004-11-28	4.5	0.01	0.86	2005-11-28	4	0.01	0.86	2006-11-28	0	0	0	2008-11-28	0	0	0
2003-11-29	16.6	0.15	12.9	2004-11-29	1.2	0.01	0.86	2005-11-29	20.8	0.04	3.44	2006-11-29	0.3	0	0	2008-11-29	1.2	0	0
2003-11-30	2	0	0	2004-11-30	0	0.01	0.86	2005-11-30	0	0.08	6.88	2006-11-30	5.8	0.02	1.72	2008-11-30	0	0.01	0.86
2003-12-01	2.4	0	0	2004-12-01	19.6	0	0	2005-12-01	0.4	0.01	0.86	2006-12-01	36.8	0.19	16.34	2008-12-01	15.2	0.04	3.44
2003-12-02	8.4	0	0	2004-12-02	3.6	0.07	6.02	2005-12-02	2.2	0.02	1.72	2006-12-02	15.5	0.01	0.86	2008-12-02	4	0	0
2003-12-03	1.8	0	0	2004-12-03	0.8	0.03	2.58	2005-12-03	19.4	0	0	2006-12-03	0	0	0	2008-12-03	0.8	0	0
2003-12-04	0	0	0	2004-12-04	1	0.01	0.86	2005-12-04	3.8	0	0	2006-12-04	0.8	0	0	2008-12-04	2.4	0.03	2.58
2003-12-05	0	0	0	2004-12-05	0.9	0	0	2005-12-05	0.6	0	0	2006-12-05	1.6	0	0	2008-12-05	0.6	0	0
2003-12-06	0	0	0	2004-12-06	1.2	0.01	0.86	2005-12-06	0	0.01	0.86	2006-12-06	0	0	0	2008-12-06	0.2	0	0
2003-12-07	0	0	0	2004-12-07	1.4	0	0	2005-12-07	0	0	0	2006-12-07	9	0	0	2008-12-07	13.4	0	0
2003-12-08	0	0	0	2004-12-08	15.2	0.05	4.3	2005-12-08	0	0.01	0.86	2006-12-08	28.2	0	0	2008-12-08	1	0	0
2003-12-09	0	0	0	2004-12-09	0	0.01	0.86	2005-12-09	9.2	0	0	2006-12-09	0.4	0.01	0.86	2008-12-09	5.2	0.01	0.86
2003-12-10	0.3	0.01	0.86	2004-12-10	0	0	0	2005-12-10	0.4	0.01	0.86	2006-12-10	0	0	0	2008-12-10	24.1	0.14	12.04
2003-12-11	9.7	0.38	32.68	2004-12-11	7.4	0.02	1.72	2005-12-11	1.8	0	0	2006-12-11	4.3	0.04	3.44	2008-12-11	0	0	0
2003-12-12	2.2	0	0	2004-12-12	1.8	0.02	1.72	2005-12-12	4.2	0	0	2006-12-12	1.3	0.04	3.44	2008-12-12	0	0	0
2003-12-13	2	0.01	0.86	2004-12-13	8.2	0.02	1.72	2005-12-13	0	0	0	2006-12-13	8.4	0.08	6.88	2008-12-13	5.6	0	0
2003-12-14	1.8	0	0	2004-12-14	2.4	0.01	0.86	2005-12-14	0.4	0	0	2006-12-14	0	0	0	2008-12-14	1.5	0	0
2003-12-15	4	0	0	2004-12-15	4.2	0.05	4.3	2005-12-15	0.6	0.01	0.86	2006-12-15	0	0	0	2008-12-15	13.8	0.12	10.32
2003-12-16	0	0.06	5.16	2004-12-16	0	0.03	2.58	2005-12-16	9.6	0	0	2006-12-16	0.6	0	0	2008-12-16	3.2	0	0
2003-12-17	5.2	0	0	2004-12-17	5	0.01	0.86	2005-12-17	0.2	0	0	2006-12-17	0	0	0	2008-12-17	6.2	0	0
2003-12-18	3.4	0	0	2004-12-18	0.6	0	0	2005-12-18	0.2	0	0	2006-12-18	0.4	0	0	2008-12-18	0	0	0
2003-12-19	1	0	0	2004-12-19	2.4	0	0	2005-12-19	0	0	0	2006-12-19	0	0	0	2008-12-19	2.8	0.02	1.72
2003-12-20	4	0	0	2004-12-20	0	0	0	2005-12-20	0	0	0	2006-12-20	0	0	0	2008-12-20	13.2	0	0
2003-12-21	1	0	0	2004-12-21	1.6	0	0	2005-12-21	9.2	0	0	2006-12-21	0	0	0	2008-12-21	4.2	0.01	0.86
2003-12-22	0	0	0	2004-12-22	0	0	0	2005-12-22	2.2	0	0	2006-12-22	2.4	0	0	2008-12-22	5.8	0	0
2003-12-23	8.8	0	0	2004-12-23	20	0	0	2005-12-23	1.4	0.01	0.86	2006-12-23	27.4	0.18	15.48	2008-12-23	2.8	0.01	0.86
2003-12-24	13.7	0.14	12.04	2004-12-24	4.2	0	0	2005-12-24	1.1	0	0	2006-12-24	1.4	0	0	2008-12-24	18.8	0.01	0.86
2003-12-25	2.4	0	0	2004-12-25	0	0	0	2005-12-25	2.6	0.02	1.72	2006-12-25	0	0	0	2008-12-25	12.6	0.09	7.74
2003-12-26	2.8	0	0	2004-12-26	2.2	0	0	2005-12-26	15	0.07	6.02	2006-12-26	4.7	0	0	2008-12-26	0.4	0	0
2003-12-27	0	0	0	2004-12-27	2	0	0	2005-12-27	1.2	0.03	2.58	2006-12-27	0	0	0	2008-12-27	7.5	0.05	4.3
2003-12-28	0	0	0	2004-12-28	0	0	0	2005-12-28	0	0.01	0.86	2006-12-28	0	0	0	2008-12-28	9.9	0.15	12.9
2003-12-29	0	0	0	2004-12-29	0	0	0	2005-12-29	7.4	0.03	2.58	2006-12-29	0	0	0	2008-12-29	0	0	0
2003-12-30	27.2	0.12	10.32	2004-12-30	0	0	0	2005-12-30	2.1	0.03	2.58	2006-12-30	0	0	0	2008-12-30	0	0	0
2003-12-31	0.8	0	0	2004-12-31	13.5	0.08	6.88	2005-12-31	2.2	0	0	2006-12-31	0.4	0	0	2008-12-31	9.4	0	0

Appendix E

Hydraulic Conductivity Testing



eNGLOBE



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH03-19-Sample3


Mass Sample (g):

100

T (oC)

20

BH03-SA3: Moderately well sorted sand low in fines



Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	2.1E-02	2.1E-04	18.55	
Hazen K (cm/s) = d ₁₀ (mm)	1.5E-02	1.5E-04	12.66	
Slichter	7.5E-03	7.5E-05	6.49	
Terzaghi	1.3E-02	1.3E-04	11.38	
Beyer	1.7E-02	1.7E-04	14.71	
Sauerbrei	1.9E-02	1.9E-04	16.50	
Kruger	2.0E-02	2.0E-04	17.54	
Kozeny-Carmen	5.3E-02	5.3E-04	45.68	
Zunker	2.6E-02	2.6E-04	22.38	
Zamarin	2.8E-02	2.8E-04	23.98	
USBR	8.9E-03	8.9E-05	7.68	
Barr	1.1E-02	1.1E-04	9.58	
Alyamani and Sen	9.4E-03	9.4E-05	8.15	
Chapuis	1.5E-02	1.5E-04	13.29	
Krumbein and Monk	1.7E-02	1.7E-04	14.90	
geometric mean	1.4E-02	1.4E-04	12.17	
arithmetic mean	1.5E-02	1.5E-04	13.22	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-04-19-Sample4


Mass Sample (g):

100

T (oC)

20

BH05-SA8: Poorly sorted clay with fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	1.2E-07	1.2E-09	0.00	
Hazen K (cm/s) = d_{10} (mm)	1.7E-07	1.7E-09	0.00	
Slichter	2.5E-08	2.5E-10	0.00	
Terzaghi	3.9E-08	3.9E-10	0.00	
Beyer	1.4E-07	1.4E-09	0.00	
Sauerbrei	8.0E-08	8.0E-10	0.00	
Kruger	1.4E-05	1.4E-07	0.01	
Kozeny-Carmen	2.8E-06	2.8E-08	0.00	
Zunker	2.0E-06	2.0E-08	0.00	
Zamarin	2.4E-06	2.4E-08	0.00	
USBR	3.9E-08	3.9E-10	0.00	
Barr	2.8E-08	2.8E-10	0.00	
Alyamani and Sen	9.0E-08	9.0E-10	0.00	
Chapuis	3.9E-10	3.9E-12	0.00	
Krumbein and Monk	4.6E-05	4.6E-07	0.04	
geometric mean	5.9E-08	5.9E-10	0.00	
arithmetic mean	6.6E-08	6.6E-10	0.00	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-06-19-Sample3


Mass Sample (g):

100

T (oC)

20

BH06-SA3: Moderately well sorted sand low in fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	2.4E-02	2.4E-04	20.82	
Hazen K (cm/s) = d ₁₀ (mm)	1.6E-02	1.6E-04	14.01	
Slichter	8.5E-03	8.5E-05	7.38	
Terzaghi	1.5E-02	1.5E-04	12.95	
Beyer	1.9E-02	1.9E-04	16.42	
Sauerbrei	2.1E-02	2.1E-04	17.98	
Kruger	2.5E-02	2.5E-04	21.35	
Kozeny-Carmen	6.4E-02	6.4E-04	55.60	
Zunker	3.1E-02	3.1E-04	27.17	
Zamarin	3.4E-02	3.4E-04	29.07	
USBR	9.3E-03	9.3E-05	8.01	
Barr	1.3E-02	1.3E-04	10.99	
Alyamani and Sen	1.1E-02	1.1E-04	9.74	
Chapuis	1.8E-02	1.8E-04	15.77	
Krumbein and Monk	1.9E-02	1.9E-04	16.29	
geometric mean	1.6E-02	1.6E-04	13.72	
arithmetic mean	1.7E-02	1.7E-04	14.98	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-08-19-Sample3


Mass Sample (g):

100

T (oC)

20

BH08-SA3: Moderately well sorted gravelly sand low in fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	4.2E-03	4.2E-05	3.64	
Hazen K (cm/s) = d ₁₀ (mm)	3.0E-03	3.0E-05	2.60	
Slichter	1.4E-03	1.4E-05	1.22	
Terzaghi	2.5E-03	2.5E-05	2.13	
Beyer	3.4E-03	3.4E-05	2.94	
Sauerbrei	2.4E-03	2.4E-05	2.09	
Kruger	2.4E-03	2.4E-05	2.09	
Kozeny-Carmen	3.7E-03	3.7E-05	3.24	
Zunker	1.9E-03	1.9E-05	1.61	
Zamarin	2.0E-03	2.0E-05	1.74	
USB	8.3E-04	8.3E-06	0.71	
Barr	2.0E-03	2.0E-05	1.75	
Alyamani and Sen	2.2E-03	2.2E-05	1.86	
Chapuis	2.1E-03	2.1E-05	1.80	
Krumbein and Monk	1.0E-03	1.0E-05	0.86	
geometric mean	1.8E-03	1.8E-05	1.55	
arithmetic mean	1.9E-03	1.9E-05	1.64	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-09-19-Sample2


Mass Sample (g):

100

T (oC)

20

BH09-SA2: Moderately well sorted sand low in fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	1.7E-02	1.7E-04	14.92	
Hazen K (cm/s) = d ₁₀ (mm)	1.2E-02	1.2E-04	10.24	
Slichter	6.0E-03	6.0E-05	5.19	
Terzaghi	1.1E-02	1.1E-04	9.09	
Beyer	1.4E-02	1.4E-04	11.86	
Sauerbrei	1.5E-02	1.5E-04	13.04	
Kruger	2.9E-03	2.9E-05	2.52	
Kozeny-Carmen	1.5E-03	1.5E-05	1.26	
Zunker	7.0E-04	7.0E-06	0.61	
Zamarin	7.4E-04	7.4E-06	0.64	
USBR	6.9E-03	6.9E-05	5.97	
Barr	8.8E-03	8.8E-05	7.62	
Alyamani and Sen	7.3E-03	7.3E-05	6.29	
Chapuis	1.2E-02	1.2E-04	10.19	
Krumbein and Monk	7.9E-03	7.9E-05	6.84	
geometric mean	9.7E-03	9.7E-05	8.34	
arithmetic mean	1.0E-02	1.0E-04	8.96	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-09-19-Sample5


Mass Sample (g):

100

T (oC)

20

BH09-SA5: Moderately well sorted sand low in fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	2.8E-02	2.8E-04	23.76	
Hazen K (cm/s) = d ₁₀ (mm)	1.8E-02	1.8E-04	15.68	
Slichter	1.0E-02	1.0E-04	8.60	
Terzaghi	1.7E-02	1.7E-04	15.10	
Beyer	2.2E-02	2.2E-04	18.60	
Sauerbrei	2.8E-02	2.8E-04	24.04	
Kruger	7.7E-03	7.7E-05	6.69	
Kozeny-Carmen	7.4E-03	7.4E-05	6.40	
Zunker	3.5E-03	3.5E-05	3.02	
Zamarin	3.6E-03	3.6E-05	3.13	
USBR	1.3E-02	1.3E-04	10.96	
Barr	1.5E-02	1.5E-04	12.97	
Alyamani and Sen	1.3E-02	1.3E-04	11.59	
Chapuis	2.3E-02	2.3E-04	19.47	
Krumbein and Monk	1.9E-02	1.9E-04	16.00	
geometric mean	1.7E-02	1.7E-04	14.88	
arithmetic mean	1.8E-02	1.8E-04	15.81	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-12-19-Sample2


Mass Sample (g):

100

T (oC)

20

BH12-SA2: Poorly sorted sand low in fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	9.5E-05	9.5E-07	0.08	
Hazen K (cm/s) = d ₁₀ (mm)	1.5E-04	1.5E-06	0.13	
Slichter	1.9E-05	1.9E-07	0.02	
Terzaghi	2.8E-05	2.8E-07	0.02	
Beyer	1.1E-04	1.1E-06	0.10	
Sauerbrei	3.6E-04	3.6E-06	0.32	
Kruger	4.1E-04	4.1E-06	0.36	
Kozeny-Carmen	1.2E-04	1.2E-06	0.10	
Zunker	8.5E-05	8.5E-07	0.07	
Zamarin	1.0E-04	1.0E-06	0.09	
USBR	7.7E-04	7.7E-06	0.67	
Barr	2.1E-05	2.1E-07	0.02	
Alyamani and Sen	9.2E-04	9.2E-06	0.79	
Chapuis	3.2E-06	3.2E-08	0.00	
Krumbein and Monk	1.3E-03	1.3E-05	1.16	
geometric mean	3.1E-04	3.1E-06	0.27	
arithmetic mean	6.6E-04	6.6E-06	0.57	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-12-19-Sample3


Mass Sample (g):

100

T (oC)

20

BH12-SA3: Poorly sorted clay with fines



a

Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	7.6E-08	7.6E-10	0.00	
Hazen K (cm/s) = d_{10} (mm)	9.3E-08	9.3E-10	0.00	
Slichter	1.7E-08	1.7E-10	0.00	
Terzaghi	2.7E-08	2.7E-10	0.00	
Beyer	8.2E-08	8.2E-10	0.00	
Sauerbrei	5.6E-08	5.6E-10	0.00	
Kruger	1.9E-05	1.9E-07	0.02	
Kozeny-Carmen	2.7E-06	2.7E-08	0.00	
Zunker	1.7E-06	1.7E-08	0.00	
Zamarin	2.0E-06	2.0E-08	0.00	
USBR	1.9E-08	1.9E-10	0.00	
Barr	2.0E-08	2.0E-10	0.00	
Alyamani and Sen	4.9E-09	4.9E-11	0.00	
Chapuis	3.3E-10	3.3E-12	0.00	
Krumbein and Monk	1.3E-04	1.3E-06	0.12	
geometric mean	1.7E-08	1.7E-10	0.00	
arithmetic mean	2.7E-08	2.7E-10	0.00	



K from Grain Size Analysis Report

Date: _____

Sample Name:

BH-13-19-Sample2


Mass Sample (g):

100

T (oC)

20

BH13-SA2: Moderately well sorted sand low in fines



a


Estimation of Hydraulic Conductivity	cm/s	m/s	m/d	de
Hazen	4.4E-03	4.4E-05	3.81	
Hazen K (cm/s) = d ₁₀ (mm)	3.3E-03	3.3E-05	2.88	
Slichter	1.4E-03	1.4E-05	1.21	
Terzaghi	2.4E-03	2.4E-05	2.10	
Beyer	3.7E-03	3.7E-05	3.16	
Sauerbrei	4.8E-03	4.8E-05	4.16	
Kruger	1.7E-03	1.7E-05	1.45	
Kozeny-Carmen	9.5E-04	9.5E-06	0.82	
Zunker	4.9E-04	4.9E-06	0.42	
Zamarin	5.4E-04	5.4E-06	0.46	
USBR	2.9E-03	2.9E-05	2.46	
Barr	1.9E-03	1.9E-05	1.68	
Alyamani and Sen	1.2E-03	1.2E-05	1.04	
Chapuis	1.8E-03	1.8E-05	1.57	
Krumbein and Monk	3.3E-03	3.3E-05	2.88	
geometric mean	2.5E-03	2.5E-05	2.14	
arithmetic mean	2.8E-03	2.8E-05	2.44	

Permeability test

Falling head 1

MW04-19

MW04-19



Paramètre	Valeur retenue
Static level (m BTOP)	2,80
Water level at t= 0s (m BTOP)	1,20
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,60

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo

Analysis method: Hvorslev

Date: 2020-01-21


K: 1,1 x10⁻⁴ m/s

Permeability test

Rising head 1

MW04-19

MW04-19



Paramètre	Valeur retenue
Static level (m BTOP)	2,80
Water level at t= 0s (m BTOP)	4,21
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,60

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo

Analysis method: Hvorslev

Date: 2020-01-21


K: 1,2 x10⁻⁴ m/s

Permeability test

Falling head 2

MW04-19

MW04-19



Paramètre	Valeur retenue
Static level (m BTOP)	2,80
Water level at t= 0s (m BTOP)	0,94
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,60

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo


Analysis method: Hvorslev

Date: 2020-01-21

K: 6,4 x10⁻⁴ m/s

Permeability test Rising head 2 MW04-19

MW04-19



Paramètre	Valeur retenue
Static level (m BTOP)	2,80
Water level at t= 0s (m BTOP)	4,05
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,60

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo

Analysis method: Hvorslev

Date: 2020-01-21


K: 1,6 x10⁻⁴ m/s

Permeability test

Falling head 1

MW05-19

MW05-19



Paramètre	Valeur retenue
Static level (m BTOP)	4,26
Water level at t= 0s (m BTOP)	3,78
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,30

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo


Analysis method: Hvorslev

Date: 2020-01-21

K: $6,0 \times 10^{-5}$ m/s

Permeability test Rising head 1 MW05-19

MW05-19



Paramètre	Valeur retenue
Static level (m BTOP)	4,26
Water level at t= 0s (m BTOP)	4,67
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,30

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo


Analysis method: Hvorslev

Date: 2020-01-21

K: $2,6 \times 10^{-5}$ m/s

Permeability test Rising head 1 MW10-19

MW10-19



Paramètre	Valeur retenue
Static level (m BTOP)	3,08
Water level at t= 0s (m BTOP)	3,91
Radius of the screen (m)	0,025
Radius of the borehole (m)	0,10
Lenght of the filter pack(m)	2,20

Client: CJDL

Scale: No Scale

Project: 284, Christie Drive

Ref. #: P-0019257.0300

Prépared by: Francis Proteau-Bédard.
Reviewed by: Jean-Philippe Gobeil. P.geo

Analysis method: Hvorslev

Date: 2020-01-21

K: $1,2 \times 10^{-5}$ m/s

Appendix F

Laboratory Certificate of Analysis



eNGLOBE



EnGlobe Corp. (London)
ATTN: ROB HELWIG
417 EXETER RD
LONDON ON N6E 2Z3

Date Received: 31-JAN-20
Report Date: 11-FEB-20 06:37 (MT)
Version: FINAL

Client Phone: 519-685-6400

Certificate of Analysis

Lab Work Order #: L2412214
Project P.O. #: NOT SUBMITTED
Job Reference: P-19257-300
C of C Numbers: 17-684348
Legal Site Desc:

Gayle Braun
Senior Account Manager

[This report shall not be reproduced except in full without the written authority of the Laboratory.]

ADDRESS: 309 Exeter Road Unit #29, London, ON N6L 1C1 Canada | Phone: +1 519 652 6044 | Fax: +1 519 652 0671
ALS CANADA LTD Part of the ALS Group An ALS Limited Company

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-1	MW-03-19							
Sampled By: CLIENT on 31-JAN-20 @ 12:00								
Matrix: WATER								
Physical Tests								
Colour, Apparent		7.5		2.0	CU		02-FEB-20	R4986514
Conductivity		599		3.0	umhos/cm		04-FEB-20	R4989650
Hardness (as CaCO3)		366		0.50	mg/L		04-FEB-20	
pH		7.78		0.10	pH units		04-FEB-20	R4989650
Total Dissolved Solids		376	DLDS	20	mg/L		07-FEB-20	R4992754
Turbidity		5.68		0.10	NTU		01-FEB-20	R4989740
Anions and Nutrients								
Alkalinity, Total (as CaCO3)		254		10	mg/L		04-FEB-20	R4989650
Ammonia, Total (as N)		0.016		0.010	mg/L		03-FEB-20	R4987506
Chloride (Cl)		12.3		0.50	mg/L		04-FEB-20	R4989990
Fluoride (F)		0.067		0.020	mg/L		04-FEB-20	R4989990
Nitrate (as N)		8.04		0.020	mg/L		04-FEB-20	R4989990
Nitrite (as N)		0.031		0.010	mg/L		04-FEB-20	R4989990
Orthophosphate-Dissolved (as P)		<0.0030		0.0030	mg/L		07-FEB-20	R4991531
Sulfate (SO4)		24.0		0.30	mg/L		04-FEB-20	R4989990
Dissolved Metals								
Dissolved Metals Filtration Location		FIELD					04-FEB-20	R4987080
Aluminum (Al)-Dissolved		<0.0050		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Antimony (Sb)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Arsenic (As)-Dissolved		0.00023		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Barium (Ba)-Dissolved		0.0230		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Beryllium (Be)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Bismuth (Bi)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Boron (B)-Dissolved		0.013		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Cadmium (Cd)-Dissolved		0.0000098		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Calcium (Ca)-Dissolved		106		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Chromium (Cr)-Dissolved		0.00051		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Cobalt (Co)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Copper (Cu)-Dissolved		0.00198		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086
Iron (Fe)-Dissolved		<0.010		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Lead (Pb)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Magnesium (Mg)-Dissolved		24.7		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Manganese (Mn)-Dissolved		0.00272		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Molybdenum (Mo)-Dissolved		0.000415		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Nickel (Ni)-Dissolved		0.00142		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		0.785		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.00111		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		6.41		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		4.24		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-1 MW-03-19 Sampled By: CLIENT on 31-JAN-20 @ 12:00 Matrix: WATER								
Dissolved Metals								
Strontium (Sr)-Dissolved		0.185		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00062		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Uranium (U)-Dissolved		0.000599		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Vanadium (V)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Zinc (Zn)-Dissolved		0.195		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Zirconium (Zr)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
L2412214-2 MW-08-19 Sampled By: CLIENT on 31-JAN-20 @ 12:30 Matrix: WATER								
Physical Tests								
Colour, Apparent		20.9		2.0	CU		02-FEB-20	R4986514
Conductivity		666		3.0	umhos/cm		04-FEB-20	R4989650
Hardness (as CaCO3)		355		0.50	mg/L		04-FEB-20	
pH		8.16		0.10	pH units		04-FEB-20	R4989650
Total Dissolved Solids		386	DLDS	20	mg/L		07-FEB-20	R4992754
Turbidity		29.4		0.10	NTU		01-FEB-20	R4989740
Anions and Nutrients								
Alkalinity, Total (as CaCO3)		315		10	mg/L		04-FEB-20	R4989650
Ammonia, Total (as N)		<0.010		0.010	mg/L		03-FEB-20	R4987506
Chloride (Cl)		9.22		0.50	mg/L		04-FEB-20	R4989990
Fluoride (F)		0.051		0.020	mg/L		04-FEB-20	R4989990
Nitrate (as N)		7.21		0.020	mg/L		04-FEB-20	R4989990
Nitrite (as N)		<0.010		0.010	mg/L		04-FEB-20	R4989990
Orthophosphate-Dissolved (as P)		0.0054		0.0030	mg/L		07-FEB-20	R4991531
Sulfate (SO4)		17.7		0.30	mg/L		04-FEB-20	R4989990
Dissolved Metals								
Dissolved Metals Filtration Location		FIELD					04-FEB-20	R4987080
Aluminum (Al)-Dissolved		0.0075		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Antimony (Sb)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Arsenic (As)-Dissolved		0.00029		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Barium (Ba)-Dissolved		0.0193		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Beryllium (Be)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Bismuth (Bi)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Boron (B)-Dissolved		0.016		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Cadmium (Cd)-Dissolved		0.0000129		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Calcium (Ca)-Dissolved		102		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Chromium (Cr)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Cobalt (Co)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Copper (Cu)-Dissolved		0.00474		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-2 MW-08-19 Sampled By: CLIENT on 31-JAN-20 @ 12:30 Matrix: WATER								
Dissolved Metals								
Iron (Fe)-Dissolved		<0.010		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Lead (Pb)-Dissolved		0.000314		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Magnesium (Mg)-Dissolved		24.3		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Manganese (Mn)-Dissolved		0.00408		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Molybdenum (Mo)-Dissolved		0.000899		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Nickel (Ni)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		0.866		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.00301		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		6.34		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		3.29		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Strontium (Sr)-Dissolved		0.146		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00031		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Uranium (U)-Dissolved		0.00100		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Vanadium (V)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Zinc (Zn)-Dissolved		0.616		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Zirconium (Zr)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
L2412214-3 MW-10-19 Sampled By: CLIENT on 31-JAN-20 @ 14:30 Matrix: WATER								
Physical Tests								
Colour, Apparent		51.5		2.0	CU		02-FEB-20	R4986514
Conductivity		600		3.0	umhos/cm		04-FEB-20	R4989650
Hardness (as CaCO3)		325		0.50	mg/L		04-FEB-20	
pH		7.71		0.10	pH units		04-FEB-20	R4989650
Total Dissolved Solids		451	DLDS	20	mg/L		07-FEB-20	R4992754
Turbidity		211		0.10	NTU		01-FEB-20	R4989740
Anions and Nutrients								
Alkalinity, Total (as CaCO3)		284		10	mg/L		04-FEB-20	R4989650
Ammonia, Total (as N)		0.018		0.010	mg/L		03-FEB-20	R4987506
Chloride (Cl)		9.71		0.50	mg/L		04-FEB-20	R4989990
Fluoride (F)		0.116		0.020	mg/L		04-FEB-20	R4989990
Nitrate (as N)		9.42		0.020	mg/L		04-FEB-20	R4989990
Nitrite (as N)		0.025		0.010	mg/L		04-FEB-20	R4989990
Orthophosphate-Dissolved (as P)		<0.0030		0.0030	mg/L		07-FEB-20	R4991531
Sulfate (SO4)		27.5		0.30	mg/L		04-FEB-20	R4989990
Dissolved Metals								
Dissolved Metals Filtration Location		FIELD					04-FEB-20	R4987080

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-3 MW-10-19 Sampled By: CLIENT on 31-JAN-20 @ 14:30 Matrix: WATER								
Dissolved Metals								
Aluminum (Al)-Dissolved		<0.0050		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Antimony (Sb)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Arsenic (As)-Dissolved		0.00040		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Barium (Ba)-Dissolved		0.0427		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Beryllium (Be)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Bismuth (Bi)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Boron (B)-Dissolved		0.013		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Cadmium (Cd)-Dissolved		0.0000137		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Calcium (Ca)-Dissolved		93.4		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Chromium (Cr)-Dissolved		0.00073		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Cobalt (Co)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Copper (Cu)-Dissolved		0.00283		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086
Iron (Fe)-Dissolved		<0.010		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Lead (Pb)-Dissolved		0.000060		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Magnesium (Mg)-Dissolved		22.2		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Manganese (Mn)-Dissolved		0.0109		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Molybdenum (Mo)-Dissolved		0.00233		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Nickel (Ni)-Dissolved		0.00103		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		1.56		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.000142		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		5.60		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		8.37		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Strontium (Sr)-Dissolved		0.199		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00037		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Uranium (U)-Dissolved		0.00110		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Vanadium (V)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Zinc (Zn)-Dissolved		0.0320		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Zirconium (Zr)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
L2412214-4 MP-01-19 Sampled By: CLIENT on 31-JAN-20 @ 15:00 Matrix: WATER								
Physical Tests								
Colour, Apparent		40.0		2.0	CU		02-FEB-20	R4986514
Conductivity		478		3.0	umhos/cm		04-FEB-20	R4989650
Hardness (as CaCO3)		283		0.50	mg/L		05-FEB-20	
pH		8.14		0.10	pH units		04-FEB-20	R4989650
Total Dissolved Solids		272	DLDS	20	mg/L		07-FEB-20	R4992754

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-4 MP-01-19								
Sampled By: CLIENT on 31-JAN-20 @ 15:00								
Matrix: WATER								
Physical Tests								
Turbidity		9.47		0.10	NTU		01-FEB-20	R4989740
Anions and Nutrients								
Alkalinity, Total (as CaCO3)		255		10	mg/L		04-FEB-20	R4989650
Ammonia, Total (as N)		0.024		0.010	mg/L		03-FEB-20	R4987506
Chloride (Cl)		2.63		0.50	mg/L		04-FEB-20	R4989990
Fluoride (F)		0.045		0.020	mg/L		04-FEB-20	R4989990
Nitrate (as N)		0.032		0.020	mg/L		04-FEB-20	R4989990
Nitrite (as N)		<0.010		0.010	mg/L		04-FEB-20	R4989990
Orthophosphate-Dissolved (as P)		0.0088		0.0030	mg/L		07-FEB-20	R4991531
Sulfate (SO4)		7.85		0.30	mg/L		04-FEB-20	R4989990
Dissolved Metals								
Dissolved Metals Filtration Location		FIELD					04-FEB-20	R4987080
Aluminum (Al)-Dissolved		<0.0050		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Antimony (Sb)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Arsenic (As)-Dissolved		0.00023		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Barium (Ba)-Dissolved		0.0169		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Beryllium (Be)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Bismuth (Bi)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Boron (B)-Dissolved		<0.010		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Cadmium (Cd)-Dissolved		<0.0000050		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Calcium (Ca)-Dissolved		86.9		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Chromium (Cr)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Cobalt (Co)-Dissolved		0.00011		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Copper (Cu)-Dissolved		0.00050		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086
Iron (Fe)-Dissolved		0.210		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Lead (Pb)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Magnesium (Mg)-Dissolved		16.1		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Manganese (Mn)-Dissolved		0.168		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Molybdenum (Mo)-Dissolved		0.000269		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Nickel (Ni)-Dissolved		0.00156		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		0.271		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.000247		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		4.82		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		2.84		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Strontium (Sr)-Dissolved		0.155		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00036		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-4 MP-01-19 Sampled By: CLIENT on 31-JAN-20 @ 15:00 Matrix: WATER Dissolved Metals								
	Uranium (U)-Dissolved	0.000126		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Vanadium (V)-Dissolved	<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Zinc (Zn)-Dissolved	0.0162		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Zirconium (Zr)-Dissolved	<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
L2412214-5 MP-04-19 Sampled By: CLIENT on 31-JAN-20 @ 15:30 Matrix: WATER Physical Tests								
	Colour, Apparent	96.1		2.0	CU		02-FEB-20	R4986514
	Conductivity	652		3.0	umhos/cm		04-FEB-20	R4989650
	Hardness (as CaCO3)	265		0.50	mg/L		04-FEB-20	
	pH	8.26		0.10	pH units		04-FEB-20	R4989650
	Total Dissolved Solids	359	DLDS	20	mg/L		07-FEB-20	R4992754
	Turbidity	24.2		0.10	NTU		01-FEB-20	R4989740
	Anions and Nutrients							
	Alkalinity, Total (as CaCO3)	251		10	mg/L		04-FEB-20	R4989650
	Ammonia, Total (as N)	0.368		0.010	mg/L		03-FEB-20	R4987506
	Chloride (Cl)	53.8		0.50	mg/L		04-FEB-20	R4989990
	Fluoride (F)	0.147		0.020	mg/L		04-FEB-20	R4989990
	Nitrate (as N)	0.829		0.020	mg/L		04-FEB-20	R4989990
	Nitrite (as N)	<0.010		0.010	mg/L		04-FEB-20	R4989990
	Orthophosphate-Dissolved (as P)	0.0069		0.0030	mg/L		07-FEB-20	R4991531
	Sulfate (SO4)	14.7		0.30	mg/L		04-FEB-20	R4989990
	Dissolved Metals							
	Dissolved Metals Filtration Location	FIELD					04-FEB-20	R4987080
	Aluminum (Al)-Dissolved	<0.0050		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Antimony (Sb)-Dissolved	<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Arsenic (As)-Dissolved	0.00082		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Barium (Ba)-Dissolved	0.0214		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Beryllium (Be)-Dissolved	<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Bismuth (Bi)-Dissolved	<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Boron (B)-Dissolved	0.018		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Cadmium (Cd)-Dissolved	0.0000073		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Calcium (Ca)-Dissolved	77.4		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Chromium (Cr)-Dissolved	<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Cobalt (Co)-Dissolved	0.00036		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Copper (Cu)-Dissolved	0.00409		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086
	Iron (Fe)-Dissolved	0.838		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
	Lead (Pb)-Dissolved	0.000242		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Magnesium (Mg)-Dissolved	17.3		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Manganese (Mn)-Dissolved	0.931		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
	Molybdenum (Mo)-Dissolved	0.00104		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-5 MP-04-19 Sampled By: CLIENT on 31-JAN-20 @ 15:30 Matrix: WATER								
Dissolved Metals								
Nickel (Ni)-Dissolved		0.00053		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		2.03		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.000127		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		4.49		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		29.7		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Strontium (Sr)-Dissolved		0.252		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00026		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Uranium (U)-Dissolved		0.000515		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Vanadium (V)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Zinc (Zn)-Dissolved		0.0081		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Zirconium (Zr)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086
L2412214-6 MW-05-19 Sampled By: CLIENT on 31-JAN-20 @ 13:30 Matrix: WATER								
Physical Tests								
pH		7.94		0.10	pH units		04-FEB-20	R4989650
Total Suspended Solids		41.4		2.0	mg/L	06-FEB-20	07-FEB-20	R4991530
Anions and Nutrients								
Fluoride (F)		0.059		0.020	mg/L		04-FEB-20	R4989990
Total Kjeldahl Nitrogen		0.18		0.15	mg/L	04-FEB-20	04-FEB-20	R4988370
Phosphorus, Total		0.0335		0.0030	mg/L	04-FEB-20	05-FEB-20	R4990111
Sulfate (SO4)		25.9		0.30	mg/L		04-FEB-20	R4989990
Sulphide (as S)		<0.018		0.018	mg/L		05-FEB-20	R4990438
Sulphide (as H2S)		<0.019		0.019	mg/L		05-FEB-20	
Cyanides								
Cyanide, Total		<0.0020		0.0020	mg/L		03-FEB-20	R4986792
Total Metals								
Antimony (Sb)-Total		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4987537
Arsenic (As)-Total		0.00053		0.00010	mg/L	04-FEB-20	04-FEB-20	R4987537
Cadmium (Cd)-Total		0.0000185		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4987537
Chromium (Cr)-Total		0.00317		0.00050	mg/L	04-FEB-20	04-FEB-20	R4987537
Cobalt (Co)-Total		0.00068		0.00010	mg/L	04-FEB-20	04-FEB-20	R4987537
Copper (Cu)-Total		0.0033		0.0010	mg/L	04-FEB-20	04-FEB-20	R4987537
Lead (Pb)-Total		0.00139		0.000050	mg/L	04-FEB-20	04-FEB-20	R4987537
Mercury (Hg)-Total		<0.0000050		0.0000050	mg/L		05-FEB-20	R4989993
Molybdenum (Mo)-Total		0.000404		0.000050	mg/L	04-FEB-20	04-FEB-20	R4987537
Nickel (Ni)-Total		0.00134		0.00050	mg/L	04-FEB-20	04-FEB-20	R4987537

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-6 MW-05-19 Sampled By: CLIENT on 31-JAN-20 @ 13:30 Matrix: WATER	Total Metals							
	Selenium (Se)-Total	0.000423		0.000050	mg/L	04-FEB-20	04-FEB-20	R4987537
	Silver (Ag)-Total	<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4987537
	Tin (Sn)-Total	0.00017		0.00010	mg/L	04-FEB-20	04-FEB-20	R4987537
	Zinc (Zn)-Total	0.0747		0.0030	mg/L	04-FEB-20	04-FEB-20	R4987537
	Aggregate Organics							
	BOD	<2.0		2.0	mg/L	03-FEB-20	08-FEB-20	R4992139
	Oil and Grease, Total	<5.0		5.0	mg/L	05-FEB-20	05-FEB-20	R4990750
	Animal/Veg Oil & Grease	<5.0		5.0	mg/L		06-FEB-20	
	Mineral Oil and Grease	<2.5		2.5	mg/L	05-FEB-20	05-FEB-20	R4990750
	Phenols (4AAP)	0.0019		0.0010	mg/L		04-FEB-20	R4989709
	Volatile Organic Compounds							
	Benzene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Chloroform	<1.0		1.0	ug/L		04-FEB-20	R4987130
	1,2-Dichlorobenzene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	1,4-Dichlorobenzene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Dichloromethane	<2.0		2.0	ug/L		04-FEB-20	R4987130
	Ethylbenzene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	1,1,2,2-Tetrachloroethane	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Tetrachloroethylene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Toluene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Trichloroethylene	<0.50		0.50	ug/L		04-FEB-20	R4987130
	Xylenes (Total)	<0.50		0.50	ug/L		04-FEB-20	
	Surrogate: 4-Bromofluorobenzene	97.1		70-130	%		04-FEB-20	R4987130
	Surrogate: 1,4-Difluorobenzene	99.7		70-130	%		04-FEB-20	R4987130
	Trihalomethanes							
	Total THMs	<2.0		2.0	ug/L		04-FEB-20	
L2412214-7 DUPLICATE Sampled By: CLIENT on 31-JAN-20 @ 14:30 Matrix: WATER	Physical Tests							
	Colour, Apparent	38.3		2.0	CU		02-FEB-20	R4986514
	Conductivity	592		3.0	umhos/cm		04-FEB-20	R4989650
	Hardness (as CaCO3)	332		0.50	mg/L		04-FEB-20	
	pH	7.72		0.10	pH units		04-FEB-20	R4989650
	Total Dissolved Solids	434	DLDS	20	mg/L		07-FEB-20	R4992754
	Turbidity	124		0.10	NTU		01-FEB-20	R4989740
	Anions and Nutrients							
	Alkalinity, Total (as CaCO3)	268		10	mg/L		04-FEB-20	R4989650
	Ammonia, Total (as N)	0.017		0.010	mg/L		04-FEB-20	R4990204
	Chloride (Cl)	9.82		0.50	mg/L		04-FEB-20	R4989990
	Fluoride (F)	0.112		0.020	mg/L		04-FEB-20	R4989990
	Nitrate (as N)	9.38		0.020	mg/L		04-FEB-20	R4989990

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

ALS ENVIRONMENTAL ANALYTICAL REPORT

Sample Details/Parameters		Result	Qualifier*	D.L.	Units	Extracted	Analyzed	Batch
L2412214-7 DUPLICATE								
Sampled By: CLIENT on 31-JAN-20 @ 14:30								
Matrix: WATER								
Anions and Nutrients								
Nitrite (as N)		0.021		0.010	mg/L		04-FEB-20	R4989990
Orthophosphate-Dissolved (as P)		<0.0030		0.0030	mg/L		07-FEB-20	R4991531
Sulfate (SO4)		27.8		0.30	mg/L		04-FEB-20	R4989990
Dissolved Metals								
Dissolved Metals Filtration Location		FIELD					04-FEB-20	R4987080
Aluminum (Al)-Dissolved		0.123		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Antimony (Sb)-Dissolved		0.00011		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Arsenic (As)-Dissolved		0.00044		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Barium (Ba)-Dissolved		0.0446		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Beryllium (Be)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Bismuth (Bi)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Boron (B)-Dissolved		0.015		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Cadmium (Cd)-Dissolved		0.0000080		0.0000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Calcium (Ca)-Dissolved		95.5		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Chromium (Cr)-Dissolved		0.00064		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Cobalt (Co)-Dissolved		0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Copper (Cu)-Dissolved		0.00670		0.00020	mg/L	04-FEB-20	04-FEB-20	R4989086
Iron (Fe)-Dissolved		0.060		0.010	mg/L	04-FEB-20	04-FEB-20	R4989086
Lead (Pb)-Dissolved		0.000276		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Magnesium (Mg)-Dissolved		22.8		0.0050	mg/L	04-FEB-20	04-FEB-20	R4989086
Manganese (Mn)-Dissolved		0.0144		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Molybdenum (Mo)-Dissolved		0.00255		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Nickel (Ni)-Dissolved		0.00112		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Phosphorus (P)-Dissolved		<0.050		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Potassium (K)-Dissolved		1.60		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Selenium (Se)-Dissolved		0.000121		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silicon (Si)-Dissolved		6.12		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Silver (Ag)-Dissolved		<0.000050		0.000050	mg/L	04-FEB-20	04-FEB-20	R4989086
Sodium (Na)-Dissolved		8.49		0.050	mg/L	04-FEB-20	04-FEB-20	R4989086
Strontium (Sr)-Dissolved		0.206		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Thallium (Tl)-Dissolved		<0.000010		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Tin (Sn)-Dissolved		0.00020		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Titanium (Ti)-Dissolved		<0.0030	DLUI	0.0030	mg/L	04-FEB-20	04-FEB-20	R4989086
Tungsten (W)-Dissolved		<0.00010		0.00010	mg/L	04-FEB-20	04-FEB-20	R4989086
Uranium (U)-Dissolved		0.00118		0.000010	mg/L	04-FEB-20	04-FEB-20	R4989086
Vanadium (V)-Dissolved		<0.00050		0.00050	mg/L	04-FEB-20	04-FEB-20	R4989086
Zinc (Zn)-Dissolved		0.0372		0.0010	mg/L	04-FEB-20	04-FEB-20	R4989086
Zirconium (Zr)-Dissolved		<0.00030		0.00030	mg/L	04-FEB-20	04-FEB-20	R4989086

* Refer to Referenced Information for Qualifiers (if any) and Methodology.

QC Samples with Qualifiers & Comments:

QC Type Description	Parameter	Qualifier	Applies to Sample Number(s)
Matrix Spike	Barium (Ba)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Boron (B)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Calcium (Ca)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Magnesium (Mg)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Potassium (K)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Silicon (Si)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Sodium (Na)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Strontium (Sr)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Uranium (U)-Dissolved	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Copper (Cu)-Total	MS-B	L2412214-6
Matrix Spike	Zinc (Zn)-Total	MS-B	L2412214-6
Matrix Spike	Ammonia, Total (as N)	MS-B	L2412214-7
Matrix Spike	Nitrate (as N)	MS-B	L2412214-1, -2, -3, -4, -5, -7
Matrix Spike	Phosphorus, Total	MS-B	L2412214-6
Matrix Spike	Phenols (4AAP)	MS-B	L2412214-6
Matrix Spike	Phenols (4AAP)	MS-B	L2412214-6

Sample Parameter Qualifier key listed:

Qualifier	Description
DLDS	Detection Limit Raised: Dilution required due to high Dissolved Solids / Electrical Conductivity.
DLUI	Detection Limit Raised: Unknown Interference generated an apparent false positive test result.
MS-B	Matrix Spike recovery could not be accurately calculated due to high analyte background in sample.

Test Method References:

ALS Test Code	Matrix	Test Description	Method Reference**
ALK-WT	Water	Alkalinity, Total (as CaCO3)	EPA 310.2
This analysis is carried out using procedures adapted from EPA Method 310.2 "Alkalinity". Total Alkalinity is determined using the methyl orange colourimetric method.			
BOD-WT	Water	BOD	APHA 5210 B
This analysis is carried out using procedures adapted from APHA Method 5210B - "Biochemical Oxygen Demand (BOD)". All forms of biochemical oxygen demand (BOD) are determined by diluting and incubating a sample for a specified time period, and measuring the oxygen depletion using a dissolved oxygen meter. Dissolved BOD (SOLUBLE) is determined by filtering the sample through a glass fibre filter prior to dilution. Carbonaceous BOD (CBOD) is determined by adding a nitrification inhibitor to the diluted sample prior to incubation.			
CL-IC-N-WT	Water	Chloride by IC	EPA 300.1 (mod)
Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.			
Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011).			
CN-TOT-WT	Water	Cyanide, Total	ISO 14403-2
Total cyanide is determined by the combination of UV digestion and distillation. Cyanide is converted to cyanogen chloride by reacting with chloramine-T, the cyanogen chloride then reacts with a combination of barbituric acid and isonicotinic acid to form a highly colored complex.			
When using this method, high levels of thiocyanate in samples can cause false positives at ~1-2% of the thiocyanate concentration. For samples with detectable cyanide analyzed by this method, ALS recommends analysis for thiocyanate to check for this potential interference			
COLOUR-APPARENT-WT	Water	Colour	APHA 2120
Apparent Colour is measured spectrophotometrically by comparison to platinum-cobalt standards using the single wavelength method after sample decanting. Colour measurements can be highly pH dependent, and apply to the pH of the sample as received (at time of testing), without pH adjustment. Concurrent measurement of sample pH is recommended.			
EC-SCREEN-WT	Water	Conductivity Screen (Internal Use Only)	APHA 2510
Qualitative analysis of conductivity where required during preparation of other tests - e.g. TDS, metals, etc.			
EC-WT	Water	Conductivity	APHA 2510 B
Water samples can be measured directly by immersing the conductivity cell into the sample.			
F-IC-N-WT	Water	Fluoride in Water by IC	EPA 300.1 (mod)

Reference Information

Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.

HARDNESS-CALC-WT	Water	Hardness	APHA 2340 B
------------------	-------	----------	-------------

Hardness (also known as Total Hardness) is calculated from the sum of Calcium and Magnesium concentrations, expressed in CaCO3 equivalents. Dissolved Calcium and Magnesium concentrations are preferentially used for the hardness calculation.

HG-T-CVAA-WT	Water	Total Mercury in Water by CVAAS	EPA 1631E (mod)
--------------	-------	---------------------------------	-----------------

Water samples undergo a cold-oxidation using bromine monochloride prior to reduction with stannous chloride, and analyzed by CVAAS.

MET-D-CCMS-WT	Water	Dissolved Metals in Water by CRC ICPMS	APHA 3030B/6020A (mod)
---------------	-------	--	------------------------

Water samples are filtered (0.45 um), preserved with nitric acid, and analyzed by CRC ICPMS.

Method Limitation (re: Sulfur): Sulfide and volatile sulfur species may not be recovered by this method.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011).

MET-T-CCMS-WT	Water	Total Metals in Water by CRC ICPMS	EPA 200.2/6020A (mod)
---------------	-------	------------------------------------	-----------------------

Water samples are digested with nitric and hydrochloric acids, and analyzed by CRC ICPMS.

Method Limitation (re: Sulfur): Sulfide and volatile sulfur species may not be recovered by this method.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011).

NH3-F-WT	Water	Ammonia in Water by Fluorescence	J. ENVIRON. MONIT., 2005, 7, 37-42, RSC
----------	-------	----------------------------------	---

This analysis is carried out, on sulfuric acid preserved samples, using procedures modified from J. Environ. Monit., 2005, 7, 37 - 42, The Royal Society of Chemistry, "Flow-injection analysis with fluorescence detection for the determination of trace levels of ammonium in seawater", Roslyn J. Waston et al.

NO2-IC-WT	Water	Nitrite in Water by IC	EPA 300.1 (mod)
-----------	-------	------------------------	-----------------

Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.

NO3-IC-WT	Water	Nitrate in Water by IC	EPA 300.1 (mod)
-----------	-------	------------------------	-----------------

Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.

OGG-SPEC-CALC-WT	Water	Speciated Oil and Grease A/V Calc	CALCULATION
------------------	-------	-----------------------------------	-------------

Sample is extracted with hexane, sample speciation into mineral and animal/vegetable fractions is achieved via silica gel separation and is then determined gravimetrically.

OGG-SPEC-WT	Water	Speciated Oil and Grease-Gravimetric	APHA 5520 B
-------------	-------	--------------------------------------	-------------

The procedure involves an extraction of the entire water sample with hexane. Sample speciation into mineral and animal/vegetable fractions is achieved via silica gel separation and is then determined gravimetrically.

P-T-COL-WT	Water	Total P in Water by Colour	APHA 4500-P PHOSPHORUS
------------	-------	----------------------------	------------------------

This analysis is carried out using procedures adapted from APHA Method 4500-P "Phosphorus". Total Phosphorus is determined colourimetrically after persulphate digestion of the sample.

PH-WT	Water	pH	APHA 4500 H-Electrode
-------	-------	----	-----------------------

Water samples are analyzed directly by a calibrated pH meter.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011). Holdtime for samples under this regulation is 28 days

PHENOLS-4AAP-WT	Water	Phenol (4AAP)	EPA 9066
-----------------	-------	---------------	----------

An automated method is used to distill the sample. The distillate is then buffered to pH 9.4 which reacts with 4AAP and potassium ferricyanide to form a red complex which is measured colorimetrically.

PO4-DO-COL-WT	Water	Diss. Orthophosphate in Water by Colour	APHA 4500-P PHOSPHORUS
---------------	-------	---	------------------------

This analysis is carried out using procedures adapted from APHA Method 4500-P "Phosphorus". Dissolved Orthophosphate is determined colourimetrically on a sample that has been lab or field filtered through a 0.45 micron membrane filter.

S2-T>H2S-CALC-WT	Water	Total Sulphide Calculated as H2S	Calculation
------------------	-------	----------------------------------	-------------

This calculation converts Total Sulphide as (S2-) and reports it as Total Sulphide as (H2S). Total Sulphide as (S2-) is determined using procedures adapted from APHA 4500-S2 "Sulphide".

SO4-IC-N-WT	Water	Sulfate in Water by IC	EPA 300.1 (mod)
-------------	-------	------------------------	-----------------

Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.

SOLIDS-TDS-WT	Water	Total Dissolved Solids	APHA 2540C
---------------	-------	------------------------	------------

This analysis is carried out using procedures adapted from APHA Method 2540 "Solids". Solids are determined gravimetrically. Total Dissolved Solids (TDS) are determined by filtering a sample through a glass fibre filter, TDS is determined by evaporating the filtrate to dryness at 180 degrees celsius.

SOLIDS-TSS-WT	Water	Suspended solids	APHA 2540 D-Gravimetric
---------------	-------	------------------	-------------------------

A well-mixed sample is filtered through a weighed standard glass fibre filter and the residue retained is dried in an oven at 104–1°C for a minimum of four hours or until a constant weight is achieved.

SULPHIDE-WT	Water	Sulphide (as S)	APHA 4500S2D
-------------	-------	-----------------	--------------

This analysis is carried out using procedures adapted from APHA Method 4500-S2-D "Methylene Blue Method". Sulphide is determined colourmetrically.

THM-SUM-PPB-CALC-WT	Water	Total Trihalomethanes (THMs)	CALCULATION
---------------------	-------	------------------------------	-------------

Total Trihalomethanes (THMs) represents the sum of bromodichloromethane, bromoform, chlorodibromomethane and chloroform. For the purpose of calculation, results less than the detection limit (DL) are treated as zero.

TKN-WT	Water	Total Kjeldahl Nitrogen	APHA 4500-Norg D
--------	-------	-------------------------	------------------

This analysis is carried out using procedures adapted from APHA Method 4500-Norg "Nitrogen (Organic)". Total Kjeldahl Nitrogen is determined by sample digestion at 380 Celsius with analysis using an automated colorimetric method.

TURBIDITY-WT	Water	Turbidity	APHA 2130 B
--------------	-------	-----------	-------------

Sample result is based on a comparison of the intensity of the light scattered by the sample under defined conditions with the intensity of light scattered by a standard reference suspension under the same conditions. Sample readings are obtained from a Nephelometer.

VOC-ROU-HS-WT	Water	Volatile Organic Compounds	SW846 8260
---------------	-------	----------------------------	------------

Aqueous samples are analyzed by headspace-GC/MS.

XYLENES-SUM-CALC-WT	Water	Sum of Xylene Isomer Concentrations	CALCULATION
---------------------	-------	-------------------------------------	-------------

Total xylenes represents the sum of o-xylene and m&p-xylene.

** ALS test methods may incorporate modifications from specified reference methods to improve performance.

The last two letters of the above test code(s) indicate the laboratory that performed analytical analysis for that test. Refer to the list below:

Laboratory Definition Code	Laboratory Location
WT	ALS ENVIRONMENTAL - WATERLOO, ONTARIO, CANADA

Chain of Custody Numbers:

17-684348

Reference Information

GLOSSARY OF REPORT TERMS

Surrogates are compounds that are similar in behaviour to target analyte(s), but that do not normally occur in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery. In reports that display the D.L. column, laboratory objectives for surrogates are listed there.

mg/kg - milligrams per kilogram based on dry weight of sample

mg/kg ww - milligrams per kilogram based on wet weight of sample

mg/kg lwt - milligrams per kilogram based on lipid weight of sample

mg/L - unit of concentration based on volume, parts per million.

< - Less than.

D.L. - The reporting limit.

N/A - Result not available. Refer to qualifier code and definition for explanation.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

Analytical results in unsigned test reports with the DRAFT watermark are subject to change, pending final QC review.

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 2 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
F-IC-N-WT	Water							
Batch R4989990								
WG3269520-2 LCS								
Fluoride (F)			101.6		%		90-110	04-FEB-20
WG3269520-1 MB								
Fluoride (F)			<0.020		mg/L		0.02	04-FEB-20
HG-T-CVAA-WT	Water							
Batch R4989993								
WG3269801-2 LCS								
Mercury (Hg)-Total			105.0		%		80-120	05-FEB-20
WG3269801-1 MB								
Mercury (Hg)-Total			<0.000005C		mg/L		0.000005	05-FEB-20
MET-D-CCMS-WT	Water							
Batch R4989086								
WG3268919-2 LCS								
Aluminum (Al)-Dissolved			102.4		%		80-120	04-FEB-20
Antimony (Sb)-Dissolved			100.0		%		80-120	04-FEB-20
Arsenic (As)-Dissolved			97.8		%		80-120	04-FEB-20
Barium (Ba)-Dissolved			101.8		%		80-120	04-FEB-20
Beryllium (Be)-Dissolved			99.0		%		80-120	04-FEB-20
Bismuth (Bi)-Dissolved			100.6		%		80-120	04-FEB-20
Boron (B)-Dissolved			98.4		%		80-120	04-FEB-20
Cadmium (Cd)-Dissolved			97.8		%		80-120	04-FEB-20
Calcium (Ca)-Dissolved			100.9		%		80-120	04-FEB-20
Chromium (Cr)-Dissolved			101.0		%		80-120	04-FEB-20
Cobalt (Co)-Dissolved			100.3		%		80-120	04-FEB-20
Copper (Cu)-Dissolved			97.3		%		80-120	04-FEB-20
Iron (Fe)-Dissolved			97.9		%		80-120	04-FEB-20
Lead (Pb)-Dissolved			102.5		%		80-120	04-FEB-20
Magnesium (Mg)-Dissolved			110.3		%		80-120	04-FEB-20
Manganese (Mn)-Dissolved			100.1		%		80-120	04-FEB-20
Molybdenum (Mo)-Dissolved			101.5		%		80-120	04-FEB-20
Nickel (Ni)-Dissolved			99.2		%		80-120	04-FEB-20
Phosphorus (P)-Dissolved			103.7		%		80-120	04-FEB-20
Potassium (K)-Dissolved			98.2		%		80-120	04-FEB-20
Selenium (Se)-Dissolved			96.5		%		80-120	04-FEB-20
Silicon (Si)-Dissolved			101.4		%		60-140	04-FEB-20
Silver (Ag)-Dissolved			101.0		%		80-120	04-FEB-20

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 3 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
MET-D-CCMS-WT		Water						
Batch	R4989086							
WG3268919-2		LCS						
Sodium (Na)-Dissolved			101.6		%		80-120	04-FEB-20
Strontium (Sr)-Dissolved			104.3		%		80-120	04-FEB-20
Thallium (Tl)-Dissolved			100.3		%		80-120	04-FEB-20
Tin (Sn)-Dissolved			97.6		%		80-120	04-FEB-20
Titanium (Ti)-Dissolved			96.5		%		80-120	04-FEB-20
Tungsten (W)-Dissolved			101.3		%		80-120	04-FEB-20
Uranium (U)-Dissolved			106.8		%		80-120	04-FEB-20
Vanadium (V)-Dissolved			101.3		%		80-120	04-FEB-20
Zinc (Zn)-Dissolved			96.8		%		80-120	04-FEB-20
Zirconium (Zr)-Dissolved			99.6		%		80-120	04-FEB-20
WG3268919-1		MB						
Aluminum (Al)-Dissolved			<0.0050		mg/L		0.005	04-FEB-20
Antimony (Sb)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Arsenic (As)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Barium (Ba)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Beryllium (Be)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Bismuth (Bi)-Dissolved			<0.000050		mg/L		0.00005	04-FEB-20
Boron (B)-Dissolved			<0.010		mg/L		0.01	04-FEB-20
Cadmium (Cd)-Dissolved			<0.0000050		mg/L		0.000005	04-FEB-20
Calcium (Ca)-Dissolved			<0.050		mg/L		0.05	04-FEB-20
Chromium (Cr)-Dissolved			<0.00050		mg/L		0.0005	04-FEB-20
Cobalt (Co)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Copper (Cu)-Dissolved			<0.00020		mg/L		0.0002	04-FEB-20
Iron (Fe)-Dissolved			<0.010		mg/L		0.01	04-FEB-20
Lead (Pb)-Dissolved			<0.000050		mg/L		0.00005	04-FEB-20
Magnesium (Mg)-Dissolved			<0.0050		mg/L		0.005	04-FEB-20
Manganese (Mn)-Dissolved			<0.00050		mg/L		0.0005	04-FEB-20
Molybdenum (Mo)-Dissolved			<0.000050		mg/L		0.00005	04-FEB-20
Nickel (Ni)-Dissolved			<0.00050		mg/L		0.0005	04-FEB-20
Phosphorus (P)-Dissolved			<0.050		mg/L		0.05	04-FEB-20
Potassium (K)-Dissolved			<0.050		mg/L		0.05	04-FEB-20
Selenium (Se)-Dissolved			<0.000050		mg/L		0.00005	04-FEB-20
Silicon (Si)-Dissolved			<0.050		mg/L		0.05	04-FEB-20
Silver (Ag)-Dissolved			<0.000050		mg/L		0.00005	04-FEB-20

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 4 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
MET-D-CCMS-WT		Water						
Batch	R4989086							
WG3268919-1 MB								
Sodium (Na)-Dissolved			<0.050		mg/L		0.05	04-FEB-20
Strontium (Sr)-Dissolved			<0.0010		mg/L		0.001	04-FEB-20
Thallium (Tl)-Dissolved			<0.000010		mg/L		0.00001	04-FEB-20
Tin (Sn)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Titanium (Ti)-Dissolved			<0.00030		mg/L		0.0003	04-FEB-20
Tungsten (W)-Dissolved			<0.00010		mg/L		0.0001	04-FEB-20
Uranium (U)-Dissolved			<0.000010		mg/L		0.00001	04-FEB-20
Vanadium (V)-Dissolved			<0.00050		mg/L		0.0005	04-FEB-20
Zinc (Zn)-Dissolved			<0.0010		mg/L		0.001	04-FEB-20
Zirconium (Zr)-Dissolved			<0.00020		mg/L		0.0002	04-FEB-20
MET-T-CCMS-WT		Water						
Batch	R4987537							
WG3268906-2 LCS								
Antimony (Sb)-Total			92.9		%		80-120	04-FEB-20
Arsenic (As)-Total			92.4		%		80-120	04-FEB-20
Cadmium (Cd)-Total			93.1		%		80-120	04-FEB-20
Chromium (Cr)-Total			95.1		%		80-120	04-FEB-20
Cobalt (Co)-Total			95.8		%		80-120	04-FEB-20
Copper (Cu)-Total			95.0		%		80-120	04-FEB-20
Lead (Pb)-Total			93.8		%		80-120	04-FEB-20
Molybdenum (Mo)-Total			95.3		%		80-120	04-FEB-20
Nickel (Ni)-Total			94.6		%		80-120	04-FEB-20
Selenium (Se)-Total			93.3		%		80-120	04-FEB-20
Silver (Ag)-Total			96.2		%		80-120	04-FEB-20
Tin (Sn)-Total			94.2		%		80-120	04-FEB-20
Zinc (Zn)-Total			92.2		%		80-120	04-FEB-20
WG3268906-1 MB								
Antimony (Sb)-Total			<0.00010		mg/L		0.0001	04-FEB-20
Arsenic (As)-Total			<0.00010		mg/L		0.0001	04-FEB-20
Cadmium (Cd)-Total			<0.000005C		mg/L		0.000005	04-FEB-20
Chromium (Cr)-Total			<0.00050		mg/L		0.0005	04-FEB-20
Cobalt (Co)-Total			<0.00010		mg/L		0.0001	04-FEB-20
Copper (Cu)-Total			<0.0010		mg/L		0.001	04-FEB-20
Lead (Pb)-Total			<0.000050		mg/L		0.00005	04-FEB-20

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 5 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
MET-T-CCMS-WT		Water						
Batch R4987537								
WG3268906-1 MB								
Molybdenum (Mo)-Total			<0.000050		mg/L		0.00005	04-FEB-20
Nickel (Ni)-Total			<0.00050		mg/L		0.0005	04-FEB-20
Selenium (Se)-Total			<0.000050		mg/L		0.00005	04-FEB-20
Silver (Ag)-Total			<0.000050		mg/L		0.00005	04-FEB-20
Tin (Sn)-Total			<0.00010		mg/L		0.0001	04-FEB-20
Zinc (Zn)-Total			<0.0030		mg/L		0.003	04-FEB-20
NH3-F-WT		Water						
Batch R4987506								
WG3268275-2 LCS								
Ammonia, Total (as N)			99.9		%		85-115	03-FEB-20
WG3268275-1 MB								
Ammonia, Total (as N)			<0.010		mg/L		0.01	03-FEB-20
Batch R4990204								
WG3268942-2 LCS								
Ammonia, Total (as N)			92.9		%		85-115	04-FEB-20
WG3268942-1 MB								
Ammonia, Total (as N)			<0.010		mg/L		0.01	04-FEB-20
NO2-IC-WT		Water						
Batch R4989990								
WG3269520-2 LCS								
Nitrite (as N)			101.1		%		90-110	04-FEB-20
WG3269520-1 MB								
Nitrite (as N)			<0.010		mg/L		0.01	04-FEB-20
NO3-IC-WT		Water						
Batch R4989990								
WG3269520-2 LCS								
Nitrate (as N)			101.1		%		90-110	04-FEB-20
WG3269520-1 MB								
Nitrate (as N)			<0.020		mg/L		0.02	04-FEB-20
OGG-SPEC-WT		Water						
Batch R4990750								
WG3269804-2 LCS								
Oil and Grease, Total			90.3		%		70-130	05-FEB-20
Mineral Oil and Grease			83.8		%		70-130	05-FEB-20
WG3269804-1 MB								
Oil and Grease, Total			<5.0		mg/L		5	05-FEB-20

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 6 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
OGG-SPEC-WT	Water							
Batch	R4990750							
WG3269804-1 MB								
Mineral Oil and Grease			<2.5		mg/L		2.5	05-FEB-20
P-T-COL-WT	Water							
Batch	R4990111							
WG3268452-2 LCS								
Phosphorus, Total			98.5		%		80-120	05-FEB-20
WG3268452-1 MB								
Phosphorus, Total			<0.0030		mg/L		0.003	05-FEB-20
PH-WT	Water							
Batch	R4989650							
WG3269181-2 LCS								
pH			6.96		pH units		6.9-7.1	04-FEB-20
PHENOLS-4AAP-WT	Water							
Batch	R4989709							
WG3268491-2 LCS								
Phenols (4AAP)			103.7		%		85-115	04-FEB-20
WG3268491-1 MB								
Phenols (4AAP)			<0.0010		mg/L		0.001	04-FEB-20
PO4-DO-COL-WT	Water							
Batch	R4991531							
WG3271575-2 LCS								
Orthophosphate-Dissolved (as P)			107.0		%		80-120	07-FEB-20
WG3271575-1 MB								
Orthophosphate-Dissolved (as P)			<0.0030		mg/L		0.003	07-FEB-20
SO4-IC-N-WT	Water							
Batch	R4989990							
WG3269520-2 LCS								
Sulfate (SO4)			101.6		%		90-110	04-FEB-20
WG3269520-1 MB								
Sulfate (SO4)			<0.30		mg/L		0.3	04-FEB-20
SOLIDS-TDS-WT	Water							
Batch	R4992754							
WG3271670-2 LCS								
Total Dissolved Solids			97.3		%		85-115	07-FEB-20
WG3271670-1 MB								

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 7 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
SOLIDS-TDS-WT	Water							
Batch	R4992754							
WG3271670-1 MB								
Total Dissolved Solids			<10		mg/L		10	07-FEB-20
SOLIDS-TSS-WT	Water							
Batch	R4991530							
WG3270932-2 LCS								
Total Suspended Solids			96.9		%		85-115	07-FEB-20
WG3270932-1 MB								
Total Suspended Solids			<2.0		mg/L		2	07-FEB-20
SULPHIDE-WT	Water							
Batch	R4990438							
WG3270258-2 LCS								
Sulphide (as S)			100.0		%		75-125	05-FEB-20
WG3270258-1 MB								
Sulphide (as S)			<0.018		mg/L		0.018	05-FEB-20
TKN-WT	Water							
Batch	R4988370							
WG3268444-2 LCS								
Total Kjeldahl Nitrogen			107.2		%		75-125	04-FEB-20
WG3268444-1 MB								
Total Kjeldahl Nitrogen			<0.15		mg/L		0.15	04-FEB-20
TURBIDITY-WT	Water							
Batch	R4989740							
WG3267944-2 LCS								
Turbidity			99.0		%		85-115	01-FEB-20
WG3267944-1 MB								
Turbidity			<0.10		NTU		0.1	01-FEB-20
VOC-ROU-HS-WT	Water							
Batch	R4987130							
WG3268332-1 LCS								
1,1,2,2-Tetrachloroethane			109.4		%		70-130	04-FEB-20
1,2-Dichlorobenzene			103.5		%		70-130	04-FEB-20
1,4-Dichlorobenzene			98.1		%		70-130	04-FEB-20
Benzene			109.0		%		70-130	04-FEB-20
Chloroform			107.7		%		70-130	04-FEB-20
Dichloromethane			111.3		%		70-130	04-FEB-20
Ethylbenzene			98.3		%		70-130	04-FEB-20



Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 8 of 9

Test	Matrix	Reference	Result	Qualifier	Units	RPD	Limit	Analyzed
VOC-ROU-HS-WT		Water						
Batch	R4987130							
WG3268332-1	LCS							
Tetrachloroethylene			96.6		%		70-130	04-FEB-20
Toluene			100.8		%		70-130	04-FEB-20
Trichloroethylene			99.0		%		70-130	04-FEB-20
WG3268332-2	MB							
1,1,2,2-Tetrachloroethane			<0.50		ug/L		0.5	04-FEB-20
1,2-Dichlorobenzene			<0.50		ug/L		0.5	04-FEB-20
1,4-Dichlorobenzene			<0.50		ug/L		0.5	04-FEB-20
Benzene			<0.50		ug/L		0.5	04-FEB-20
Chloroform			<1.0		ug/L		1	04-FEB-20
Dichloromethane			<2.0		ug/L		2	04-FEB-20
Ethylbenzene			<0.50		ug/L		0.5	04-FEB-20
Tetrachloroethylene			<0.50		ug/L		0.5	04-FEB-20
Toluene			<0.50		ug/L		0.5	04-FEB-20
Trichloroethylene			<0.50		ug/L		0.5	04-FEB-20
Surrogate: 1,4-Difluorobenzene			99.0		%		70-130	04-FEB-20
Surrogate: 4-Bromofluorobenzene			96.7		%		70-130	04-FEB-20

Quality Control Report

Workorder: L2412214

Report Date: 11-FEB-20

Page 9 of 9

Legend:

Limit	ALS Control Limit (Data Quality Objectives)
DUP	Duplicate
RPD	Relative Percent Difference
N/A	Not Available
LCS	Laboratory Control Sample
SRM	Standard Reference Material
MS	Matrix Spike
MSD	Matrix Spike Duplicate
ADE	Average Desorption Efficiency
MB	Method Blank
IRM	Internal Reference Material
CRM	Certified Reference Material
CCV	Continuing Calibration Verification
CVS	Calibration Verification Standard
LCSD	Laboratory Control Sample Duplicate

Hold Time Exceedances:

All test results reported with this submission were conducted within ALS recommended hold times.

ALS recommended hold times may vary by province. They are assigned to meet known provincial and/or federal government requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by the US EPA, APHA Standard Methods, or Environment Canada (where available). For more information, please contact ALS.

The ALS Quality Control Report is provided to ALS clients upon request. ALS includes comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against pre-determined data quality objectives to provide confidence in the accuracy of associated test results.

Please note that this report may contain QC results from anonymous Sample Duplicates and Matrix Spikes that do not originate from this Work Order.



1. If any water samples are taken from a **Regulated Drinking Water (DW) System**, please submit using an **Authorized DW COC form**.

Page of the white - report copy.

Appendix G

MECP Well Records and Well Survey Results (Summary)



eNGLOBE

TOWNSHIP CON LOT	UTM	DATE CNTR	CASING DIA	WATER	PUMP TEST	WELL USE	SCREEN	WELL	FORMATION
NORTH DORCHESTER TOW TR N 04 008	17 493974 4759213 W	1962/08 2801	5					4102900 ()	CLAY MSND 0003 MSND GRVL BLD R 0008 CLAY BLD R 0026 MSND GRVL 0028 WHIT CLAY BLD R 0031 ROCK 0036
NORTH DORCHESTER TOW TR S A 020	17 493874 4759063 W	1962/07 2801	10					4102938 ()	LOAM MSND 0006 GRVL CLAY 0012 CLAY GRVL 0019 CLAY MSND 0027 GRVL 0031
NORTH DORCHESTER TOW TR S A 018	17 494159 4759188 W	1953/03 2801	4 4 4	FR	39/40/19/7:0	NU	0055 7	4102950 ()	LOAM 0001 MSND GRVL CLAY 0045 MSND GRVL 0057 BLD R MSND GRVL 0062 MSND GRVL BLD R 0072 ROCK 0074
NORTH DORCHESTER TOW TR S A 019	17 494574 4758703 W	1965/06 1708	4 4	FR 0067	44/64/7/8:0	DO	0059 3	4102952 ()	PRDR 0067 MSND 0069 BLD R 0070
NORTH DORCHESTER TOW TR S A 020	17 493574 4758503 W	1956/06 1708	6 6	FR 0063	15/45/2/4:0	DO		4102953 ()	YLLW MSND 0025 STNS HPAN 0052 MSND 0053 HPAN 0063 GRVL 0064
NORTH DORCHESTER TOW TR S A 020	17 493554 4758733 W	1956/06 1708	6 6	FR 0068	15/21/8/8:0	DO		4102954 ()	LOAM 0002 HPAN 0068 MSND 0070
NORTH DORCHESTER TOW TR S A 020	17 493794 4758865 L	1962/07 2801	10					4102955 ()	LOAM MSND 0002 MSND 0006 CLAY MSND 0026 CLAY GRVL ROCK 0027
NORTH DORCHESTER TOW TR S A 020	17 493794 4758865 L	1962/07 2801	10					4102956 ()	LOAM MSND 0001 MSND 0006 CLAY MSND GRVL 0029 ROCK 0030
NORTH DORCHESTER TOW TR S A 020	17 493574 4758673 W	1965/07 4741	6	FR 0055	10/14/8/24:0	DO	0055 3	4102957 ()	HPAN STNS 0055 GRVL 0058
NORTH DORCHESTER TOW TR S A 020	17 493574 4758943 W	1966/08 1708	5 5	SU 0051	11/18/10/8:0	DO		4102958 ()	CLAY BLD R 0003 YLLW MSND 0016 BLUE CLAY MSND 0034 BLUE CLAY 0046 MSND SILT 0051 LMSN 0052
NORTH DORCHESTER TOW TR S A 020	17 493534 4758793 W	1968/09 1708		5 FR 0060	10/45/12/12:0	DO		4104566 ()	LOAM 0001 GRVL STNS 0011 GREY CLAY GRVL 0018 GREY CLAY 0037 GREY CLAY GRVL STNS 0060 MSND GRVL 0062
NORTH DORCHESTER TOW TR S A 019	17 494634 4758573 W	1972/11 2644	6					4106110 ()	LOAM 0001 SAND GRVL 0002 SAND 0052 SAND GRVL 0055 SILT 0058 CLAY SILT STNS 0083 GREY CLAY 0090 SILT SAND 0092 LMSN 0098
NORTH DORCHESTER TOW TR S A 020	17 493528 4758876 W	1974/10 1708	5	FR 0067	23/30/9/8:0	DO		4107012 ()	LOAM 0001 YLLW SAND 0002 GREY CLAY STNS 0010 GREY CLAY GRVL 0025 GREY CLAY SAND GRVL 0048 GREY CLAY GRVL 0053 GREY CLAY SAND SILT 0065 GREY CLAY GRVL 0066 BRWN SAND 0067
NORTH DORCHESTER TOW TR S A 020	17 493614 4758583 W	1975/08 1708	5	FR 0040	4/27/16/8:0	DO		4107534 ()	BLCK LOAM 0001 BRWN SAND 0008 GREY CLAY STNS 0020 GREY CLAY GRVL 0040 CGVL 0041
NORTH DORCHESTER TOW TR S A 020	17 493654 4758843 W	1976/06 1708	5	FR 0063	9/27/13/8:0	DO		4107861 ()	SAND 0005 CLAY GRVL STNS 0023 CLAY GRVL 0043 GREY LMSN 0045 GRVL STNS CLAY 0063 LMSN 0064
NORTH DORCHESTER TOW TR S A 020	17 493574 4758543 W	1976/10 1708	5	FR 0045	5/26/8/5:0	DO		4107872 ()	BRWN SAND 0010 GREY SAND 0018 GRVL CLAY 0038 SAND GRVL CMTD 0045 GRVL 0046
NORTH DORCHESTER TOW TR S A 019	17 494634 4758543 W	1979/06 4741	5	FR 0013	37/45/8/5:0	DO	0051 3	4108889 ()	LOAM 0001 BRWN SAND CLAY LYRD 0055 CLAY HARD 0092 LMSN 0092
NORTH DORCHESTER TOW TR S A 019	17 494534 4758823 W	1979/04 5413	8	FR 0059	48///:	DO	0061 12	4109170 ()	BRWN SAND STNS DRY 0019 GREY CLAY STNS HPAN 0032 GREY CLAY SILT SOFT 0052 GREY CLAY STNS HARD 0059 BRWN SAND WDFR STNS 0073
NORTH DORCHESTER TOW TR S B 019	17 494634 4758483 W	1981/04 4741	5	FR 0045	39/45/10/2:0	DO	0057 3	4109513 ()	BRWN SAND CLAY DRY 0045 FSND CLN 0061
NORTH DORCHESTER TOW TR S A 019	17 494614 4758763 W	1981/04 4741	5	FR 0055	45/51/10/2:0	DO	0064 5	4109514 ()	BRWN SAND CLAY DRY 0055 FSND CLN 0070
NORTH DORCHESTER TOW TR S A 019	17 494614 4758743 W	1981/04 4741	5	FR 0055	45/51/10/2:0	DO	0064 3	4109515 ()	BRWN SAND CLAY DRTY 0055 FSND CLN 0070
NORTH DORCHESTER TOW TR S A 019	17 494514 4758523 W	1981/04 4741	5	FR 0045	39/45/10/2:0	DO	0056 3	4109516 ()	BRWN SAND CLAY DRY 0045 FSND CLN 0060
NORTH DORCHESTER TOW TR S A 019	17 494514 4758783 W	1981/11 4741	6	FR 0070	//200/:	MN	0070 8	4109693 ()	LOAM 0001 BRWN SAND 0070 GRVL 0078 CLAY GRVL 0081
NORTH DORCHESTER TOW TR S A 019	17 494634 4758643 W	1982/11 4741	5	FR 0045	39/45/10/1:0	DO	0057 3	4109805 ()	LOAM FILL 0002 BRWN SAND 0045 SAND 0061
NORTH DORCHESTER TOW TR S A 019	17 494434 4758923 W	1983/07 4741	5	FR 0045	39/45/10/1:0	DO	0057 3	4109877 ()	LOAM FILL 0002 BRWN SAND 0045 SAND 0061
NORTH DORCHESTER TOW TR S A 019	17 494614 4758683 W	1983/08 4741	5	FR 0045	39/45/10/1:0	DO	0057 3	4109878 ()	LOAM FILL 0002 BRWN SAND 0045 SAND 0061
NORTH DORCHESTER TOW TR S A 019	17 494434 4758903 W	1983/07 4741	5	FR 0045	39/45/10/1:0	DO	0057 3	4109879 ()	LOAM FILL 0002 BRWN SAND 0045 SAND 0061
NORTH DORCHESTER TOW TR S A 019	17 494554 4758823 W	1979/07 4741	5	FR 0055	47/53/12/2:0	DO	0074 3	4108888 ()	LOAM 0001 BRWN SAND HARD 0055 BRWN SAND 0070 GRVL 0078 CLAY 0078
NORTH DORCHESTER TOW TR S A 019	17 494494 4758743 W	1984/05 4741	5	FR 0052	42/51/10/1:0	DO	0066 4	4110043 ()	BRWN SAND 0052 SAND 0070
NORTH DORCHESTER TOW TR S A 019	17 494494 4758723 W	1984/05 4741	5	FR 0048	40/48/10/1:0	DO	0063 4	4110044 ()	BRWN SAND 0048 SAND 0067
NORTH DORCHESTER TOW TR S A 019	17 494494 4758683 W	1984/05 4741	5	FR 0048	40/48/10/1:0	DO	0064 3	4110045 ()	BRWN SAND 0048 SAND 0067
NORTH DORCHESTER TOW TR S A 018	17 494594 4758883 W	1984/12 4741	5	FR 0040	41/42/10/2:0	DO	0060 3	4110125 ()	BRWN SAND 0040 BRWN CSND 0064
NORTH DORCHESTER TOW TR S A 018	17 494674 4758883 W	1984/12 4741	5	FR 0040	41/43/10/2:0	DO		4110126 ()	BRWN SAND 0040 BRWN CSND 0067
NORTH DORCHESTER TOW TR S A 018	17 494634 4758923 W	1984/12 4741	5	FR 0040	40/41/10/1:0	DO	0057 3	4110143 ()	BRWN SAND 0040 BRWN CSND 0060
NORTH DORCHESTER TOW TR S A 018	17 494634 4758743 W	1985/05 4741	5	FR 0035	//10/1:0	DO	0066 3	4110217 ()	BRWN SAND 0035 GREY CSND 0069
NORTH DORCHESTER TOW TR S A 018	17 494654 4758703 W	1985/07 4741	5	FR 0040	45/47/10/2:0	DO	0067 3	4110324 ()	BRWN SAND 0040 GREY SAND 0070
NORTH DORCHESTER TOW TR S A 018	17 494654 4758603 W	1985/07 4741	5	FR 0038	45/47/10/2:0		0060 3	4110325 ()	BRWN SAND 0038 BRWN SAND WBRG 0063 CLAY 0065
NORTH DORCHESTER TOW TR S A 018	17 494654 4758683 W	1985/07 4741	5	FR 0040	45/47/10/2:0	DO	0065 3	4110326 ()	BRWN SAND 0040 GREY SAND 0070
NORTH DORCHESTER TOW TR S A 018	17 494614 4758783 W	1985/07 4741	5	FR 0040	45/47/10/2:0	DO	0067 3	4110327 ()	BRWN SAND 0040 GREY SAND 0070
NORTH DORCHESTER TOW TR S A 019	17 494634 4758543 W	1985/08 4741	5	FR 0035	35/39/10/0:1	DO	0048 3	4110328 ()	BRWN SAND 0035 GREY SAND 0055
NORTH DORCHESTER TOW TR S A 019	17 494214 4758883 W	1985/05 4741	1	FR 0027	4///:	NU	0023 3	4110329 ()	SAND 0022 GRVL 0027 CLAY 0030
NORTH DORCHESTER TOW TR S A 019	17 494194 4758883 W	1985/05 4741	2	FR 0027	4///:		0022 4	4110330 ()	SAND 0022 GRVL 0027 CLAY 0030
NORTH DORCHESTER TOW TR S A 019	17 494454 4758863 W	1985/05 4741	7	FR 0070				4110333 ()	BRWN SAND 0030 CLAY SAND 0050 SAND WBRG 0070
NORTH DORCHESTER TOW TR S A 019	17 494194 4758783 W	1985/05 4741	7					4110335 ()	SAND 0025 CLAY 0052 GRVL STNS 0054 CLAY 0085
NORTH DORCHESTER TOW TR S A 019	17 494454 4759263 W	1985/05 4741	7					4110336 ()	GRVL 0012 BRWN CLAY 0017 BLUE CLAY STNS 0040
NORTH DORCHESTER TOW TR S A 019	17 494314 4758963 W	1985/05 4741						4110337 ()	BRWN SAND 0006 BRWN FSND SILT 0016 BRWN FSND SILT 0043 BRWN FSND MSND 0051 BRWN SAND GRVL 0053 GREY CLAY 0063 GREY CLAY GRVL 0073 GREY GRVL CLAY HARD 0079 GREY LMSN 0081
NORTH DORCHESTER TOW TR S A 020	17 493974 4759063 W	1985/05 4741	5	FR 0016	5/11/20/24:0		0013 3	4110338 ()	BRWN CLAY SNDY 0010 CGVL 0016
NORTH DORCHESTER TOW TR S A 019	17 494074 4759143 W	1985/10 4741	5	FR 0010	2/10/10/1:0		0006 4	4110339 () A	BRWN CLAY SILTY 0006 BRWN GRVL 0010
NORTH DORCHESTER TOW TR S A 019	17 494494 4758623 W	1985/07 4741	5	FR 0036	36/45/10/1:0	DO	0059 3	4110340 ()	BRWN SAND 0036 SAND WBRG 0062 CLAY 0066
NORTH DORCHESTER TOW TR S A 019	17 494514 4758583 W	1985/08 4741	5	FR 0038	38/45/10/1:0	DO	0057 3	4110341 ()	BRWN CLAY 0038 GREY SAND 0055 CSND 0062

TOWNSHIP CON LOT	UTM	DATE CNTR	CASING DIA	WATER	PUMP TEST	WELL USE	SCREEN	WELL	FORMATION
NORTH DORCHESTER TOW TR S A 019	17 494454 4758663 W	1985/08 4741	5	FR 0040	40/47/10/2:0	DO	0059 3	4110342 ()	BRWN SAND 0040 GREY SAND 0058 CSND GRVL 0065
NORTH DORCHESTER TOW TR S A 019	17 494494 4758703 W	1985/08 4741	5	FR 0040	39/47/10/1:0	DO	0059 3	4110343 ()	BRWN CLAY 0040 GREY SAND 0058 CSND 0064
NORTH DORCHESTER TOW TR S A 019	17 494374 4759343 W	1985/10 4741	10	SU 0064	///24:0			4110332 ()	GRVL 0003 BRWN CLAY 0017 BLUE CLAY STNS 0045 GREY LMSN 0078
NORTH DORCHESTER TOW TR S A 019	17 494144 4758788 W	1986/09 4741	5	FR 0005	3/17/30/72:0	MN	0026 4	4110676 (NA)	BRWN SAND SILT 0005 BRWN SAND 0022 GREY FSND 0025 CGVL SNDS 0029 GRVL CLAY 0030
NORTH DORCHESTER TOW TR S A 019	17 494134 4758783 W	1986/09 4741	5	FR 0005	3/13/30/72:0	MN	0026 4	4110677 (NA)	BRWN SAND SILT 0005 BRWN SAND 0022 GREY FSND 0025 CGVL SAND 0029 GRVL CLAY 0030
NORTH DORCHESTER TOW TR S A 019	17 494147 4758789 W	1986/09 4741	5	FR 0005	3//20/1:0	NU	0019 4	4110678 (NA)	BRWN SAND SILT 0005 BRWN SAND 0018 GREY GRVL SAND 0023 GRVL CLAY 0024
NORTH DORCHESTER TOW TR S A 019	17 494179 4758798 W	1986/11 4741	5	FR 0005	6/14/25/24:0	DO	0018 4	4110679 (NA)	BRWN SAND SILT 0005 BRWN SAND 0018 GREY GRVL SAND 0023 GRVL SAND 0024
NORTH DORCHESTER TOW TR S A 019	17 494164 4758793 W	1986/09 4741	5	FR 0005	3/16/25/72:0	MN	0018 4	4110680 (NA)	BRWN SAND SILT 0005 BRWN SAND 0017 GRVL SAND 0022 GRVL CLAY 0023
NORTH DORCHESTER TOW TR S A 019	17 494659 4758653 W	1986/09 4741	5	FR 0038	32/43/10/1:0	DO	0064 3	4110681 (NA)	BRWN SAND 0038 GREY CSND 0067
NORTH DORCHESTER TOW TR S A 019	17 494679 4758563 W	1986/09 4741	5	FR 0038	32/43/10/1:0	DO	0057 3	4110682 (NA)	BRWN SAND 0038 GREY CSND 0060
NORTH DORCHESTER TOW TR S B 018	17 495009 4758573 W	1987/06 1708	5	FR 0051	28/41/5/4:0	DO	0047 4	4110864 (NA)	BRWN SAND 0022 YLLW SAND 0041 STNS GRVL 0045 BRWN SAND SLTY 0047 SAND GRVL 0051 SAND GRVL CMTD 0052
NORTH DORCHESTER TOW TR S A 018	17 494694 4758543 W	1987/11 5466	5	FR 0061	39/47/12/6:0	DO	0058 3	4111046 (03859)	BRWN SAND PKCD 0056 BRWN CSND GRVL LOOS 0061
NORTH DORCHESTER TOW TR S A 021	17 493424 4758983 W	1988/08 4741	5	SU 0005	29/35/12/1:0	CO	0059 3	4111489 (39807)	BRWN SAND 0012 BLUE CLAY STNS 0059 GRVL 0062
NORTH DORCHESTER TOW TR S B 020	17 493720 4757866 W	1988/06 5466	6	FR 0123	49/68/15/24:0	DO ST		4111587 (39942)	BRWN SAND PKCD 0008 BRWN CLAY SAND PKCD 0010 BRWN SAND PKCD 0074 GREY FSND CLAY 0093 GREY GRVL SAND CLAY 0115 GREY GRVL CLAY PKCD 0122 GREY GRVL PORS 0123
NORTH DORCHESTER TOW TR S A 018	17 494332 4758917 W	1989/03 5466	5 4 4	FR 0050	30/38/12/1:0	DO	0043 3 0043	4112086 (46703)	BLCK LOAM PORS 0001 BRWN SAND GRVL PKCD 0006 BRWN SAND PKCD 0043 BRWN MSND LOOS 0050 GREY GRVL PKCD 0052
NORTH DORCHESTER TOW TR S A 019	17 494312 4758889 W	1990/06 3563	5	FR 0049	30/46/12/2:0	DO	0046 3	4112087 (75626)	BRWN SAND 0006 GREY SAND 0046 GREY GRVL 0049
NORTH DORCHESTER TOW TR S A 019	17 494320 4758854 W	1990/06 3563	5	FR 0051	31/48/12/5:0	IR	0049 49	4112101 (75639)	BRWN SAND 0050 GREY STNS SAND 0051
NORTH DORCHESTER TOW TR S B 020	17 494045 4757560 L	2003/05 7190	2			NU	0006 10	4115301 (255950)	BRWN SAND LOAM 0001 UNKN UNKN 0010 GREY SILT 0016
NORTH DORCHESTER TOW	17 494569 4758985 W	2007/05 3366	1.25	FR 0025	25//8/1:	IR	0032 4	7046016 (Z52840) A046982	SAND 0036
NORTH DORCHESTER TOW	17 494506 4758957 W	2007/05 3366	1.25	FR 0027	27//10/1:	IR	0034 4	7046017 (Z52849) A046981	SAND 0038
NORTH DORCHESTER TOW A 21	17 493400 4758765 W	2007/11 7090	30.6	FR 0017 FR 0026	17/27/5/2:30	DO		7101341 (Z75041) A047822	BLCK LOAM LOAM 0002 BRWN SAND GRVL 0026 GREY GRVL HPAN HARD 0050
NORTH DORCHESTER TOW	17 494552 4758960 W	2009/05 3366	1.25	FR 0026	26/26/5/1:0	IR	0032 4	7124369 (Z92693) A068895	SAND 0036
NORTH DORCHESTER TOW TR S B 018	17 494539 4758103 W	2009/05 7190	2			MO	0005 15	7124841 (Z91226) A047892	BRWN SAND DRY 0005 BRWN SAND 0010 BRWN SAND 0015 GREY CLAY SOFT 0020
NORTH DORCHESTER TOW	17 493625 4758402 W	2010/09 3366	6					7153878 (Z113673) A086008 A	
NORTH DORCHESTER TOW TR S A 018	17 493074 4758983 W	1971/11 2607	36	FR 0020	20//:	DO		4105677 ()	BRWN MSND 0017 GRVL BLDR 0022 BLUE CLAY 0025
NORTH DORCHESTER TOW TR S A 021	17 493064 4758963 W	1960/11 3410	5	FR 0063	13/40/4/24:0	DO		4102961 ()	BLCK LOAM 0002 GRVL 0012 HPAN 0053 STNS GRVL 0063 GRVL 0064
NORTH DORCHESTER TOW TR S A 021	17 493154 4758963 W	1960/10 1708	5 5	SU 0067	23/58/7/8:0	DO		4102960 ()	CLAY STNS 0029 HPAN 0065 BRWN LMSN 0069
NORTH DORCHESTER TOW TR S B 020	17 493750 4757788 W	2017/06 7090	6 6	UT 0082	37/44/15/1:0	DO	0069 12	7290286 (Z260360) A216698	BLCK LOAM LOAM 0001 BRWN SAND SILT LYRD 0014 BRWN FSND 0034 BRWN SAND LOOS 0070 BRWN FSND CLN 0082 GREY SILT SOFT 0086
NORTH DORCHESTER TOW TR S B 020	17 493779 4757758 W	2017/06 7090	6 6	UT 0082	29/40/15/1:30	DO	0069 12	7290287 (Z260363) A216697	BLCK LOAM LOAM 0001 BRWN SAND ---- DRY 0012 BRWN FSND 0035 BRWN FSND CLN 0069 BRWN SAND ---- 0082 GREY SILT CLAY LYRD 0086
NORTH DORCHESTER TOW TR S B 020	17 493786 4757725 W	2017/06 7090	6 6	UT 0080	19/30/15/1:30	DO	0068 12	7290288 (Z260362) A216696	BLCK LOAM LOAM 0001 BRWN SAND ---- 0011 BRWN FSND CLN 0062 BRWN SAND ---- 0080 GREY SAND ---- 0085
NORTH DORCHESTER TOW TR S B 018	17 495294 4758023 W	1986/02 1708	2	FR 0025	7//20/1:0		0026 5	4110619 (NA)	LOAM 0002 BRWN SAND SILT 0018 BRWN GRVL SAND 0025 GREY GRVL SAND 0031 GREY CLAY GRVL CMTD 0042
NORTH DORCHESTER TOW TR S B 018	17 493750 4757885 W	2017/06 7090	6 6	UT 0079	42/49/10/1:30	OT OT	0067 12	7290291 (Z260370) A216692	BLCK LOAM LOAM 0002 BRWN CLAY ---- LYRD 0011 BRWN FSND ---- 0029 BRWN SAND CLN 0066 GREY FSND CLN 0079 GREY CLAY SOFT 0084
NORTH DORCHESTER TOW TR S B 018	17 495249 4757858 W	2021/05 7534	1.25	FR 0015	//15/1:	IR	0024 3	7413606 (WDLH6ZWD) A325180	BRWN SAND 0015
NORTH DORCHESTER TOW TR S B 018	17 495245 4758461 W	2021/03 7190	2 4	UT 0012	12//:	MO	0020 5	7384169 (NPDDT895) A316308	BRWN SAND LOOS 0025
NORTH DORCHESTER TOW TR S B 018	17 495161 4758141 W	2021/03 4876						7408332 (Z352355) A229683 A P	
NORTH DORCHESTER TOW TR S B 018	17 495156 4758119 W	2021/03 4876						7408331 (Z352353) A238071 A P	
NORTH DORCHESTER TOW TR S B 019	17 494637 4757680 L	2003/07 3563	6 5	FR 0058	37/46/10/3:0	DO	0050 8	4115364 (259605)	BRWN SAND 0059
NORTH DORCHESTER TOW TR S B 020	17 494637 4757680 L	2003/07 3563				DO		4115365 (259604) A	
NORTH DORCHESTER TOW TR S B 020	17 493908 4758277 W	2019/07 7190	4 2	UT 0025	25//:	MO	0030 5	7354509 (DRFM8BD4) A273374	BRWN SAND DNSE 0025 BRWN SAND 0034
NORTH DORCHESTER TOW TR S B 020	17 494247 4757763 W	2019/08 7190	4 2	UT 0028	9//:	MO	0025 5	7354510 (6RDHYBAG) A273379	BRWN LOAM LOOS 0001 BRWN SILT CLAY HARD 0010 GREY SILT CLAY SOFT 0028 BRWN FSND LOOS 0029 GREY SILT CLAY TILL 0030
NORTH DORCHESTER TOW TR S B 020	17 494454 4756843 W	1978/11 1708	5	FR 0083	32/33/15/4:0	DO	0088 3	4108771 ()	FILL 0008 BRWN SAND 0044 GREY CLAY 0074 GREY CLAY GRVL 0083 GRVL SAND 0091 GREY CLAY DNSE 0092
NORTH DORCHESTER TOW TR S A 020	17 494494 4756883 W	1984/06 1708	5	FR 0075 UK 0089	34/35/10/3:0	DO	0084 4	4110139 ()	BRWN CLAY 0018 BRWN SAND FSND 0054 GREY CLAY 0066 GREY CLAY GRVL 0075 GRVL SAND 0089
NORTH DORCHESTER TOW TR S A 020	17 494078 4758532 W	2019/07 7190	4 2	UT 0014	14//:	MO	0014 5	7354654 (Q8TXQJHH) A273373	BRWN SAND DNSE 0006 BRWN CLAY SLTY TILL 0014 BRWN SAND 0018
NORTH DORCHESTER TOW TR S A 020	17 493604 4758383 W	2020/07 7090	6 6	UT 0077	18/29/10/:	DO		7363010 (Z331271) A237007	BRWN LOAM 0001 BRWN CLAY 0014 GREY CLAY STNS 0042 GREY CLAY SAND 0077 GREY LMSN 0080
NORTH DORCHESTER TOW	17 494967 4758102 W	7675						7393805 (C50345) A323494 P	
NORTH DORCHESTER TOW TR S A 021	17 493343 4758394 W	2021/06 7190	2 4	UT 0013	13//:	MO	0012 5	7394925 (UMU9P268) A323649	BLCK LOAM 0001 BRWN SAND GRVL 0014 GREY SILT SAND 0016 GREY SILT TILL HARD 0018
NORTH DORCHESTER TOW TR S A 021	17 493522 4758315 W	2021/06 7190	2 4	UT 0005	5//:	MO	0008 5	7394926 (HVLAPFPK) A323650	BLCK LOAM 0001 BRWN SAND SILT 0012
NORTH DORCHESTER TOW TR S A 021	17 493242 4758913 W	2021/06 7190	2 4	UT 0010	10//:	MO	0010 5	7394927 (WJOVCARD) A323660	BLCK LOAM SAND 0001 BRWN SAND SILT 0015
NORTH DORCHESTER TOW TR S A 021	17 493497 4758765 W	2021/06 7190	2 4			MO	0015 5	7394928 (DWJE6URC) A323663	BLCK LOAM 0001 BRWN SILT TILL 0008 GREY SILT TILL 0020
NORTH DORCHESTER TOW TR S B 018	17 493530 4758578 W	2021/06 7190	2 4			MO	0015 5	7394929 (XB32QEF6) A323670	BLCK LOAM 0001 BRWN SILT TILL 0003 GREY SILT TILL 0020
NORTH DORCHESTER TOW TR S A 019	17 495040 4758061 W	2021/08 7534	1.25	FR 0017	///1:	IR	0025 3	7405032 (3RLHYDRG) A329459	BRWN SAND 0017
NORTH DORCHESTER TOW TR S A 019	17 494540 4759029 W	2021/06 7534	1.25	FR 0025	///1:	IR	0030 4	7405040 (VWV9LR5A) A325149	BRWN SAND 0025
WESTMINSTER TOWNSHIP NTR	17 475582 4750813 W	2004/09 2604	12		56//:			4115786 (Z08238) A	PRDR 0131
WESTMINSTER TOWNSHIP NTR 065	17 477002 4748890 W	2004/06 7215					0010 5	4115699 (Z13052) A012971	

Appendix H

Residential development and sewer plans




eNGLOBE

DRAFT PLAN OF SUBDIVISION

PART OF LOT 19 & 20 CONCESSION 'A' & PART OF LOT 19 & 20 CONCESSION 'B' SOUTH OF THE RIVER THAMES
GEOGRAPHIC TOWNSHIP OF NORTH DORCHESTER
MUNICIPALITY OF THAMES CENTRE
COUNTY OF MIDDLESEX

INFORMATION REQUIRED UNDER SECTION 51(17) OF THE PLANNING ACT RSO 1990
(A) ON PLAN
(B) ON PLAN
(C) ON PLAN
(D) AS SHOWN ON LAND USE SCHEDULE
(E) NORTH - EXISTING RESIDENTIAL & WETLAND
(F) WEST - EXISTING RESIDENTIAL & WETLAND
(G) EAST - EXISTING RESIDENTIAL, CULTIVATED LANDS
(H) SOUTH - CULTIVATED LANDS, FUTURE RESIDENTIAL
(I) ON PLAN
(J) MUNICIPAL WATER AVAILABLE
(K) STORM SEWERS, SANITARY SEWERS, TELEPHONE, GAS, T.V. CABLE
(L) MUNICIPALITY OF THAMES CENTRE OFFICIAL PLAN ZONING BY-LAW
DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.



KEY PLAN
SCALE: 1:10,000

SUPPLEMENTARY BOUNDARY SCHEDULE


LINE	BLOCK	BEARING	DISTANCE
L100		N 10° 23' 20" W	530.655
L101	XX	N 78° 25' 40" E	322.504
L102		N 11° 14' 45" W	215.819
L103		N 11° 19' 55" W	191.028

LAND USE SCHEDULE


	DESCRIPTION	AREA (ha)
LOTS 1-161	FREEHOLD RESIDENTIAL	10.36
BLOCK 162, 163	MEDIUM DENSITY RESIDENTIAL	1.14
BLOCK 164	HIGH DENSITY RESIDENTIAL	3.92
DEDICATED STREETS	STREETS 'A'-'F', 'H', 'J'	3.57
BLOCK 165, 166	FUTURE ROAD ALLOWANCE	0.17
BLOCK 167, 168	WALKWAY/ SERVICING BLOCKS	0.04
BLOCK 169, 170	OPEN CHANNEL DRAIN/TRAIL CORRIDOR	1.21
BLOCK 171, 172, 173	PARK/ TRAIL CORRIDOR	0.25
BLOCK 174, 175	OPEN SPACE	1.29
BLOCK 176, 177	PARK	1.61
BLOCK 178	STORMWATER MANAGEMENT	1.53
BLOCK 179	ARCHAEOLOGICAL SITE	0.57
BLOCK 180	FUTURE DEVELOPMENT	5.37
BLOCK 181	FUTURE DEVELOPMENT	12.95
BLOCK 182	PARK/ TRAIL CORRIDOR	0.32
TOTAL		44.30

SUBJECT TO THE CONDITIONS, IF ANY, SET FORTH IN OUR LETTER DATED _____ DAY OF _____ 20____ THIS DRAFT PLAN IS APPROVED UNDER SECTION 51 OF THE PLANNING ACT THIS _____ DAY OF _____ 20____

DATE _____ SIGNATURE _____



SCALE: 1:1500



NOTE: ORIGINAL CONTOURS SHOWN FROM 2020 QJUL SURVEY

OWNER'S CERTIFICATE
DOUG TARRY LIMITED, THE REGISTERED OWNER OF THE LANDS TO BE SUBDIVIDED, HEREBY AUTHORIZES CJD CONSULTING ENGINEERS TO SUBMIT THIS DRAFT PLAN OF SUBDIVISION FOR APPROVAL.

DATE _____ DOUG TARRY, PRESIDENT, DOUG TARRY LIMITED

SUBDIVIDER'S CERTIFICATE
I HEREBY CERTIFY THAT THE BOUNDARIES OF THE LANDS TO BE SUBDIVIDED AND THEIR RELATIONSHIP TO THE ADJACENT LANDS ARE ACCURATELY AND CORRECTLY SHOWN ON THIS PLAN.

DATE _____ KIM HUSTED, ONTARIO LAND SURVEYOR

PLAN PREPARED BY:
CJD
Consulting Engineers

JOB No. 18010

Cyril J. Demery Limited
P.O. Box 460, 261 Broadway
Tillamook, Ontario, N4G 4K6
Tel: 519-688-1000
886-322-9886
Fax: 519-842-3235
cjd@cjdeng.com

DATE: 2 FEB 2024

MATCHLINE SEE RIGHT KEY PLAN
SUPPLEMENTARY BOUNDARY SCHEDULE

Appendix I

Water balance



eNGLOBE

1. Climate Information

Precipitation (collected from Env. Canada data)	1011,5 mm/a
Evapotranspiration	598,2 mm/a
Water Surplus	413,3 mm/a

2. Infiltration Rates

Infiltration Factors (Table 2, Chapter 4 of MOE, 1995)

Rolling land (modified)	0,2
Open sandy loam	0,3
Cover (cultivated land)	0,1
TOTAL	0,6

Infiltration (0.55 x 446.5 mm/a)	248,0 mm/a
Run-off (Water Surplus - Infiltration)	165,3 mm/a

Typical Recharge Rates (Table 3, Chapter 4, MOE, 1995)

silty sand to sandy silt	150-200 mm/a
fine to medium sand	200-250 mm/a
coarse sand and gravel	250+ mm/a

Site development area is underlain by glaciolacustrine material (sand).

Based on the above, the recharge rate is approximately 248 mm/a
with runoff of 165,3 mm/a

3. Site Statistics

Pre-Development:

Building roofs	0,00 ha	0 m ²
Parking Areas, Roadways, Other impervious Areas	0,00 ha	0 m ²
Green space, open space, natural areas	25,66 ha	256 600 m ²
TOTAL	25,66 ha	256 600 m ²

Post-Development:

			Impervious surfaces
Medium density residential	1,14 ha	11 400 m ²	8550 m ²
High density residential	3,92 ha	39 200 m ²	33320 m ²
Freehold residential	10,36 ha	103 600 m ²	67340 m ²
SWM pond	1,53 ha	15 300 m ²	15 300 m ²
Open channel, archaeological site, parks and open space	4,93 ha	49 300 m ²	0 m ²
Streets and walkways	3,78	37 800 m ²	37800
TOTAL	25,66 ha	256 600 m ²	162 310 m ²

4. Annual Pre-Development Water Balance

Land Use	Area (m ²)	Precipitation (m ³)	Evapotranspiration (m ³)	Infiltration (m ³)	Run-Off (m ³)
Impervious surfaces	0	0	-	-	0
Residential (without impervious)	0	0	-	-	0
Green Space	256 600	259 551	153 498	63 637	42 416
TOTAL	0	259 551	153 498	63 637	42 416

5. Annual Post-Development Water Balance without LID Techniques

Land Use	Area (m ²)	Precipitation (m ³)	Evapotranspiration (m ³)	Infiltration (m ³)	Run-Off (m ³)
Impervious surfaces	162 310	164 177	-	-	164 177
Residential (without impervious surfaces)	44 990	45 507	26 913	11 158	7 437
Green space, open space, natural areas	49 300	49 867	29 491	12 226	8 149
TOTAL	256 600	259 551	56 404	23 384	179 763

6. Comparison of Pre-Development and Post-Development

	Precipitation (m ³)	Evapotranspiration (m ³)	Infiltration (m ³)	Run-Off (m ³)
Pre-Development	259 551	153 498	63 637	42 416
Post-Development	259 551	56 404	23 384	179 763
Change	0	-97 094	-40 253	137 347