

ENVIRONMENTAL NOISE ASSESSMENT MN 233 UPPER QUEEN STREET, THORNDALE

LDS PROJECT NO. LD-00267 APRIL 12, 2022

Submitted to:

MUNICIPALITY OF THAMES CENTRE

Department of Planning and Development

Distribution (via email):

RAND Developments Knutson Development Consultants Inc.

TABLE OF CONTENTS

1.0	Introduction1	į
2.0	Criteria1	1
2.1	Guidelines1	8
3.0	Analysis Procedures)
3.1	Rail Traffic Data2)
3.2	Calculation Methods and Parameters2)
4.0	Projected Noise Levels)
5.0	Conclusions and Recommendations	3

LIST OF TABLES

Table 1 – Noise Criteria for Residential Land Use	1
Table 2 – Rail Day-Time Noise, Ventilation and Warning Clause Requirements	1
Table 3 – Rail Night-Time Noise, Ventilation and Warning Clause Requirements	2
Table 4 – Summary of Rail Traffic Volumes and Parameters	2

LIST OF FIGURES

Figure 1 – Site Location Figure 2 – Site Plan

LIST OF APPENDICES

Appendix A – MOECC and CN Noise Warning Clauses

- Appendix B CN Train Count Data
- Appendix C Stamson Output

1.0 Introduction

LDS Consultants Inc. was retained by RAND Developments to complete an Environmental Noise Assessment for the property located at MN 233 Upper Queen Street in Thorndale. The site is located on the south side of Upper Queen Street and east of Agnes Street, as illustrated in Figure 1. The proposed development is comprised of 0.95 hectares and is proposed for the construction of thirty-eight (38) vacant land condominium (VLC) units. The purpose of this study is to assess the noise impact of railway traffic from CN's Guelph Subdivision rail line on the subject property using the computerized version of the MECP's noise model (STAMSON v5.03). Recommendations for noise control measures will be outlined to achieve acceptable noise levels for future residents of the proposed development while satisfying the planning requirements of the Municipality of Thames Centre.

2.0 Criteria

This report and the included analysis have been prepared to meet the requirements presented in the Ministry of the Environment and Climate Change's (MECP's) publication titled "Environmental Noise Guideline – Stationery and Transportation Sources – Approval and Planning (NPC-300)".

2.1 Guidelines

The MECP has produced noise level guidelines for the use in noise assessment and land use planning. Noise level criteria for residential land use are summarized below in Table 1.

Location	Day-Time (7:00 - 23:00 (16hr))	Night-Time (23:00 - 7:00 (8hr))
Outdoor Living Area	55 dBA	N/A
Indoor Living Area	40 dBA at plane of living room window	35 dBA at plane of bedroom window

Table 1 – Noise Criteria for Residential Land Use

Noise levels in excess of the guidelines presented in Table 1 are acceptable under certain conditions and with certain provisions. Tables 2 and 3 set out noise levels in excess of the specified criteria, and the required provisions to allow residential activity in locations where noise level criteria are exceeded. MECP noise warning clauses are provided in Appendix A.

Table 2 - Rail Day-Time Noise	e, Ventilation and Warning Clause Requirements
-------------------------------	--

Location	Leq (16hr)	Ventilation Requirements	Outdoor Control Measures	Warning Clause
	Leq ≤ 55 dBA	N/A	None required	Not Required
Outdoor Living Area	55 < Leq ≤ 60 dBA	N/A	Control Measures (barriers) not required but should be considered	Required if resultant Leq exceeds 55dBA Type A
	Leq > 60 dBA	N/A	Control measures (barriers) required to reduce the Leq to below 60 dBA and as close to 55dBA as technically, economically, and administratively feasible.	Required if resultant Leq exceeds 60dBA Type B
	Leq ≤ 40 dBA	N/A	N/A	Not Required
Plane of Livingroom Window	40 < Leq ≤ 50 dBA	Forced air heating with provision for central air conditioning	N/A	Required Type C
	Leq > 50 dBA	Central air conditioning	N/A	Required Type D

(Source: MECP's NPC-300 Publication)

Location	Leq (8hr)	Ventilation Requirements	Warning Clause*
Plane of	Leq ≤ 35 dBA	Not Required	Not Required
Bedroom	35 < Leq ≤ 45 dBA	Forced air heating with provision for central air conditioning	Required - Type C
Window	Leq > 45 dBA	Central air conditioning	Required- Type D

Table 3 – Rail Night-Time Noise, Ventilation and Warning Clause Requirements

(Source: MOECC's NPC-300 Publication)

3.0 Analysis Procedures

3.1 Rail Traffic Data

Rail traffic data for the adjacent CN Guelph Subdivision was received from CN, attached in Appendix B. There are two way-freight (<25 cars, 4 engines) and three passenger (<10 cars, 2 engines) trains that travel this segment of CN's rail line during day-time hours. As described in the attached correspondence, rail traffics volumes are expected to increase by 2.5% per annum for 10 years. The projected growth is reflected in the volume of trains outlined in Table 4. There are no train whistle by-laws in the vicinity of the subject site, thus train whistles will be included in the noise calculations. As well, the mainline track was considered to be continuously welded rail throughout the study area as stated in the Train Data.

3.2 Calculation Methods and Parameters

Rail noise levels were calculated using the Stamson v5.03 computer program from the MECP. There is no rail traffic during night-time hours, therefore only day-time noise conditions have been calculated for both indoor and outdoor living areas. These calculations will dictate which units require noise control measures, which depends on the exceedance levels described in Tables 2 and 3. Indoor day-time levels were estimated by placing the receiver 1.5m off the ground surface against the pane of the window (POW). Similarly, the day-time OLA noise levels were estimated by placing the receiver 1.5m off the ground surface against the pane of the ground and 3m off the building envelope. The noise assessment was calculated using 5 rows of houses at a 20% house density, which represents the 5 lots between the railway corridor and the subject site.

Day-time Period (7:00-23:00)	CN Guelph Subdivision Speed Limit = 24 km per hour							
Day-time Period (7.00-23.00)	Number of Trains	Max Length (cars)	Max Engines					
Way Freight	3	25	4					
Passenger	4	10	2					

Table 4 – Summary of Rail Traffic Volumes and Parameters

4.0 Projected Noise Levels

The receiver distance of 94.89m was used for the initial assessment representing the closest distance from the railway corridor to the subject property as shown in Figure 1. The closest distance results in the maximum sound propagation from the rail line. This conservative measure resulted in a Leq of 39.99 dBA which is below the day-time outdoor living area and indoor living area threshold of 55 dBA and 40 dBA respectively, as outlined in Table 2. Unit 36 is the closest VLC unit to the railway situated approximately 100m away, this distance resulted in a Leq of 39.63 dBA. As the receiver moved to the rear of the property the a Leq decreased to 37.76 dBA. The calculated noise levels are provided in Appendix C, and description of noise warning clauses are provided in Appendix A, it being noted that MOECC Warning Clauses aren't applicable to these units as the subject property meets the minimum noise requirements for day-time indoor and outdoor living areas. Additionally, CN's standard warning clause which is required for all residential developments located within 300m of their branch line should be registered on the title of all units, as detailed in Appendix A. It should be noted again that there is no rail traffic at night, thus the assessment was modeled using day-time standards.

5.0 Conclusions and Recommendations

Based on the preceding findings, the following recommendations are made.

- Based on a 10-year projected horizon, Day-time Outdoor Living Area and Day-time Indoor Living Area predicted noise levels are below the MECP's criteria of 55 dBA and 40 dBA respectively. Therefore, noise control barriers and MOECC warning clauses are not required for the subject site;
- CN's standard warning clause should be inserted in all development agreements, offers to purchase, and agreements of purchase and sale or lease of each dwelling unit within 300m of the railway right-of-way, as per Appendix A; and,
- All buildings must be constructed in accordance with the Ontario Building Code.

The inclusion of these measures will allow the residential development to proceed in accordance with the MECP's criteria with respect to environmental noise.

We trust this report to be complete, however should any questions arise please do not hesitate to contact the undersigned.



Connor Brown EIT o: (226) 289-2952 c: (226) 376-2139 e: <u>connor.brown@LDSConsultants.ca</u>

Figures




NOR.BF	EXISTING SERVICES	DRAWING #, SOURCE	DATE	CONSTRUCTED SERVICES	COMPLETION	DETAILS	No.	REVISIONS	DATE	
CON						DESIGN CB				
ň						DRAWN BY CB				
×						CHECKED AG				
38 P						APPROVED AG				
23:3						DATE 2022-03-31				
3:2										
5										
ъ										
7-						7_Site Plan 2022.03.30.	turn			
202					0020	/_Site Fiuli 2022.03.30.	uwg			





SCALE	233 UPPER QUEEN STREET, THORNDALE	PROJECT №. 1614—00267
NOT TO SCALE	RAND DEVELOPMENTS	SHEET No.
	SP1	
		PLAN FILE No.



						PATIO (TYP)]						
	2	3	4	5	6	7	8	9		10	11	12	13	14	
/	DWY	DWY	DWY	DWY	DWY	DWY	DWY	DWY		DWY	DWY	DWY	DWY	DWY	

DWY													
35	34	33	32	31	30	29	28	27	26	25	24	23	
													ļ

	-	 		
			_	

3 0 6m	^{™LE} 233 UPPER QUEEN STREET, THORNDALE RAND DEVELOPMENTS	PROJECT No. 1614-00267 Sheet No.
	FIGURE 2: SITE PLAN	PLAN FILE No.

APPENDIX A

WARNING CLAUSES

MOECC Warning Clauses

The following warning clauses may be used individually or in combination:

TYPE A:

"Purchasers / tenants are advised that sound levels due to increasing road (rail) (air) traffic may occasionally interfere with some activities of the dwelling occupants as the sound levels exceed the Municipality's and the Ministry of the Environment's noise criteria."

TYPE B

"Purchasers / tenants are advised that despite the inclusion of noise control features in the development and within the building units, sound levels due to increasing road (rail) (air) traffic may on occasion interfere with some activities of the dwelling occupants as the sound levels exceed the Municipality's and the Ministry of the Environment's noise criteria."

TYPE C

"This dwelling unit has been fitted with a forced air heating system and the ducting, etc. was sized to accommodate central air conditioning. Installation of central air conditioning by the occupant will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the Municipality's and the Ministry of the Environment's noise criteria. (Note: The location and installation of the outdoor air conditioning device should be done so as to comply with noise criteria of MOE Publication NPC-216, Residential Air Conditioning Devices and thus minimize the noise impacts both on and in the immediate vicinity of the subject property.)"

TYPE D

"This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the Municipality's and the Ministry of the Environment's noise criteria."

CN's Standard Warning Clause

The following clause should be inserted in all development agreements, offers to purchase, and agreements of Purchase and Sale or Lease of each dwelling unit within 300m of the railway right-of-way:

"Warning: Canadian National Railway Company or its assigns or successors in interest has or have a rightsof-way within 300 metres from the land the subject hereof. There may be alterations to or expansions of the railway facilities on such rights-of-way in the future including the possibility that the railway or its assigns or successors as aforesaid may expand its operations, which expansion may affect the living environment of the residents in the vicinity, notwithstanding the inclusion of any noise and vibration attenuating measures in the design of the development and individual dwelling(s). CNR will not be responsible for any complaints or claims arising from use of such facilities and/or operations on, over or under the aforesaid rights-of-way."

APPENDIX B

CN Train Count Data



1 Administration Road Concord, ON, L4K 1B9 T: 905.669.3264 F: 905.760.3406

TRANSMITTAL

To: Destinataire :	LDS Consultants Inc. 15875 Robins Hill Road, Unit 1 London ON N5V0A5	Project :	GPH-110.58- Thorndale Rd. Thorndale, ON			
Att'n:	Joe Vandenberg	Routing:	joe.vandenberg@LDSconsultants.ca			
From: Expéditeur :	Michael Vallins	Date:	2020/05/14			
Cc:	Adjacent Development CN via e-mail					
🗌 Urgent 🗌 For Your Use 🗌 For Review 📕 For Your Information 🗌 Confidential						
Re: Train Traffic Data – CN Guelph Subdivision- Thorndale Road in						
Thorndale	Thorndale, ON					

Please find attached the requested Train Traffic Data; this data does not reflect GO Metrolinx Traffic. The application fee in the amount of **\$500.00** +HST will be invoiced.

Should you have any questions, please do not hesitate to contact the undersigned at 905-669-3264.

Sincerely, CN Design & Construction

11

Michael Vallins P.Eng Manager, Public Works- Eastern Canada permits.gld@cn.ca Date: 2020/05/14

Dear Joe:

Re: Train Traffic Data – CN Guelph Subdivision near Thorndale Rd., Thorndale, ON

The following is provided in response to Joe's 2020/04/02 request for information regarding rail traffic in the vicinity of Thorndale Rd. in Thorndale at approximately Mile 110.58 on CN's Guelph Subdivision.

Typical daily traffic volumes are recorded below. However, traffic volumes may fluctuate due to overall economic conditions, varying traffic demands, weather conditions, track maintenance programs, statutory holidays and traffic detours that when required may be heavy although temporary. For the purpose of noise and vibration reports, train volumes must be escalated by 2.5% per annum for a 10-year period.

Typical daily traffic volumes at this site location are as follows:

Maximum train speed is given in whies					
	0700-2300				
Type of Train	Volumes	Max.Consist	Max. Speed	Max. Power	
Freight	0	140	15	4	
Way Freight	2	25	15	4	
Passenger	3	10	15	2	

*Maximum	train	speed i	s given in	Miles	per Hour
----------	-------	---------	------------	-------	----------

	2300-0700			
Type of Train	Volumes	Max.Consist	Max. Speed	Max. Power
Freight	0	140	15	4
Way Freight	0	25	15	4
Passenger	0	10	15	2

The volumes recorded reflect westbound and eastbound freight and passenger operations on CN's Guelph Subdivision.

Except where anti-whistling bylaws are in effect, engine-warning whistles and bells are normally sounded at all at-grade crossings. There are five (5) at-grade crossing in the immediate vicinity of the study area at Mile 109.76 Conc. 3-4, Lot 17, Mile 110.01 Farm Xing, Mile 110.58 Thorndale Rd., Mile 111.37 Farm Xing and Mile 111.86 City Road 27. Anti-whistling bylaws are not in effect at these crossings. Please note that engine warning whistles may be sounded in cases of emergency, as a safety and or warning precaution at station locations and pedestrian crossings and occasionally for operating requirements.

With respect to equipment restrictions, the gross weight of the heaviest permissible car is 263,000 lbs.

The single mainline track is considered to be continuously welded rail throughout the study area.

The Canadian National Railway continues to be strongly opposed to locating developments near railway facilities and rights-of-way due to potential safety and environmental conflicts. Development adjacent to the Railway Right-of-Way is not appropriate without sound impact mitigation measures to reduce the incompatibility. For confirmation of the applicable rail noise, vibration and safety standards, Adjacent Development, Canadian National Railway Properties at <u>Proximity@cn.ca</u> should be contacted directly.

I trust the above information will satisfy your current request.

Sincerely,

1

Michael Vallins P.Eng Manager, Public Works – Eastern Canada permits.gld@cn.ca

APPENDIX C

STAMSON OUTPUT

STAMSON 5.0 NORMAL REPORT Date: 31-03-2022 10:28:31 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT Time Period: Day/Night 16/8 hours Filename: Description: OLA Daytime Unattenuated 5 house @ 20% Rail data, segment # 1: Way Freight (day/night) -----Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld 1 ! 3.0/0.0 ! 24.0 ! 4.0 ! 25.0 !Diesel! Yes 1. Data for Segment # 1: Way Freight (day/night) Angle1Angle2: -90.00 deg90.00 degWood depth: 0(No woods.No of house rows: 5 / 5House density: 20 %Surface: 1(Absorptive) (No woods.) (Absorptive ground surface) Receiver source distance : 94.89 / 94.89 m Receiver height: 1.50 / 4.50 mTopography: 1 (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Rail data, segment # 2: Passanger (day/night) ------Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld ----+----+----+-----+-----1. ! 4.0/0.0 ! 24.0 ! 2.0 ! 10.0 !Diesel! Yes Data for Segment # 2: Passanger (day/night) Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth:0No of house rows:5 / 5House density:20 %Surface:1 (No woods.) (Absorptive ground surface) Receiver source distance : 94.89 / 94.89 m Receiver height : 1.50 / 4.50 m Topography : 1 (Flat Topography (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Results segment # 1: Way Freight (day) -----LOCOMOTIVE (0.00 + 37.66 + 0.00) = 37.66 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.58 58.59 -12.70 -1.33 0.00 -6.90 0.00 37.66 _____ WHEEL (0.00 + 24.27 + 0.00) = 24.27 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 45.93 -13.30 -1.46 0.00 -6.90 0.00 24.27 Segment Leq : 37.85 dBA Results segment # 2: Passanger (day)

LOCOMOTIVE (0.00 + 35.71 + 0.00) = 35.71 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.58 56.64 -12.70 -1.33 0.00 -6.90 0.00 35.71 _____ WHEEL (0.00 + 21.69 + 0.00) = 21.69 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 43.34 -13.30 -1.46 0.00 -6.90 0.00 21.69 _____ Segment Leq : 35.88 dBA Total Leq All Segments: 39.99 dBA Results segment # 1: Way Freight (night) LOCOMOTIVE (0.00 + -20.04 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq - - - - - - - - - - --90 90 0.50 0.00 -11.98 -1.17 0.00 -6.90 0.00 -20.04 -----WHEEL (0.00 + -21.07 + 0.00) = 0.00 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -12.82 -1.35 0.00 -6.90 0.00 -21.07 _____ Segment Leq : 0.00 dBA Results segment # 2: Passanger (night) LOCOMOTIVE (0.00 + -20.04 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.50 0.00 -11.98 -1.17 0.00 -6.90 0.00 -20.04 -----WHEEL (0.00 + -21.07 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -12.82 -1.35 0.00 -6.90 0.00 -21.07 _____ Segment Leq : 0.00 dBA Total Leq All Segments: 0.00 dBA * TOTAL Leq FROM ALL SOURCES (DAY): 39.99 (NIGHT): 0.00

.

STAMSON 5.0 NORMAL REPORT Date: 31-03-2022 12:49:20 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT Time Period: Day/Night 16/8 hours Filename: Description: OLA Daytime Unattenuated 5 house @ 20% 100m Rail data, segment # 1: Way Freight (day/night) -----Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld 1 ! 3.0/0.0 ! 24.0 ! 4.0 ! 25.0 !Diesel! Yes 1. Data for Segment # 1: Way Freight (day/night) Angle1Angle2: -90.00 deg90.00 degWood depth: 0(No woods.No of house rows: 5 / 5House density: 20 %Surface: 1(Absorptive) (No woods.) (Absorptive ground surface) Receiver source distance : 100.00 / 100.00 m Receiver height : 1.50 / 4.50 m Topography : 1 (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Rail data, segment # 2: Passanger (day/night) ------Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld ----+----+----+-----+-----1. ! 4.0/0.0 ! 24.0 ! 2.0 ! 10.0 !Diesel! Yes Data for Segment # 2: Passanger (day/night) Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth:0No of house rows:5 / 5House density:20 %Surface:1 (No woods.) (Absorptive ground surface) Receiver source distance : 100.00 / 100.00 m Receiver height:1.50 / 4.50 mTopography:1 Topography (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Results segment # 1: Way Freight (day) -----LOCOMOTIVE (0.00 + 37.30 + 0.00) = 37.30 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.58 58.59 -13.06 -1.33 0.00 -6.90 0.00 37.30 _____ WHEEL (0.00 + 23.89 + 0.00) = 23.89 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 45.93 -13.68 -1.46 0.00 -6.90 0.00 23.89 Segment Leq : 37.49 dBA Results segment # 2: Passanger (day)

LOCOMOTIVE (0.00 + 35.35 + 0.00) = 35.35 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.58 56.64 -13.06 -1.33 0.00 -6.90 0.00 35.35 _____ WHEEL (0.00 + 21.31 + 0.00) = 21.31 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 43.34 -13.68 -1.46 0.00 -6.90 0.00 21.31 _____ Segment Leq : 35.52 dBA Total Leq All Segments: 39.63 dBA Results segment # 1: Way Freight (night) LOCOMOTIVE (0.00 + -20.38 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.50 0.00 -12.32 -1.17 0.00 -6.90 0.00 -20.38 -----WHEEL (0.00 + -21.44 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -13.18 -1.35 0.00 -6.90 0.00 -21.44 _____ Segment Leq : 0.00 dBA Results segment # 2: Passanger (night) LOCOMOTIVE (0.00 + -20.38 + 0.00) = 0.00 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.50 0.00 -12.32 -1.17 0.00 -6.90 0.00 -20.38 -----WHEEL (0.00 + -21.44 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -13.18 -1.35 0.00 -6.90 0.00 -21.44 _____ Segment Leq : 0.00 dBA Total Leq All Segments: 0.00 dBA * TOTAL Leq FROM ALL SOURCES (DAY): 39.63 (NIGHT): 0.00

-

STAMSON 5.0 NORMAL REPORT Date: 31-03-2022 10:30:58 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT Time Period: Day/Night 16/8 hours Filename: Description: OLA Daytime Unattenuated 5 house @ 20% Rail data, segment # 1: Way Freight (day/night) -----Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld 1 ! 3.0/0.0 ! 24.0 ! 4.0 ! 25.0 !Diesel! Yes 1. Data for Segment # 1: Way Freight (day/night) Angle1Angle2: -90.00 deg90.00 degWood depth: 0(No woods.No of house rows: 5 / 5House density: 20 %Surface: 1(Absorptiv) (No woods.) (Absorptive ground surface) Receiver source distance : 131.18 / 131.18 m Receiver height : 1.50 / 4.50 m Topography : 1 (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Rail data, segment # 2: Passanger (day/night) ------Train! Trains! Speed !# loc !# Cars! Eng !ContType!!(km/h) !/Train!/Train! type !weld --+---+----+----+----+-----+-----1. ! 4.0/0.0 ! 24.0 ! 2.0 ! 10.0 !Diesel! Yes Data for Segment # 2: Passanger (day/night) Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth:0No of house rows:5 / 5House density:20 %Surface:1 Wood depth (No woods.) (Absorptive ground surface) Receiver source distance : 131.18 / 131.18 m Receiver height:1.50 / 4.50 mTopography:1(Flat Topography (Flat/gentle slope; no barrier) No Whistle Reference angle : 0.00 Results segment # 1: Way Freight (day) -----LOCOMOTIVE (0.00 + 35.44 + 0.00) = 35.44 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.58 58.59 -14.93 -1.33 0.00 -6.89 0.00 35.44 _____ WHEEL (0.00 + 21.94 + 0.00) = 21.94 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 45.93 -15.63 -1.46 0.00 -6.89 0.00 21.94 Segment Leq : 35.63 dBA Results segment # 2: Passanger (day)

LOCOMOTIVE (0.00 + 33.49 + 0.00) = 33.49 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.58 56.64 -14.93 -1.33 0.00 -6.89 0.00 33.49 _____ WHEEL (0.00 + 19.36 + 0.00) = 19.36 dBA Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.66 43.34 -15.63 -1.46 0.00 -6.89 0.00 19.36 _____ Segment Leq : 33.65 dBA Total Leq All Segments: 37.76 dBA Results segment # 1: Way Freight (night) LOCOMOTIVE (0.00 + -22.14 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.50 0.00 -14.08 -1.17 0.00 -6.89 0.00 -22.14 _____ WHEEL (0.00 + -23.31 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -15.07 -1.35 0.00 -6.89 0.00 -23.31 _____ Segment Leq : 0.00 dBA Results segment # 2: Passanger (night) LOCOMOTIVE (0.00 + -22.14 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.50 0.00 -14.08 -1.17 0.00 -6.89 0.00 -22.14 -----WHEEL (0.00 + -23.31 + 0.00) = 0.00 dBAAngle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq _____ -90 90 0.60 0.00 -15.07 -1.35 0.00 -6.89 0.00 -23.31 _____ Segment Leq : 0.00 dBA Total Leq All Segments: 0.00 dBA * TOTAL Leq FROM ALL SOURCES (DAY): 37.76 (NIGHT): 0.00

-